


Appendix B

Final Preliminary Design Report

**FINAL DESIGN REPORT
FOR THE
PRELIMINARY DESIGN
OF
MAIN STREET MULTI-MODAL ACCESS AND
REVITALIZATION PROJECT**

(CARS SHARING MAIN STREET)



NYS DOT P.I.N 5822.12
FTA No. NY-03-0428



PREPARED BY

DIDONATO ASSOCIATES, ENGINEERING, ARCHITECTURE, P.C.



IN CONJUNCTION WITH:

**URS CORPORATION
FOIT-ALBERT ASSOCIATES
MATHEWS NIELSEN LANDSCAPE ARCHITECTS, P.C.**

AUGUST 24, 2006

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

ABBREVIATIONS

	<u>Page No.</u>
SECTION 1 - EXECUTIVE SUMMARY	
1.1 Background.....	1-1
1.2 Purpose.....	1-1
1.3 Design Options Considered.....	1-3
1.4 Methodology.....	1-3
1.5 Summary.....	1-3
1.5.1 Roadway Design Elements.....	1-3
1.5.2 Traffic Modeling.....	1-4
1.5.3 Light Rail System Improvements.....	1-5
1.5.4 Urban Design Elements.....	1-6
1.5.5 Construction Phasing.....	1-6
1.5.6 Project Costs.....	1-7
SECTION 2 – ROADWAY GEOMETRY	
2.1 Lane Configurations, Widths and Alignment.....	2-1
2.2 Intersections.....	2-3
2.3 Roadside Elements.....	2-4
2.4 Bicycles.....	2-5
2.5 Pedestrian Crossings.....	2-6
2.6 Right-of-Way.....	2-6
2.7 Summary.....	2-7
SECTION 3 – TRAFFIC ENGINEERING AND SIGNALIZATION	
3.1 Forecasting.....	3-1
3.2 Signal Timing and Operation.....	3-3
3.3 LRRT Operations.....	3-5
3.4 Parking and Loading Zones.....	3-5
3.5 Traffic Modeling and Analysis.....	3-6
3.6 LRRT Station Locations.....	3-10
3.7 Safety Recommendations.....	3-11
3.8 Summary.....	3-12
SECTION 4 – TRACKBED, RAIL ELEMENTS AND PAVEMENT	
4.1 Existing Conditions.....	4-1
4.2 Rail Components.....	4-2
4.3 Pavement.....	4-4
4.4 Crossovers.....	4-5
4.5 Overhead Catenary System.....	4-6
4.6 Utilities.....	4-7
4.7 Drainage.....	4-7
4.8 Train Control.....	4-8
4.9 Summary.....	4-10
SECTION 5 – STATION REHABILITATION AND LOCATION	
5.1 Architecture.....	5-1
5.2 Boarding Area.....	5-2
5.3 Weather Protection.....	5-2
5.4 Accessibility.....	5-2

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

5.5 Equipment and Furnishings.....	5-3
5.6 Station Locations	5-4
5.7 Communications, Power and Monitoring.....	5-5
5.8 Summary.....	5-9

SECTION 6 – ACCESSIBILITY/ADA COMPLIANCE

6.1 Sidewalks.....	6-1
6.2 Crosswalks.....	6-1
6.3 Station Areas.....	6-1
6.4 Parking.....	6-1
6.5 Summary.....	6-1

SECTION 7 – SIDEWALKS, STREETScape AND URBAN DESIGN

7.1 Existing Conditions.....	7-1
7.2 Districts and Street Typologies.....	7-1
7.2.1 Station Areas.....	7-2
7.2.2 Parking Areas.....	7-4
7.2.3 Intersections.....	7-5
7.2.4 Unique Spatial Conditions.....	7-5
7.3 Sidewalks & Materials.....	7-5
7.4 Pedestrian Amenities.....	7-6
7.5 Landscaping.....	7-6
7.6 Light Fixtures.....	7-7
7.7 Events Spaces.....	7-7
7.8 Artwork.....	7-7
7.9 Encroachments.....	7-8
7.10 Utilities.....	7-8
7.11 Drainage.....	7-10
7.12 Special Wind Conditions.....	7-10
7.13 Feature Removals.....	7-11
7.14 Heated Sidewalks.....	7-11
7.15 Summary.....	7-11

SECTION 8 – SAFETY AND SECURITY MEASURES

8.1 Lighting.....	8-1
8.2 Monitoring.....	8-1
8.3 Special Conditions.....	8-1
8.3.1 Portal Entrance.....	8-1
8.3.2 HSBC Underpass.....	8-2
8.3.3 LRV Modifications.....	8-2
8.4 Summary.....	8-2

SECTION 9 – CONSTRUCTION PHASING

9.1 General Approach.....	9-1
9.2 LRRT Operations.....	9-2
9.3 Work Hours and Duration.....	9-2
9.4 Schedule.....	9-3
9.5 Summary.....	9-3

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

SECTION 10 – COST ESTIMATING

10.1 Cost Analysis.....	10-1
10.2 Phasing Considerations.....	10-2
10.3 Funding.....	10-2
10.4 Summary.....	10-2

SECTION 11 – ADDITIONAL CONSIDERATIONS

11.1 Maintenance Jurisdiction.....	11-1
11.2 Snow Removal.....	11-1
11.3 Vault Abandonments.....	11-1
11.4 Environmental Assessment.....	11-1
11.5 Public Input.....	11-1
11.6 Coordination with Other Projects.....	11-2

APPENDICES

Appendix A	Exhibits – Road and Trackbed Plans, Profiles, Sections & Details
Appendix B	Exhibits – Station Concept Plans, Elevations & Details
Appendix C	Exhibits – Streetscape Concept Plans & Details
Appendix D	Traffic Engineering and Analysis Data
Appendix E	Construction Cost Estimates
Appendix F	Reference Standards
Appendix G	Public Information Meeting Comment Summary & Responses
Appendix H	Catenary Pole Study
Appendix I	Safety and Security Measures
Appendix J	APTA Peer Review

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

ABBREVIATIONS

AASHTO	American Association of State Highway and Transportation Officials
AC	Advisory Committee
ADA	Americans with Disability Act
AFC	Automatic Fare Collection
ANSI	American National Standard Institute
APTA	American Public Transportation Association
AREMA	American Railway Engineering and Maintenance Association
BP	Buffalo Place
CCTV	Closed Circuit TeleVision
COB	City of Buffalo
CS	Combined Sewer
DLP	Digital Light Projection
EA	Environmental Assessment
ECH	Erie Canal Harbor
EPA	Environmental Protection Agency
EPM	Environmental Procedures Manual
FHWA	Federal Highway Administration
FTA	Federal Transit Administration
FT	Feet
Ft.-C	Foot Candle
GBNRTC	Greater Buffalo Niagara Transportation Council
HDM	Highway Design manual
HSBC	Hongkong Shanghai Bank Corporation
IEEE	Institute of Electric and Electronics Engineers
IN	Inches
ITE	Institute of Transportation Engineers
K	Thousand
LED	Light Emitting Diode
LOS	Level of Service
LRRT	Light Rail Rapid Transit
LRV	Light Rail Vehicle
M	Million
MOE	Measures of Effectiveness
MPH	Miles Per Hour
MAS	Maximum Authorized Speed
Mhz	Mega hertz
MUTCD	Manual of Uniform Traffic Control Devices
NEPA	National Environmental Policy Act
NFTA	Niagara Frontier Transportation Authority
NIMO	Niagara Mohawk
NYS	New York State
NYSDOT	New York State Department of Transportation
NYSDEC	New York State Department of Environmental Conservation
NITTEC	Niagara International Transportation Technology Coalition
NYCRR	New York Code of Rules and Regulations
OCC	Operations Control Center
OCS	Overhead Catenary System
PA	Public Announcement

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

PACE	Passenger Assistance Communication Equipment
PIDS	Public Information Displays
RTOR	Right Turn on Red
ROW	Right-Of-Way
RTU	Remote Terminal Units
SCADA	Supervisory Control Data Acquisition
SEQRA	New York State Environmental Quality Review Act
SF	Square Feet
TC	Train Control
TCC	Train Control Communication
TCS	Train Control System
TP	Traction Power
TSP	Transit Signal Priority
VDU	Video Display Units
VISSIM	Visual Simulation

SECTION 1 – EXECUTIVE SUMMARY

1.1 Background

Vehicular traffic was permitted on Main Street prior to being converted to a light rail rapid transit corridor with a shared pedestrian mall in the 1980's. Deteriorating economic conditions since the conversion have generated a movement to reintroduce vehicular traffic to Main Street. As such, the concept of returning vehicular traffic to Main Street has been studied for several years beginning with a feasibility study completed in 1998 by Erdman Anthony through the Environmental Assessment (EA) sponsored by the City of Buffalo, the Niagara Frontier Transportation Authority (NFTA), Erie County, the New York State Department of Transportation, and Buffalo Place. The Federal Transit Administration (FTA) is currently reviewing the final draft EA. Several options for improvements to Main Street were evaluated in the EA with the recommended option being the "*Share the Trackbed Alternative*". This involves the sharing of the travel lanes by vehicular and light rail traffic within the existing trackbed.

The scope of this project is to advance the "preferred alternative" to a preliminary design level. The preliminary design effort is being sponsored by the City of Buffalo in conjunction with the NFTA and Buffalo Place. The Design Team for the project is headed by DiDonato Associates, Engineering and Architecture, PC and includes URS Corporation, Foit-Albert Associates and Mathews Nielsen Landscape Architects. The Technical Committee responsible for the decision making process is comprised of members of the Client Team, Design Team, NYSDOT and the Greater Buffalo-Niagara Regional Transportation Council (GBNRTC). An Advisory Committee has been appointed by the Mayor of Buffalo to insure community involvement and help refine the scope and decision making process for the project.

1.2 Purpose

The primary objective of the project is to reopen Main Street to two-way vehicular traffic from Scott Street to Goodell Street through the implementation of the preferred alternative identified under the Environmental Assessment (EA), the "*Share the Trackbed Alternative*", (see Exhibit 1-Project Location Map). The proposed alternative will meet the needs and the revitalization objective outlined in the EA and help achieve the following:

- Increase Multi-Modal access options and Light Rail Rapid Transit ridership
- Simplify access to downtown
- Encourage public/private economic development
- Increase business visibility
- Provide vehicular access to adjacent land use
- Provide short-term parking
- Enhance aesthetics
- Provide a public friendly environment

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

1.3 Design Options Considered

The overall project scope calls for the implementation of the “*Share the Trackbed Alternative*” recommended in the EA. As such, options to be considered for the project are related more to construction materials and streetscape elements than related to geometric and layout options. Trackbed rehabilitation, turn lanes, catenary pole relocations, curb alignment and station relocations are among the elements considered and discussed in the various sections of the report. Prioritizing the various scope elements considered in order to develop a fundable project was a key part in evaluating the various options.

1.4 Methodology

The goal of the preliminary design effort for the project is to establish concepts and design criteria that form the basis for the final design and construction for the entire project corridor. A primary component of the preliminary design is to evaluate projected vehicular traffic conditions and incorporate recommendations to insure that the vehicular, light rail and pedestrian traffic can coexist without sacrificing safety and not have a significant adverse impact on light rail operations. Streetscape improvements and design of intersections will play a key role in developing a safe and attractive environment for pedestrians. Redesign and placement of the LRRT stations is an important component, as well as the enhancement of visibility to properties while meeting the needs of transit accessibility and optimizing safety along the corridor. Establishing material selection criteria is essential for long-term durability and maintenance considerations. Developing estimates for the overall construction and determining the impacts of phasing on properties along the corridor and LRRT operations along with the establishment of funding will be key in determining the optimal approach to construction.

1.5 Summary

The initial overall project scope elements considered for the project were defined and summarized in the Scope Summary Memorandum. The determination of scope elements were based on preliminary studies, including the EA, as well as the early stages of the preliminary design with input from the Client Group, Technical Committee and the Advisory Committee. As part of the preliminary design effort to further shape the project scope, construction cost estimates have been developed for each of the scope elements to establish an overall project estimate. Based on the costs developed, direction was given to evaluate alternatives for minimizing work that is not essential to the primary project objective of opening Main Street to cars. The primary scope modifications considered are related to reducing work within the actual trackbed. Further discussion is contained in the following sections.

1.5.1 Roadway Design Elements

Implementation of the “Sharing the Trackbed” concept inherently imposes certain constraints on the geometric design options within the shared trackbed segments. A single travel lane in each direction will be shared by cars and light rail vehicles (LRV’s). A 15-mile per hour speed limit will be

established for the entire project corridor to maximize safety. The existing roadway/trackbed vertical alignment will be maintained, as the rail alignment will remain unchanged. The curb lines and station platforms in train boarding areas are currently located to properly interface with the train. The existence of the catenary poles to support the overhead wires create constraints or pinch points and fixed object hazards for vehicular traffic. As such, the decision was made to retain the existing curb alignment as well as to relocate the catenary poles, located between the inbound and outbound tracks and install new poles outside the trackbed to maximize the lane widths while maintaining the existing curb train interfaces for train boarding operations. The existing cantilevered, mini-high platforms at the stations currently project into the trackbed, which also creates a fixed object. Increasing the station platform offset to 2 feet and installing automated bridge plates mounted to the platforms will adequately address this clearance concern. Parking lanes are proposed along the shared trackbed sections, which are 9 feet in width and include a 3-foot wide buffer zone to the travel lanes.

Geometrically adequate lane transitions are proposed around the portal entrance to the subsurface rail section. The section between Goodell Street and Tupper Street will have two travel lanes, one in each direction, a center median and dedicated left turn lanes at the intersections. Dedicated bike lanes are proposed for bike access from the north project limit at Goodell Street to a future bike route on Pearl Street. The bike lanes will be constructed between Chippewa Street and the portal and from Tupper Street to Goodell Street. A wider travel lane around the portal will function as a shared vehicular and bike lane. Delineation of bike access along Chippewa Street will be performed to interface with the future Pearl Street improvements.

The connection of Eagle Street and Mohawk Street to Main Street is currently included in the project scope. This will be re-evaluated in the final design phases to determine if cost or operational considerations would require their elimination from the project. Each road segment would consist of a single travel lane in each direction and parking lanes. Eagle Street would extend from Washington Street to Main Street while Mohawk Street would extend from Washington Street to Pearl Street.

1.5.2 Traffic Modeling

Traffic modeling has been performed, which determined that the reintroduction of cars to Main Street could be accommodated without significant, negative impact to LRRT operations. The traffic analysis shows that the vehicular traffic and the train traffic can operate simultaneously with acceptable intersection level of service and with minimal delays to the train operations, less than one minute during peak hours in each direction. Analysis of the entire corridor shows that dedicated right turn lanes are not required provided that right turns on red are permitted. Also, the model shows that left turns can be made from the shared lane though certain intersections such as Church Street will require additional measures to insure safe conditions for vehicular and pedestrian traffic. New signals and controllers will be required at each intersection to accommodate the new traffic conditions. Additional

cameras supported by the NFTA CCTV system are recommended for monitoring of traffic conditions. Supplemental measures are required to properly delineate the unique conditions that will exist at the portal interface.

1.5.3 Light Rail System Improvements

While the primary objective is to return two-way car traffic to Main Street, it is important for the LRRT system to continue to operate safely and efficiently. Traffic modeling has demonstrated that the shared trackbed concept could be implemented without significant adverse impact to train operations. Elements of the LRRT system that have been evaluated in the preliminary design include trackbed and rail components, overhead catenary system, train control system, signalization, wayside systems including communications, power, surveillance, emergency notification and utilities which share NFTA duct banks. Trackbed sections along the project corridor that are in poor condition will be rehabilitated as required.

Drainage of the trackbed is a significant factor that contributes to deteriorated trackbed areas, therefore, subsurface drainage is proposed adjacent to the existing curb just outside the trackbed to provide for some surface drainage. The existing curb will remain and will be cut flush to the pavement in parking areas.

The train traction power system consists of an overhead electrification system supported by poles located in the center of the trackbed. Sectionalizing switches within the trackbed as well as power feeds running through conduit under the trackbed control the power to the system. Removal of the catenary poles and switch components from the trackbed as mentioned under Section 1.5.1 is important to the lane configurations as well as to maximize accessibility under emergency conditions. New poles will be installed outside of the trackbed that would support cross-span wires and would support the electrification system. The poles would be installed at setbacks similar to the existing light poles and would serve a dual purpose as light poles. The catenary pole spacing of approximately 130 feet would not inhibit fire and emergency service access.

Adjustment to the station platform locations is required to provide adequate queue length in advance of intersections as well as to prevent backup of vehicles into preceding intersections. Combining the Theatre and Fountain Plaza Stations into one location between Huron and Chippewa Streets will accommodate the lane transitions around the portal as well as the anticipated traffic conditions. A station platform setback of 2 feet from the curb is important to comply with clear zone provisions. Accessibility to trains will be maintained from the platforms through the use of automated bridge plates that will interface with the train control system. The stations will be uniform in size and will be significantly smaller than the existing stations. The stations will include transparent wall panels to provide weather protection, to reduce viewing impact on building fronts and will be constructed of weather resistant materials to reduce long- term maintenance costs.

LRRT system components associated with the stations include Closed Circuit Television Vision (CCTV), Passenger Assistance Communication Equipment (PACE), Public Announcement (PA) system, Automatic Fare Collection (AFC), Passenger Information Displays (PIDS), and Train Control Communication (TCC). All of the components will be relocated or replaced and incorporated into the stations structures. Intersection traffic controllers will be replaced and will continue to interface with the train control system. Additional CCTV cameras will be installed to monitor intersections utilizing the existing NFTA cable infrastructure.

1.5.4 Urban Design Elements

A significant part of the project design effort is to develop an enhanced streetscape that will compliment the improved access to the area. Streetscape design includes strategic layout of short-term parking (over 250 spaces currently proposed, including proposed parking along Eagle and Mohawk Streets) and loading zones, effective use of station zones, establishing adequate pedestrian travel routes and integration of public spaces. Enhancements proposed include new sidewalk surfaces, enhanced crosswalks, improved lighting, new sustainable landscaping, seating, street furnishings, power outlets, removal of obsolete or conflicting features, new transparent screening for the portal, medians from the portal to Goodell Street and wind screening elements in localized problem areas. Additional considerations that will be evaluated further include the installation of drip irrigation systems, heated sidewalks (individually funded), artwork, display boards and informational signage. The preliminary design effort for the streetscape design has focused on the three blocks at the north end of the project, which is currently planned as the first construction phase. These blocks are generally representative of the conditions anticipated throughout the project corridor. Further design of the remaining blocks are reserved until the detailed design phases.

A key issue sponsored by the Advisory Committee is the utilization of parking within station boarding areas. Currently the NFTA operates with 2-car trains on a normal basis with a limited number of 3-car trains during peak hour operations. Four car trains are used during special events such as hockey games. NFTA has resolved that they will continue to utilize 4-car trains during special events in lieu of modifying train frequency. The Advisory Committee requested and the COB has agreed to implement provisions for parking in the third and the fourth car zone through the use of a traversable curb during the hours when the three and four cars are not in operation by the NFTA. A number of operational and safety concerns will be evaluated further as part of the final design effort before considering implementation of parking within these zones.

1.5.5 Construction Phasing

The COB has conveyed that the intent is to generally construct the project in a north to south direction with three distinct phasing segments determined to date. However, the timing of potential development near the foot of Main Street must be factored as well. The pending development projects directly

impact the timing of the segment between Scott Street and Exchange Street. Therefore, an initial phasing approach has been established as follows:

- Phase 1A – Goodell Street to Chippewa Street
- Phase 1B – Exchange Street to Scott Street
- Phase 2 – Chippewa Street to Exchange Street
- Phase 3 – Improvements South of Scott Street

Initial funding has been secured to potentially begin the construction work in 2007 for Phase 1A pending resolution of the EA. Similarly, funding for phase 1B has also been secured for the lower Main Street. Officials from the Erie Canal Harbor Development Corporation have conveyed that the timing of the proposed development at lower Main Street may require that Phase 1B be completed in 2008. No definitive time frame or sub-phasing has been established for the remaining segments at this point and further co-ordination will be required between the various agencies (involved in the developments) prior to setting the final phasing of construction.

A key element for staging of construction operations is, to structure the phasing so that all work to be performed within a given block is completed in one construction season. Noise restrictions within residential and hotel areas, maintenance of LRRT systems, maintenance of pedestrian traffic, and maintenance of access to businesses will also be considered.

1.5.6 Project Costs

The process of evaluating the various scope considerations included the development of construction cost estimates and impact on the overall cost of the project. The cost estimates were developed in 2006 construction dollars and are based on available data published by the NYSDOT as well as recent construction bid data from area projects of similar work elements. Design contingencies have been applied to each of the work elements to account for unknowns that will not be determined until the completion of the final design. A 15 percent contingency was used for the project as a whole with additional contingencies applied to certain items that have a greater potential for variation in cost. Estimates were then categorized under major work elements and divided into one-block segments in order to provide a means of evaluation for different phasing scenarios. Though a fixed budget was not established for the project, the EA listed an estimated cost of \$53 million for the “Shared Trackbed” concept in 2003 dollars. A recent update to the EA projected the costs to \$75 million, which was escalated to 2008 dollars and included the addition of the Church Street crossover, a new crossover south of Scott Street and the catenary pole relocation work. Subsequent to the EA cost update, direction was given to the design team from the COB to alter the scope as necessary to get the project scope more in line with the initial EA cost projections in order to be more fundable.

As such, estimates have been developed for each of the trackbed work alternatives. The lowest construction cost option is the minimal trackbed repair approach at just under \$51 million (approximately \$ 61 million total project cost), which is based on all work being completed by the end of 2009.

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

funding has been secured for Phase IA and IB. The rehabilitation (resurfacing) and reconstruction approaches would cost an additional \$6 million and \$16 million respectively for the same construction time period. The preferred approach recommended by the COB and Advisory Committee is the minimal trackbed work approach, which includes moving the catenary poles outside of the trackbed but does not include the Church Street crossover. This approach accomplishes the objective of returning vehicle traffic to Main Street in a cost effective manner.

SECTION 2 – ROADWAY GEOMETRY

Implementation of the preferred shared trackbed alternative, poses a unique challenge of creating lanes that will accommodate varied transportation modes consisting of light rail vehicles, cars, emergency vehicles and bicycles as well as pedestrians. Lane widths and configurations must be coordinated with the positioning of rail stations and loading areas as well as the catenary pole system. The curb location in the vicinity of stations is of particular concern in order to insure that adequate vehicular clearance is provided around the stations as well as maintaining the proper interface between the stations and rail cars. Turn lane size and configurations will be established as part of the traffic analysis. Other important geometry related issues include the transition and delineation of the vehicular lanes around the portal, crosswalk configurations, bike access at stations, turning radii at intersections to accommodate the selected design vehicle, maximizing the number of parallel parking spaces, providing for loading zones, clearing of obstacles to maximize sight distance and the protection of potential roadside hazards.

2.1 Lane Configurations, Widths and Alignment

This project will be designed in accordance with the requirements of the City of Buffalo *Standards and Specifications*, the New York State Department of Transportation (NYSDOT) *Highway Design Manual (HDM)*, *Environmental Procedures Manual (EPM)*, and *A Policy on Geometric Design of Highways and Streets, 2004 (AASHTO)*, for a functional classification of Urban Street. The project segment between Scott Street at the south limit and Goodell Street at the north limit will be designed as a two lane local urban street. A 15 mph speed limit will be established for the entire project corridor.

Trackbed Segments

The existing trackbed section is 23.5 feet wide and is currently used by Light Rail Vehicles (LRV's), emergency vehicles and delivery type vehicles with permits. The proposed shared trackbed segment between Scott Street and the end of the Light Rail Rapid Transit (LRRT) surface section at the portal entrance to the subsurface section of the LRRT system, just south of Tupper Street, will consist of two (2) 11.75 feet travel lanes for passenger vehicles with no curb offset. The lane widths are dictated in the LRRT station blocks by the train boarding interface requirement that are discussed further in Section 5. The 11.75 feet lane widths are maintained in the non-station blocks for consistency. Relocation of the Overhead Catenary System (OCS) poles outside of the roadway is necessary in order to utilize the full lane widths as discussed in Section 4. The station boarding areas and platforms are prohibitive in allowing space for a shared or dedicated bike lane. A 9 foot-wide parking lane and 3-foot wide buffer zone is proposed for each side of the trackbed in non-station areas. Consolidation of the Theatre and Fountain Plaza Stations provide the opportunity to incorporate a 5-foot wide bike lane from Chippewa Street to the portal area.

The horizontal alignment of the trackbed is generally straight with three deflections within the surface section. One deflection of approximately 0°10.5' is located near Seneca Street at approximately Sta.53+50. The other two deflections of approximately 0°28' and 0°17' are located north of Chippewa Street at approximately Sta.91+00 & Sta.94+00 respectively. The vertical alignment is generally uniform in nature ranging from 0.25% to 1% through most

of the corridor with the exception of the lower portion of Main Street between Scott Street and Seneca Street and in the portal area. The longitudinal grade varies from 0.66% to 5.91% in the lower Main Street segment with the steepest grade just north of Exchange Street at HSBC Tower. The slope into the portal is approximately 6%. No changes to the horizontal or vertical alignments are proposed. The pavement surface condition at intersection approaches will be evaluated further in final design in areas where the grades exceed 5 percent.

Designated right turn lanes were initially considered on the Main Street approaches for each of the intersections. However, installing turn lanes nearly doubles the pedestrian crossing distance for the standard trackbed width. Also, maintaining narrow widths at intersections produces a beneficial calming effect on vehicular traffic, which is important for maintaining a low speed corridor as well as enhancing safety. No significant delays were observed in the traffic modeling for Main Street and its intersections due to the elimination of the dedicated right turn lanes (with permitted right turn on red). Traffic modeling was performed for inclusion and exclusion of right turn lanes and is discussed further under Section 3. Exclusive left turn lanes were not considered for this project for safety concerns over moving traffic in and out of the shared lane as well as the additional widening that would be required on the opposite side of the intersections.

Non-Trackbed Segments

A transition is required between the shared trackbed segments at the portal to the non-trackbed segments north of the portal. The distance over which the shifts shall occur is based on Table 262-2 from the 17 NYCRR also known as the New York State's *Manual of Uniform Traffic Control Devices* (MUTCD) for a design speed of 20 mph. It is desirable to minimize the transition distance for several reasons, which include minimizing of impact on existing properties, traffic calming benefits of having to maintain lower speeds to maneuver, and visual clarity in having an abrupt shift versus long transitions. Proper signage and delineation as well as physical measures to prevent vehicles from entering the portal are essential to the lane shift designs. The start of the shift is approximately two train car lengths south of the portal, which was selected to prevent a typical size train stopped at the portal from blocking northbound cars transitioning around the portal.

The section between portal and Tupper Street will consist of one (1) 14 feet wide travel lane on each side of the portal walls and 8-foot wide parking lanes. The travel lanes are adequate in size to accommodate bikes. A slight alignment shift across the Tupper Street intersection is required to align with the travel lanes between Tupper Street and Goodell Street. The travel lanes between Tupper Street and Goodell Street are proposed to be 11 feet in width separated by a 10-foot wide median. A raised, landscaped median is proposed for each end of the block to form a transition into dedicated left turn slots. A 5-foot wide bike lane and an 8-foot wide parking lane are proposed along each side for this block. No changes are proposed to horizontal and vertical alignments for the segment between the portal and Goodell Street.

The connection of Eagle Street and Mohawk Street to Main Street is currently included in the overall project scope. Each road segment would consist of (2)

12-foot wide travel lanes and 8-foot wide parking lanes. Eagle would extend from Washington Street to Main Street but not connect to Pearl Street due to the existence of the Main Place Mall. Mohawk would extend from Washington Street to Pearl Street. This option however will be re-evaluated in the final design phases of the project should cost or operational considerations require elimination from the project.

The overall Plans, Profiles and Typical Section drawings showing all geometric components, including parking and station layouts are shown in Appendix A of this report.

2.2 Intersections

There are a total of 11 existing side streets that intersect with Main Street within the project limits. Eagle Street and Mohawk Street right-of-way is connected with the Main Street right-of-way with no physical connection or crossing of the roadways. Both Eagle Street and Mohawk Street connections to Main Street are being considered under this project. A majority of the side streets intersect Main Street at right angles with a few exceptions. The intersection angles are as follows:

Side Street	Intersecting Angle
1. Scott Street/Marine Drive	70.6°±
2. Exchange Street (East & West)	90°±
3. Seneca Street (East & West)	90°±
4. Swan Street (East & West)	90°±
5. Cathedral Park	90°±
6. South Division/Church Street	80°±
6. North Division/Church Street	83°±
7. Eagle Street	90°±
8. Clinton/Court Street	56°±
8. Broadway/Court Street	53°±
9. Mohawk Street (East & West)	90°±
10. Huron Street (East & West)	90°±
11. Chippewa Street (East & West)	90°±
12. Tupper Street (East & West)	90°±
13. Goodell/Pearl Street (East & West)	68°±

Traffic calming is a key element of the design for this project, as the mixing of vehicular traffic with LRRT vehicles requires special safety considerations. The LRRT's currently travel at speed limits of 15 mph during normal operating hours. Therefore, a 15 mph speed limit for vehicular traffic will be established throughout the project corridor. Narrowing of intersection widths is a proven traffic calming measure. Limiting the size of corner radii to the minimum required for a typical passenger vehicle using Main Street will help limit the size of vehicles attempting to use Main Street as well as minimize the crossing distance for pedestrians. A corner radius of 15 feet at a typical 90-degree intersection will accommodate passenger vehicles. Weight limits will be imposed to restrict the largest vehicles using Main Street to single unit type trucks (3 tons maximum).

2.3 Roadside Elements

Overhead Catenary System & Station Platforms

The existing overhead catenary system for the LRRT is supported by poles located in the center of the trackbed. As such, the poles create a fixed object hazard for vehicular traffic. The existing raised platforms at the LRRT stations extend approximately 6-inches into the trackbed along the curb line to meet the accessibility requirements for the light rail vehicles (LRV's). The cantilevered platforms are a fixed object hazard as they violate the City of Buffalo standard curb offset requirement of 2 feet. Both conditions will be addressed through design measures. The poles will be relocated outside of the roadway on each side with the catenary wires being supported by cross span wires. The poles will be moved to an offset on average of 18 feet from the existing curb line, except where it is possible to move closer at intersections. Movable bridge plates mounted to the raised station platforms are proposed to fill the gap between the rail car doors and the platforms.

Additional information regarding the Overhead Catenary System (OCS) is discussed in Section 4 and the Station Platforms and Bridge Plates are discussed in Section 5 of this report.

Portal Walls

The LRRT system is comprised of the surface segment of rail track's between Scott Street and Tupper Street and the subsurface segment of the rail track's between Tupper Street and the LRRT north terminus at University Station. Cars will share the trackbed between Scott Street and the portal south of the Tupper Street intersection. Approximately 600 feet south of the Tupper Street intersection, the rail tracks and the vehicular travel lanes will separate. The 42-inch high portal walls at the entrance to the subsurface segment of the LRRT system create a barrier separation from northbound and southbound vehicular travel lanes. A 2-foot minimum curb offset is proposed between the vehicular travel lanes and the portal wall to conform to the minimum offset for fixed objects. Replacement of the fencing extending above the portal walls is discussed further under section 7 of this report.

Signs & Traffic Signal Poles

The traffic and other informational signs will be located outside of the 2 foot clear zone as required by the City of Buffalo standards. Traffic signal poles will be located at all signalized intersections. The interface of the signal heads and overhead catenary wires must be carefully coordinated as clearances to the wires must be maintained while the signal heads must be properly aligned with the travel lanes. Additional signals and gates will be required at the portal area.

Lighting

The street light poles will generally be located within the sidewalk area and will be outside of the required minimum clear zone. Light fixtures for street and sidewalk lighting are proposed to be mounted on the new catenary support poles

in the sidewalk areas as discussed in Section 4. Additional light poles will be required for sidewalk areas as needed to enhance security and to provide adequate lighting of the sidewalks during the night. The AASHTO guidelines require that the minimum illumination required for a local road should be 0.2 foot-candle (ft.-c) for residential use and 0.6 ft-c for commercial areas. The recommended uniformity ratio for a residential roadway is 10:1 and for commercial walkways is 4:1. The lighting requirements will be further evaluated in the final design phase to provide sufficient lighting and to minimize the shadow effects within the project corridor for vehicular and pedestrian traffic. Main Street within the corridor will be a combined residential and commercial street. Light poles located in the vicinity of the intersections will also be located at least 2 feet from the curb.

Medians

A raised median is proposed between the travel lanes near each end of the 700 block of Main Street with a flush median section between to facilitate access. This median will be 10 feet wide and will be landscaped. The section between the portal and Tupper Street will also have a landscaped median to separate the vehicular traffic.

Streetscape Amenities

Streetscape amenities will be provided along the entire Main Street corridor and will include benches, planters, and furnishings that will be developed as part of the detailed design of the project and remain out of the designated roadway clear zone. More detail regarding these amenities is provided in Section 7 of this report.

Utility Cabinets

There are aboveground utility cabinets (Green cabinets) located along Main Street in the vicinity of the LRRT stations. The cabinets primarily house train control, communications and power associated with the LRRT systems and are discussed further in Section 5.

The information drums located along the project corridor will be removed as part of this project.

Driveways

There are no driveways within the trackbed area along Main Street. The three existing driveways within the 700-block will be retained.

2.4 Bicycles

Bicycle access has been identified as a project objective. The limiting trackbed width, potential hazard presented by the track rails, position of the station mini-high platforms are among the elements that present challenges to incorporation of measures to accommodate bicycles. The current trackbed, curb to curb, width that will be maintained is 23.5 feet, resulting in 11.75 feet wide travel lanes,

which is not desirable for a shared vehicle/bike lane. Typically, 14 feet is desirable for a shared lane, with 12 feet being the minimum for experienced bicyclists. The condition is exacerbated by the existence of the track rails, which are located approximately 2 feet from the curb line. The rail is a slipping hazard for bike tires and the rail flange creates a catch point for bike tires. Further discussion on the rail is included under Section 4.

Given the roadway limitations for bicycle access, the sidewalk area was considered for a bikeway. However, as with the roadway, there are a number of safety concerns for bicycles traveling in sidewalk areas. The primary concern is with mixing bicyclists and pedestrians in an urban setting. Having an exclusive bike lane would require pedestrians to cross the lane at numerous locations including intersections and train boarding areas. Furthermore, this would result in a net reduction of the useable sidewalk width and create pinch points at LRRT stations, sidewalk cafes and encroachment areas. It would also result in limitations in the placement of various streetscape elements including seating and plantings. As such, a revised approach has been proposed that would provide a connection for bicycles from the north project limit at Goodell Street to a future bike corridor along Pearl Street.

The access through the project for the Main-Pearl connection would be through a dedicated 5-foot wide bike lane on the segment from Goodell Street to Tupper Street, a shared 14-foot wide travel lane around the portal where space is limited and a dedicated 5-foot wide bike lane on the segment from Tupper Street to Chippewa Street. Improvements along Chippewa Street and Pearl Street to accommodate bicycles would be incorporated into a separate project.

2.5 Pedestrian Crossings

Reintroducing vehicular traffic to the shared pedestrian and light rail mall increases the importance of clearly defined pedestrian crossings at locations familiar to motorists. Clearly delineated crosswalks at intersections controlled by signalization will provide the safest interface for multi-modal use of the project corridor. Signed and marked mid-block crosswalks are not used on the City of Buffalo's downtown street network. The pedestrian movements at intersections are currently controlled by traffic signals. New pedestrian signals with count down timers will be installed at the new crosswalks at all intersections. Introducing mid-block crosswalks will pose increased risk along this corridor due to the mixed-use traffic. Further discussion on cross walks is included under Section 7.

2.6 Right-of-Way

The right-of-way on Main Street is generally 99 feet with the exception of a segment near the Hyatt Hotel where it reduces to approximately 79 feet. The right-of-way generally coincides with building fronts, with the exception of encroachment areas listed under Section 7. The intersecting side street right-of-ways vary in width but similarly to Main Street, generally coincide with the building lines. The right-of-way information below is based on the record plans and tax maps and is without the benefit of a boundary survey.

Side Street	Right-of-Way Width (Ft.)
1. Scott Street (East)	Varies
1. Marine Drive (West)	49.5
2. Exchange Street (East & West)	Varies
3. Seneca Street (East & West)	66
4. Swan Street (East & West)	66
5. Cathedral Park	99
6. North & South Division Streets	361±
7. Church Street	112±
8. Eagle Street	71±
9. Clinton & Broadway Streets	249±
10. Mohawk Street (East & West)	66±
11. Huron Street (East)	Varies
11. Huron Street (West)	66±
12. Chippewa Street (East & West)	66±
13. Tupper Street (East & West)	50±
14. Goodell Street	66±
15. Pearl Street	Varies

2.7 Summary

Key decisions related to the roadway geometry recommendations for the project include maintaining the roadway/trackbed width to facilitate ground level train boarding, removing the catenary poles from the roadway/trackbed and installing new poles in the sidewalk areas, setting the station platforms and all fixed objects a minimum of 2 feet from the travel lanes to maintain proper clear zones and establishing a 15 mph speed limit for the entire project segment to maximize safety. A summary of the geometric components for the project are listed as follows:

1. Travel Lane widths:
 - Main Street:
 - =11.75 ft. (Shared trackbed segment)
 - =14 ft. (Portal to Tupper Street shared bicycle lane)
 - = 11 ft. travel, 5 ft. bicycle (Tupper to Goodell)
 - = 5 ft. bicycle lane (Chippewa Street to portal)
 - Side Streets:
 - Mohawk Street =12 feet
 - Eagle Street =12 feet
 - All other side streets to match existing lane widths
2. Parking Lane Widths:
 - 9 feet – trackbed segments; 8 Feet non-trackbed segments
 - 3 Foot buffer in shared trackbed areas
 - Stall Lengths = 22 feet
3. Design Speed = 20 mph for 15 mph speed limit
4. Lateral clearance = 2 Feet Min.
5. Design Vehicle = Passenger Car with limited number single unit trucks (3 Tons)
6. Turning Radii for Design Vehicle = 15 ft. min.

SECTION 3 – TRAFFIC ENGINEERING AND SIGNALIZATION

The reintroduction of automobile traffic onto Main Street creates a unique challenge for maintaining the schedule of light rail vehicles in this corridor. Careful coordination of the station locations, consideration of turn lanes at intersections, designated on-street parking areas, and the traffic signal system will be required for this project. The traffic engineering modeling was used to determine the interaction between all of these factors and adjustments can then be made to the design parameters.

3.1 Forecasting

Traffic Volume Development

The purpose of this section is to document the development of year 2025 traffic forecasts for Main Street. The year 2025 peak hour traffic forecasts on Main Street were based on traffic volumes reported in the *City of Buffalo Main Street Multi-Modal Access and Revitalization Project Draft Final Environmental Assessment* (August 2005). Future year traffic volumes on other downtown Buffalo streets in the vicinity of Main Street were developed by applying projected traffic growth rates to the base year (2005) peak hour turning movement volumes.

Existing Traffic Volumes

The existing condition traffic volumes were developed from peak hour traffic volumes contained in Synchro files provided by the GBNRTC. The GBNRTC provided Synchro models for both the AM and PM peak hours that cover most intersections within downtown Buffalo. The GBNRTC also provided the intersection turning movement count sheets for several downtown City of Buffalo intersections. The majority of the intersection turning movement counts were conducted in 2005.

In some cases the traffic volumes between adjacent intersections varies significantly. This occurred in some cases because the traffic counts were conducted at different times of the year. In these instances, the base year traffic volumes were adjusted in a “smoothing” process so that traffic volumes between intersections were relatively consistent except in locations where parking facilities are likely significant sinks/sources of traffic. The parking garage on Pearl Street, south of Chippewa Street, is an example of a location where the smoothing process assumed traffic was destined during the AM peak and traffic originated during the PM peak hour. The 2005 AM, mid-day and PM peak hour volumes are illustrated in Figures 1 thru 3 of Appendix D.

Development of 2025 Peak Hour Forecasts

The design year for this project is assumed to be 2025, as documented in the *City of Buffalo Main Street Multi-Modal Access and Revitalization Project Draft Final Environmental Assessment (Final EA)*. The year 2025 PM peak segment traffic volumes provided in Table 3-13 of the Draft Final EA generally served as

the starting point for development of the design year traffic forecasts. Additional assumptions used in the development of the design year traffic forecasts are summarized below:

- A background annual traffic growth factor of 0.5% was recommended in the Final EA and confirmed in a conversation with the GBNRTC.
- The PM peak hour segment volumes were available in the Final EA. These volumes were used with some modifications.
- Development of morning and midday traffic volumes on Main Street were developed based on existing study area morning and midday traffic patterns (i.e., directional and peak hour percentages) compared to afternoon traffic volumes.
- Approximately 25% of the Main Street traffic was assumed to be new traffic to the study area and the other 75% would be traffic diverted from adjacent corridors.
- In general, existing turn movement proportions by approach were maintained for intersections in adjacent corridors.
- The amount of circulating traffic for each block of Main Street varied depending on the availability and the number of on-street parking spaces.

As with the existing year traffic data, the future year traffic volumes needed to be smoothed between intersections taking into account parking facilities. The 2025 AM, mid day and PM peak hour volumes are shown in Figures 4 thru 6 of Appendix D.

Pedestrian Volumes

Downtown Buffalo and Main Street have a considerable amount of pedestrian activity throughout the day and especially during peak periods. Buffalo Place has been conducting pedestrian counts over lunch time hours along Main Street since the early 1980's. The most recent Main Street pedestrian count was conducted in 2005. The GBNRTC also provided pedestrian counts for other downtown intersections.

The development of Main Street pedestrian volumes for the AM and PM peak hours was based on a Buffalo Place *2000 Pedestrian Study* report that provided a comparison between midday volumes versus morning and afternoon volumes. A one percent annual growth was assumed for pedestrian volumes when developing 2025 pedestrian volumes.

Special Events Traffic Volumes

The special event traffic volumes were developed from traffic counts conducted by the consultant for both a single and dual special event. The single special event was a Buffalo Sabres hockey game held on January 12, 2006 with a starting time of 7:00 pm. The dual special event was a theater event at Sheas Theater combined with a Buffalo Sabres hockey game, both held in the evening of February 9, 2006.

The traffic counts showed vehicles arriving to the events throughout the period of sixty to ninety minutes prior to the event; however, most vehicles attempted to leave within a thirty-minute period of time immediately following the events. Vehicles start arriving for these special events towards the end of the PM peak hour and continued up until the event start times. The arrival travel patterns for inbound vehicles to the special events are normally different from outbound commuter travel patterns. For these reasons, the special event forecasts were developed for outbound traffic. In general, the streets not affected by special events typically have 25-35% of the traffic seen during peak periods. The single and dual special events traffic forecasts are shown in Figures 7 and 8 of Appendix D.

3.2 Signal Timing and Operation

The current traffic signal timings for downtown Buffalo intersections were obtained from sources including: GBNRTC Synchro models, City of Buffalo, NYSDOT, and NFTA. The signal timing data obtained from the agencies were supplemented by field investigations by the consultant. A majority of the intersections in the downtown area operate as fixed time traffic signals and use similar signal phasing during both the AM and PM peak periods. Traffic signals along Main Street also use fixed time operations, but preemption is allowed for LRRT operations.

The existing traffic signal system was installed in the early 1980's. The traffic signal system as stated earlier uses preemption as required by the LRRT movement along the tracks. The system works as any other intersection traffic signal system for the vehicular traffic at the signalized intersections. Inductance loops are placed within the train tracks that provide the necessary information for preempting the vehicular traffic signal system at intersections. Prior to moving the train from the station the train operator pushes a button on the control console of the LRV, which in return transmits a frequency signal into the interactive loop. The loop receives the transmission and determines the validity of the request, at which point a closed contact is made within the Train Control cabinet located at the stations which completes a circuit that is transmitted from the intersection controller located at the street. Once the signal controller has setup the preemption, a lamp located within the station area lights up indicating that the train operator can proceed.

The existing traffic signals are beyond their useful life. The hardware as well as the software being used for the intersection traffic control and the preemption system are now outdated and need to be replaced. The entire traffic control system within the Main Street corridor will be redesigned as part of this project.

A summary of the traffic signal timings for existing conditions is provided in Table 3-1.

Table 3-1 Existing Traffic Signal Timings				
Intersection	Cycle Length	Signal Phasing^a		
		1	2	3
Main / Scott ^b	88	32	33	23
Washington / Scott	54	30	24	
Main / Exchange	58	25	33	
Washington / Exchange	66	33	33	
Pearl / Seneca	64	31	33	
Main / Seneca	70	44	26	
Washington / Seneca	60	35	25	
Pearl / Swan	75	37	38	
Main / Swan	56	24	32	
Washington / Swan	75	37	38	
Pearl / Church	75 / 85	25 / 25	50 / 60	
Main / Church	83	39	44	
Washington / N. Division	75 / 85	30 / 30	45 / 55	
Washington / S. Division	75 / 85	30 / 30	45 / 55	
Pearl / Court ^c	70 / 70	28 / 28	42 / 30	- / 12
Main / Court	69	38	31	
Washington / Broadway	75	43	32	
Washington / Clinton	75	43	32	
Pearl / Huron	80	52	28	
Main / Huron	56	24	32	
Washington / Huron & Genesee ^d	88	40	26	22
Pearl / Chippewa	80	35	45	
Main / Chippewa	68	24	44	
Washington / Chippewa	75	45	30	
Pearl / Tupper	75	30	45	
Main / Tupper	75	30	45	
Washington / Tupper	75	30	45	
Main / Goodell	85	25	60	
Washington / Goodell	85	30	55	

Notes:

X / X = cycle or phase in the AM / PM peak periods

a – phase 1 = northbound/southbound; phase 2 = eastbound/westbound; phase 3 = other phase

b – phase 3 is northbound Main Street

c – phase 3 is a westbound left-turn

d – phase 2 = Huron Street and phase 3= Genesee Street

The traffic signal phasing for Main Street intersections appear to be based on pedestrian crossing times which results in several different cycle lengths along this street. LRRT vehicles operating along Main Street sometimes preempt the cross street signal phase. These preemption events result in either a shorter cross street phase or a longer Main Street phase. This decision is made by the control center using an algorithm that calculates minimum pedestrian times and releases LRRT vehicles from the station at the appropriate time. The traffic

signal timing along Main Street is classified as preemption because there is no attempt to get the traffic signals back in 'synch' following a preemption event.

Intersection Traffic Controllers & Train Control Interfaces

Existing

The existing intersection traffic controller is a combination of standard City of Buffalo/NYS DOT traffic signal controllers with preemption capabilities. The special software required to preempt the traffic signal was installed in late 1979 and early 1980's by NFTA. The system is well beyond its useful life to the point that when parts are needed they are obtained from a spare parts supply that the LRRT staff has accumulated from NYSDOT when they retire or renew traffic controllers statewide.

Proposed

The proposed traffic signal system for the entire Main Street corridor intersections will be similar to the most updated City of Buffalo and NYSDOT recommended traffic signal controllers. The preemption system required for the operations of the LRRT will be integrated into the new signal controllers. The new software for the preemption will be as required by NFTA and will function similar to the existing traffic control system.

3.3 LRRT Operations (Existing)

The NFTA LRRT system operates at the street level along Main Street between the Portal (located south of Tupper Street) and Scott Street. The LRRT system operates from approximately 5:30 am to 1:00 am on weekdays. During the peak hours, the number of trains operating along Main Street is 8 to 9 per hour with approximately a seven-minute headway and a mix of two and three-car trains. The average dwell time at stations is approximately 45 seconds during the peak periods.

3.4 Parking and Loading Zones

The City of Buffalo and Buffalo Place recently conducted studies on downtown parking in Buffalo. These studies looked at both on-street parking and off-street parking facilities. An inventory of available parking spaces was included in these studies. The Buffalo Place study also looked at occupancy and duration of parking for on-street parking spaces. The average duration for on-street meter parking spots was approximately one hour.

The Main Street project will add approximately 160 on-street parking spaces along Main Street between Scott Street and Tupper Street with an additional 44 parking spaces between Tupper and Goodell Street. Loading zones will be provided in select locations along Main Street. Passenger drop-off zones will be provided in the 600 block of Main Street for Theater patrons. Further discussion of parking is contained in Section 7 of this report.

3.5 Traffic Modeling and Analysis

The evaluation of traffic and transit operations along Main Street was completed for existing and future year conditions. The future year traffic analysis includes automobiles on Main Street. The multi-modal characteristics (e.g., LRRT, autos, pedestrians) found along this street were analyzed using a micro-simulation program called VISSIM. The ability to model the activity at mid-block locations (e.g., transit stops, parking vehicles) is a primary reason for using a micro-simulation model. The primary goal of this analysis effort is to determine how the re-introduction of automobiles and on-street parking into the Main Street corridor affects intersection operations and LRRT operations along the corridor.

Microscopic traffic simulation models like VISSIM treat each vehicle as an individual entity and vehicle trajectories are altered at each time step by factors like car-following logic, other vehicles, and traffic control devices. Each vehicle in the simulation has a number assigned to it that is between 1 and 10 that determines how passive or aggressive that vehicle is when interacting with other vehicles. A more aggressive vehicle in the simulation will tend to travel faster, be more likely to change lanes to pass, and accept shorter gap times when completing a turn maneuver. For transit operations, the VISSIM model allows the user to input transit routes, transit stops, and dwell times for transit vehicles at the stops.

The output of the VISSIM model includes a variety of measures of effectiveness (MOE) for both automobile and transit operations. Examples of the types of MOEs available for automobiles from VISSIM include stop and total delay time at intersections, travel time and delay time along a corridor, queue length, and emissions data. Examples of MOEs for transit operations include travel time and delay along a corridor, delay at intersections, and average station dwell times.

Modeling Assumptions

A traffic model requires a considerable amount of data related to traffic and transit operations. Some of the required data inputs (e.g., traffic volumes) have been discussed in the previous sections. Additional information on modeling assumptions is provided below.

Street Network – The Main Street model includes the parallel streets of Pearl Street and Washington Street. This was done to gain a better understanding of how vehicle queues on the east-west cross street could affect Main Street intersection operations. New east west cross street connections at Eagle Street and Mohawk Street are included in the Main Street model.

Main Street Geometry – The proposed Main Street layout from the EA document suggested that right-turn lanes be provided for the northbound/southbound approaches to each Main Street intersection. The initial VISSIM model runs included these right-turn lanes, however, the final traffic analysis does not include any right-turn lanes based on the recommendations of the Technical and Advisory Committees.

Traffic Signal Timing – The existing Main Street traffic signal control is quite unique and would require a computer program to be written for each traffic signal controller along Main Street. For this analysis effort, a form of transit signal priority (TSP) timings was used to give preferential treatment to LRRT vehicles. The TSP timings will either extend Main Street green time to service an approaching LRRT vehicle or truncate the cross street green time to minimize the wait time for LRRT vehicles on Main Street. The same traffic signal control is used for all traffic analyses.

Main Street / Goodell Street – A northbound left-turn lane and a left-turn arrow was assumed for this modeling effort. This is due to the large area covered by the intersection and the amount of southbound traffic on Main Street.

Theater Station – This station is included in the existing conditions analysis, but is assumed to be removed for the future year conditions analysis based on the recommendations of the Technical and Advisory Committees.

On-Street Parking – The location of on-street parking areas were revised from the original layout contained in the EA document to reflect the current preferred design layouts proposed. The latest version of the VISSIM model includes the ability to model on-street parking areas. This capability was evaluated and found to be inadequate for this analysis effort because the actual parking maneuver causes little or no delay for Main Street traffic. An alternative solution was developed that involves a new ‘parking’ vehicle class and stop signs that only stops vehicles in this particular class. These stop signs are placed along Main Street where on-street parking zones are located and when a ‘parking’ class vehicle reaches these stop signs they stop and dwell there for 20 to 50 seconds. This dwell time stops traffic along Main Street and creates the corridor friction associated with on-street parking maneuvers. The percentage of ‘parking’ class vehicles and the number of ‘parking’ stop signs were calibrated to create approximately 125 to 150 parking maneuvers per hour.

Vehicle Mix – It is assumed that cars and delivery trucks (i.e., no large trucks) are the only vehicles allowed on Main Street.

Right-Turn on Red – The right-turn on red maneuver is allowed for vehicles turning from Main Street to the cross streets. No right-turn on reds are allowed for vehicles turning from the cross streets onto Main Street.

Speed Limits – The assumed speed for Main Street is 15 mph and speeds ranging from 25 to 30 mph were assumed for the other streets in the model.

Level of Service

The evaluation of intersections for this analysis results in a MOE called total delay. Total delay is computed by VISSIM for each vehicle by taking the difference between actual travel time and the theoretical (ideal) travel time. The total delay value reported by VISSIM is very similar to the “Control Delay” performance measure found in the *2000 Highway Capacity Manual*.

Observations of traffic flows provide an understanding of the general nature of traffic, but are insufficient to indicate either the ability of the street network to carry additional traffic or the quality of service provided by the street system. For this reason, the concept of level of service (LOS) has been developed to correlate numerical traffic volume data to subjective descriptions of traffic performance at intersections. LOS categories range from A (best) to F (worst), as shown in Table 3-2.

For the purposes of this study, a deficiency is defined as LOS E or worse. This threshold was developed based on conversations with City staff and a lower threshold is common in a downtown environment.

Level of Service	Delay per Vehicle (seconds)	Description
A	≤10	Free flow, minimal delays
B	>10 and ≤20	Stable flow, occasional delays
C	>20 and ≤35	Stable flow, periodic delays
D	>35 and ≤55	Restricted flow, regular delays
E	>55 and ≤80	Maximum capacity, extended delays
F	>80	Forced flow, excessive delays

Source: Exhibit 16-2, *2000 Highway Capacity Manual*, Transportation Research Board

Traffic Analysis Results for Existing Conditions

The results of the signalized intersection capacity analyses and LRRT travel times for each peak period are summarized on Exhibits C-TF-1 thru C-TF-3 included in Appendix D. The results of the traffic analysis indicate that all of the Main Street intersections operate at LOS C or better during both peak periods.

Traffic Analysis Results for Future Conditions (Cars Sharing Main Street)

The results of the signalized intersection capacity analyses and LRRT travel times for each peak period are summarized on Exhibits included in Appendix D. The results of the traffic analysis indicate that all of the Main Street intersections operate at LOS D or better during both peak periods. There is some delay for both auto and LRRT vehicles on the Main Street approaches to the Church, Huron, and Chippewa Street intersections. Based on the traffic model, the travel time will increase by approximately one minute in each direction.

Most of the corridor delay along Main Street results from the LRRT vehicles stopped at stations while automobiles queue up behind the LRRT vehicle. Occasionally, it was observed that queued vehicles at an intersection would block a LRRT vehicle from reaching the station. The on-street parking maneuvers do result in some corridor delay, but do not typically result in impacts at intersections or LRRT stations.

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

In most cases, allowing left-turn vehicles does not appear to increase intersection delays significantly. The left-turn movements at the Main Street intersections with Court and Church Street seem to cause a little more delay due to the considerable number of pedestrians that reduce the capacity of the turning movements at these intersections.

The projected overall travel times for LRRT operations along Main Street increase by approximately one minute with cars sharing the roadway. The light-rail vehicles are projected to incur some delay at nearly every station due to the presence of automobiles on Main Street. The overall impact on the LRRT travel time along Main Street will be offset somewhat by the proposed consolidation of the Fountain Plaza and Theater District stations.

The following table summarizes the overall level of service for each of the Main Street intersections for the final layout conditions for the AM peak, PM peak and for the dual special events conditions.

Table 3-3 - LEVEL OF SERVICE			
YEAR 2025 CARS SHARING MAIN STREET			
INTERSECTION	OVERALL INTERSECTION LOS		
	AM PEAK	PM PEAK	DUAL SPECIAL EVENTS
Scott Street/Marine Drive	C	D	E
Exchange Street	B	C	B
Seneca Street	B	C	B
Swan Street	B	C	C
Church Street	C	C	C
Eagle Street	C	C	B
Court Street	C	C	B
Mohawk Street	C	C	B
Huron Street	C	C	B
Chippewa Street	B	C	B
Tupper Street	B	B	B
Goodell Street	B	B	B

Traffic Analysis Results for Special Event Conditions (Cars Sharing Main Street)

The traffic analysis results for conditions attributed to special events for Main Street intersection operations and light-rail travel time along Main Street are summarized in Appendix D of this report. The traffic analysis shows a poor level of service (LOS E) at the Main Street/Scott Street and Main Street/Church Street intersections and in particular the northbound approach to this intersection. The remaining intersections along Main Street are projected to operate at LOS C or better.

Field observations following a hockey event saw most of the congestion/delays experienced by motorists occurring within the parking facilities and accessing the street network at driveways. Once vehicles reach the street network they tend to experience some delay for the first few intersections and then traffic starts to disperse and intersection delays decrease as they move further away from the parking facilities. Similar observations following a theater event showed most of the delays occurring within parking lots.

The traffic analysis did not show significant delay to light-rail travel along Main Street. The Erie Canal Harbor northbound station is situated to allow for significant queuing at the Main Street/Exchange Street intersection and does not impact light-rail operations. The northbound station that indicates some potential delay for light-rail transit is the Church station due to its close proximity to the Eagle Street intersection. The Eagle Street intersection is a minor one and it is possible to incorporate some form of signal preemption as the northbound light-rail vehicle approaches the Church Street Station in order to clear the northbound queue at Eagle Street.

It is important to maintain a high quality of service for transit operations so that it is seen as a viable transportation alternative. Therefore, it is recommended that NFTA continue to use both the Event and Erie Canal Harbor stations and both tracks at each station for boarding passengers. This will require the segment of Main Street between Scott Street and Exchange Street to be closed to automobile traffic for a period of time immediately following an arena event. This period of time would be approximately 15-30 minutes following conclusion of the event. To enforce this roadway closure an additional police officer(s) would need to be stationed at the Main Street/Exchange Street intersection. The police officers at the Main Street intersections with Scott Street and Exchange Street could be supplemented with temporary cones or barricades to reinforce to automobile traffic that the roadway is closed.

3.6 LRRT Station Locations

The locations of LRRT stations along Main Street were driven by the traffic analysis, intersection safety and in some cases through the streetscape/urban design process as discussed in Section 7. The proposed station locations are based on the required queue lengths for the vehicular traffic at a particular intersection, the proposed parking along Main Street, the urban design within the

block and space required for vehicles leading and trailing the LRV's, in order to remain clear of crosswalks and intersections. The station locations are discussed in detail in section 5.6 of this report. Station shifts that are proposed in order to minimize the potential for delays in trains pulling into stations include: The in-bound and outbound Church Street stations; the in-bound and out-bound Fountain Plaza stations; the in-bound Seneca Station.

The ability of a LRRT vehicle to travel from station-to-station with minimal delays is important to the reliability of this mode of transportation. A LRRT vehicle caught in a line of queued vehicles only a few feet short of the station is a frustrating occurrence for users of the LRRT system. It also results in additional delay for the vehicles following the LRRT vehicle once the LRRT vehicle reaches the station. Therefore, it is important to balance the needs of efficient transit operations versus the streetscape/urban design concepts for this corridor. The LRRT travel times for existing and future conditions and for special events are shown in Figures 9 and 10 in Appendix D of this report

3.7 Safety Recommendations

The re-introduction of automobiles and on-street parking into the Main Street corridor results in more interaction between cars, pedestrians and LRRT vehicles. The location of LRRT stations can be viewed as one safety issue. Other safety issues are discussed below:

- In general, right-turn pockets do not appear to be necessary for Main Street intersections. The corridor appears to function adequately without right-turn pockets as long as right-turn on red (RTOR) movements are allowed, without any adverse impact on the level of service. If the RTOR maneuvers are not allowed then the right-turn pocket/station location issue should both be revisited.
- In general, left-turn movements appear to function adequately without causing much additional delays. Restricting left turns at intersection during peak hours will also be studied further during the final design phase. These movements can be further evaluated once the system is opened and can be revised if a traffic operation problem arises.
- The Main Street intersections with Court and Church Street are quite large (i.e., significant travel distances to traverse the intersection for Main Street traffic) and this results in several potential problems. First, left-turn vehicles stop in the middle of the intersection to wait for their turn and this results in other stopped vehicles behind them being trapped in the intersection when the traffic signal turns red. Second, opposing left-turn vehicles (with queued vehicles behind them) can create a gridlock situation where neither left-turning vehicle can make the turn. Finally, if a left-turn vehicle is among the first few vehicles at the stop bar, this often results in only a couple of vehicles being served during a cycle. The high pedestrian volumes at these intersections reduces the capacity of these turn movements and further degrades traffic operations.
- A left-turn lane and left-turn arrow should be added at Main Street / Goodell Street for the northbound approach to the intersection. This is a

large intersection and it is difficult for the northbound left-turn drivers to judge opposing traffic.

- Closed Circuit Television cameras will be installed at major intersections to monitor the traffic conditions at these intersections. The system will be connected to the existing NITTEC system. The installation of these cameras will help in providing current traffic information and in an event of an accident the information could be relayed to the emergency crews as soon as it occurs.
- The unique conditions at the portal area and Scott Street intersection will be addressed by the installation of flashing signals, warning/guide signs and pavement markings. A flashing signal should be installed at the portal area where the vehicular traffic merges with LRV's. The gatearm would prevent the vehicular traffic to from moving forward when a train is exiting the portal. Traffic control barriers, signals and other safety measures, such as rumble strips would be installed to deter motorist from following LRV into the portal. These features will be studied further during the final design phase.
- Message display boards will be strategically located to inform the public of any accidents. The boards will help in redirecting vehicular traffic from an area of concern.
- Directing traffic away from lower Main Street for special events.

3.8 Summary

The evaluation of traffic and transit operations along Main Street was completed for existing and future year conditions. The future year traffic analysis includes automobiles on Main Street. The multi-modal characteristics (e.g., LRRT, autos, pedestrians) found along this street were analyzed using a micro-simulation program called VISSIM.

- The traffic analysis shows that the vehicular traffic and the train traffic can operate simultaneously with acceptable intersection level of service and without significant delays to the train operations. Turning movements will be evaluated further during the final design phase.
- New traffic signs will be installed along the Main Street corridor as required by the Federal MUTCD and the NYS MUTCD for vehicular as well as train traffic.
- The existing traffic signal system including the preemption system will be replaced with a new traffic signal system that will incorporate new software to interface with the LRRT system. The new traffic signal system will include new traffic signal heads and pedestrian traffic signal system with count down timers. The crosswalks at intersections will be made more visible using different surface materials.
- Additional traffic control measures will be installed along the portal area where the vehicular traffic will merge with the LRRT. The southbound lane between Tupper Street and the portal will have a signal with **gatearm**, to prevent vehicular traffic merging while the train is coming out of the portal. New left turn lanes for southbound traffic will be provided at

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

Tupper Street and a left turn lane for the northbound traffic at Goodell Street. The traffic control system at the Scott Street intersection will be reviewed with plans for Bass Pro and Erie Canal Harbor Development at the southern limits of the project as they become available.

SECTION 4 – TRACKBED, RAIL ELEMENTS AND PAVEMENT

In addition to the preliminary design of pavements outside of the trackbed, a number of issues related to the trackbed and rail system were identified in the Scope Summary Memorandum for consideration under this project. Issues to be evaluated include trackbed rehabilitation, modifications to rail flange, fixation of the rail, stray current isolation, train control system modifications, catenary pole protection or relocation and trackbed drainage. The primary focus of all improvements is what is required to accommodate the reintroduction of cars to share the trackbed with the LRV's. While the age and condition of the trackbed and rail components must be considered, anything that is not required to meet the objective of bringing cars back to Main Street can only be considered further if supported by funding. As such, each of the elements considered have been evaluated relative to scope and associated cost. In terms of trackbed rehabilitation, three options that were considered include full depth trackbed reconstruction, trackbed resurfacing and minimal trackbed repairs. Many of the rail system improvements could only be considered under the full depth trackbed reconstruction option due to their impact on the pavement structure. In order to fully explain the various work considered, the following paragraphs describe in detail work associated with pavement and rail system elements that were evaluated.

4.1 Existing Conditions

Background: As described earlier, since 1984, approximately 10 blocks of Main Street in the Buffalo Central Business District have been used as a transit-pedestrian mall. This 10-block segment between Scott Street and south of Tupper Street forms approximately 1.2 miles of street grade light rail transit operated by the Niagara Frontier Transportation Authority (NFTA). In addition to the transit vehicles, only delivery, emergency, and maintenance vehicles operate in this mall segment. Passenger car and other vehicular traffic cross the light rail transit tracks at several street intersections along the mall.

In this mall area, the two-track light rail route has six stations on each side. NFTA light rail vehicles are powered from an overhead catenary system supported on poles located generally 130 feet apart in the center of the trackbed. These two tracks are spaced 13 feet 6 inches apart from track centerline to track centerline. The track structure is 128 RE 7A girder groove rail embedded in the street pavement. Gauge rods connecting the rails are spaced approximately five feet apart. The rails are supported on a concrete slab, approximately 13 inches thick. Elastomeric bearing pads and epoxy grout leveling courses transfer rail loads to the slab.

Rail Condition: A visual inspection of the existing rail was performed. While only the railhead and flangeway guard are visible, these elements appear to be in good condition and are within standard specifications. Based on the observations that could be made and the discussions conducted with NFTA personnel, it is anticipated that the rail can continue to be used in the mall area. The continued use or reuse of the existing rail requires confirmation in subsequent design steps.

This type of track construction is typical of systems that were built in the 1980's. Toronto had a similar pavement maintenance problem with gauge rods with their streetcar system and developed a program in the 1990s to replace the gauge rod

system with a direct fixation track system, similar to that described below. There has been a history of maintenance problems with the current embedded track design along the Main Street mall. Vibration, expansion and corrosion of the embedded gauge rods between the rails have caused breakage and cracking in the concrete pavement, creating an unsightly appearance and maintenance needs.

Possible approaches for addressing the above maintenance issues are described below.

4.2 Rail Components

The following considerations and improvements are relevant to the full depth trackbed reconstruction option and not to the other rehabilitation options considered:

As described above, an approach to providing a long-term solution for reducing pavement deterioration and its associated maintenance is to utilize a direct fixation track system. This direct fixation type of track structure is commonly used with in-street running light rail transit systems and uses direct fastening of the rail to an underlying support structure, such as a concrete slab.

A transit track system must be developed and designed with close consideration of the transit vehicle being used. Key factors include the wheel/rail interface, the wheel profile, the vehicle truck design, and the size of the flangeway required. These are considerations if a new rail section is to be used. (Flangeway is the opening along the head of the rail in which the wheel flange passes. The flangeway can be formed using girder groove rail, as currently used in Main Street, or by forming the opening in the embedment pavement.)

A common type of track structure used with in-street running light rail transit systems is direct fixation track. In this type of track, the rail is directly fastened to an underlying support structure, such as a concrete slab. There are various approaches to this design and many variables to consider. When adapting an existing system, there are additional unique factors to consider.

The following lists issues related to the track structure to be studied further:

- **Rail:** While, as described above, the existing rail appears to be in good condition, it is not known the condition that would result from construction needed to prepare for fixation. If new rail is to be used, the above design factors would need to be addressed. Girder groove rail is not manufactured in the United States, with girder groove rail used in LRRT systems generally being supplied from Europe. The 128 RE-7A girder groove rail is no longer manufactured. Should new rail be needed beyond that which NFTA currently has available, the rail selection is a very important element in the design.
- **Fasteners:** There are a variety of fasteners available. The fasteners generally use anchor bolts to attach the rail directly to an underlying support slab. The fastener to be utilized depends on the rail selected, the condition of the existing slab (below), and the approach to stray current control.

- **Support Slab:** From observations during maintenance work, NFTA reports the existing slab is in generally good condition. The actual design of the direct fixation system to be employed is a function of how much of the existing support slab can be reused.
- **Stray Current Control:** Stray current control is essential on light rail transit systems. Proper isolation of the track structure is needed. For the embedded track configuration in Main Street, a possible method of controlling the stray current is to employ an electrostatic “boot” that separates the rail from the surrounding concrete. In subsequent design steps, analysis is needed to determine whether the boot can accommodate the rather unorthodox existing rail section (if the existing track is to be used). A custom-shaped boot may be needed. Other approaches include isolating the entire track and slab structure or creating an isolated trough around the rail area.
- **Roadway Pavement:** Various pavements are used where light rail transit tracks are located in streets. The pavements are asphalt, poured-in-place Portland cement concrete, pre-cast concrete slabs, and decorative modular block. Often, the poured in place Portland cement concrete pavement section is used for in-street running light rail transit systems where relatively small strips of pavement exist outside of the track slab. Where the in-street section is wider, asphalt often provides an economic solution. However, frequently the over-riding factor in the pavement selection is that of urban design providing for an attractive appearance.
- **Drainage:** As with other types of track structure, surface track area drainage and drainage from the subsurface track support system are important for a direct fixation track installation.

At two locations along Main Street, at the HSBC tower and at the transition to the portal near Tupper Street, the track is constructed on a floating slab. In the past, repairs have been made as needed to the pavement near the rails. Broken concrete was removed and replaced by a fast-curing pavement mixture. Similar repairs have been under recent consideration.

Flangeway

Consideration has been given to the possible use of some type of flangeway filler as a safety measure if bicycles were to use the trackbed area. If available, the flangeway filler would need to be able to adequately resist the pressure of a bicycle tire, be sufficiently flexible to permit the rail vehicle wheel passage while staying in place, be able to withstand the general vehicular traffic, stay in place through the freezing and thawing cycles, and stay in place through snow removal operations. In contacting suppliers of products for the railroad and transit industries, no such flangeway filler material was identified that met all of the criteria. There is no known use of such a material by transit agencies in the United States for this type of application.

Further, bicycle tire contact with rail surfaces, especially when wet, at small skew angles, poses loss of friction problems for the bicyclist, which could also result in accidents. The flangeway opening can catch a narrow bicycle tire, resulting in steering and balancing problems for the bicyclist. In addition, conflicts result from the operation of transit vehicles, roadway traffic, and bicycles. Possible shared use by bicycles within the track area is a safety concern.

4.3 Pavement

Trackbed

The existing trackbed pavement was constructed as part of the track work installation project completed in 1983. The pavement generally consists of 5 ½ - inch concrete slabs supported by an underlying rubberized asphalt section of variable depth. The rubberized asphalt course bears directly on the concrete track slabs and select fill between the slabs. Other special pavement conditions which exist within the project corridor include continuous floating slab sections located at the HSBC tower and the portal approach, as well as a continuous track rail slabs at the Amtrak train tunnel and crossover slabs. The trackbed slab is supported by resilient pads, which bear on structural concrete decks in the floating slab and tunnel locations.

Overall, the slabs are showing signs of deterioration in the form of cracking, joint raveling and spalling. NFTA has performed maintenance over the years in the form of isolated slab replacements, joint sealant replacement and partial depth repairs. Rail vibration and poor subsurface drainage contribute to the deteriorated condition of the pavement. Surface repairs at crack joints and spalled areas are required to maintain the functional condition of the trackbed for vehicular use. Further investigation is necessary to determine actual remaining life based on the projected traffic.

Options considered for the trackbed pavement include full depth replacement of the concrete trackbed pavement; a 2" mill and resurfacing with epoxy resin bonded overlay; and minimal trackbed repairs to improve surface condition. A key component to the full depth and resurfacing options is the ability to work on at least one half of the trackbed at a time during normal daytime operating hours in order to minimize construction impacts on residences in various locations and overall construction costs. This would require NFTA to operate using a single track at a time. NFTA currently operates from 5:30 a.m. to 1:00 a.m. Monday through Friday and reduced hours on weekends. The current locations of the double crossover tracks that would have to be utilized for single-track operations are at the Erie Canal Harbor and Allen Street Stations. Utilizing these crossovers would more than double the operating time during peak hours. A crossover north of Church Street discussed under Section 4.4 would be required in order to maintain acceptable operating times during construction. The minimal trackbed repair work proposed would primarily consist of partial depth repairs that could be performed during reduced operating times on weekends and during nighttime shutdowns.

Direct fixation of the rail, which would directly benefit the proposed pavement structure by reducing the vibration and eliminating the need to provide a special joint to accommodate gauge rods, could only be addressed as part of the full depth pavement option. A 10-inch concrete pavement bearing directly on the rail support slabs would be the recommended pavement for the full depth option along with the installation of an underdrain system to maximize the life of the pavement.

Retaining the existing curb is necessary for the minimal trackbed option in order to prevent undermining of the trackbed slab adjacent to the curb. An underdrain

system is recommended behind the curb line below the sidewalk in order to improve the subsurface conditions that presently contribute to the trackbed deterioration.

Non-Trackbed Pavements

Concrete and asphalt pavements were evaluated as pavement options in non-trackbed areas. While concrete may provide some aesthetic advantage, asphalt pavement is proposed for costs savings. A 10 inch, full depth asphalt concrete pavement section is proposed for the vehicular traffic lanes outside of the trackbed. The pavements include parking and bicycle lanes, the lanes around the portal and Eagle and Mohawk Streets. A surface mill and 2" overlay is proposed for the 700 block section from Tupper Street to Goodell Street as the pavement appears in good condition with the exception of isolated failures which require full depth repairs. Saw cutting of the existing curb between the trackbed and proposed parking areas is required for vehicular access. Underdrain is proposed for all new pavement areas. Patterned, full depth concrete pavement is proposed within the intersections from the edge of the trackbed to the work limits, inclusive of the crosswalks, to enhance visibility and durability.

4.4 Crossovers

A track crossover is a connection between two nearby and, normally parallel, tracks. This connection provides the means for trains to pass safely from one track to the other. A crossover provides operational flexibility: trains are able to operate in the reverse direction to the normal pattern for special purposes (such as performing maintenance functions). Crossovers are normally utilized at the ends of a rail transit line, to allow trains to perform a "turn-back" operation. Future crossover benefits include the maintenance of trackbed and pavement without any major interruption to the rail operations, though vehicular traffic impacts would have to be addressed.

There is currently only one existing crossover within the street running portion of the LRRT line. This crossover is located at the Erie Canal Harbor station and allows trains to reverse their direction or continue onto the NFTA rail yard. An additional crossover was originally planned as part of the LRRT system construction near Church Street; however, due to budget constraints the crossover was shelved. Certain infrastructure was installed including the base slab for the track, gapping of the catenary poles and the isolation switches.

NFTA has indicated that the installation of this originally planned crossover would provide additional operational capacity and flexibility. The crossover could facilitate single-track operations during the construction of this project and provide long-term benefits for NFTA during periods of high maintenance requirements. Decisions associated with phasing and cost are discussed further in Sections 9 and 10.

At various times, installation of the crossover at Church Street has been considered. It has been felt that having the crossover in place would aid greatly in conducting track and roadway maintenance and upgrading. An analysis conducted by NFTA in 1992-showed improvement in operating flexibility. Further, the analysis indicated cost savings after allowing for the construction cost of the

Church Street crossover. Also, the analysis projected further future savings in pavement and track repair costs.

The NFTA analysis conducted in 1992 projected the construction cost at \$1,610,000, without construction management/administration costs. Subsequently, in 1997, NFTA projected a cost for the Church Street crossover of \$2,600,000, plus \$480,000 in costs for design and construction management/administration. Using Engineering News Record Cost Index information and other data, the probable construction cost estimate, in 2006 dollars, for the crossover would be approximately \$3,500,000. This cost would include track materials, switches, track slab removal and replacement, subsurface drainage, fasteners, stray current provisions, catenary pole adjustments, train control and communication wiring, design, and construction management/administration.

Consideration for the Church Street crossover is evaluated as part of the overall project costs discussed in section 10.

The current Erie Canal Harbor crossover is located mid-block between Scott Street and Exchange Street. When this segment is reopened to traffic, the use of this crossover would be limited to times when the road is closed. Therefore, an additional crossover south of Scott Street is required to maintain LRRT operations. The actual position of the crossover will be evaluated further during the final design phase in coordination with other projects currently being planned for this area.

4.5 Overhead Catenary System

Overhead Catenary System (OCS) Pole Relocations

The existing OCS is supported by poles located in the center of the trackbed. The poles are up to 18-inches in diameter and are spaced between 130 and 150 feet apart. The poles are supported on 3'-6" diameter pier foundations, 14 to 21 feet deep, that extend to the trackbed surface with the anchor bolts projecting above the surface. The poles create a fixed object hazard in the center of the road for the proposed vehicular traffic as well as limit the useable width of the roadway. A study was performed comparing retaining the poles in the trackbed center versus removing the poles and installing new poles outside the trackbed. The relocation of the catenary poles outside of the trackbed will provide travel lane widths of 11'-9". If the poles are not relocated then the poles will have to be protected from the vehicular traffic. This would be done by providing a 3-foot wide median (6 inches high) between the catenary poles. The provision of this median would reduce the lane widths to 10'-3". Comparison of these alternatives is discussed further in Appendix H. There is a cost saving of approximately \$2.5 million by retaining the poles; however, the safety concerns and aesthetics must be considered.

Given the overriding improvement in safety to the roadway and train boarding requirements, removing the poles from the trackbed is the preferred alternative. The poles would generally be in locations similar to the existing light poles in the

sidewalks. Underground utilities and vaults will impact the final placement of the poles. The poles will serve a dual purpose as both catenary support and lighting.

Given the location of the poles, cross-span wires are proposed to support the existing contact and messenger wires in the trackbed, in lieu of bracket arms. The cross-span wires will connect directly to the poles to maximize accessibility for emergency responders by not having additional longitudinal wires outside of the trackbed. Aesthetics will not be adversely affected, as the number of poles down the corridor will actually be reduced by the removal of the center poles. The catenary poles will be designed to look consistent with lighting for the project area.

The supporting hardware consisting of isolation switched and anchor poles will also be required.

4.6 Utilities (Trackbed)

When the LRRT was installed in the 1980's, utilities were generally relocated outside of the trackbed. The relocations were performed to provide room for the train control and traction power duct banks and structures located between the rail support slabs as well as avoid future impact on rail operations to access utilities. The duct banks generally run the entire length of the LRRT surface section and consist of one 6-way, 4-inch concrete encased duct for rail system traction power elements and one 8-way, 4 inch concrete encased duct for train control and communication elements. The duct banks are connected throughout the surface section with 8' wide by 8' long by 6' deep manholes, which also serve as splice points for 2-way, 2-inch concrete encased duct banks which feed existing catenary poles along the rail system. The LRRT system ducts are used by a number of tenants, which include Time Warner Cable (formerly Adelphia Communications), AT&T and MCI Communications. Utility crossings as well as some abandoned sewer and waterlines are known to exist within the trackbed. Major utility crossings include a 48-inch and 20-inch diameter water transmission main south of the HSBC building as well as 36 inch diameter transmission mains at Court Street and Huron Street. Numerous smaller diameter water mains cross at various intervals throughout the project corridor. Additionally, Electrical, Sewer and Telephone facilities cross at various locations within the project limits. No utilities will be installed within the trackbed under this project with the exception of additional conduits as needed for train operations.

4.7 Drainage

The existing drainage along Main Street is provided by a closed drainage system. Trench drains are located within the curbed section of the trackbed and run perpendicular to the tracks at regular intervals. These trench drains were installed as part of the trackbed construction in the 1980's and have been upgraded/retrofitted as part of the maintenance program. Trench drains along the trackbed are connected to catch basins along the sidewalks. These catch basins carry the stormwater to the main combined sewer trunk lines. There are various outfalls located along Main Street for the combined system.

As part of the project, rehabilitation or replacement of the trench drains and installation of new underdrain is proposed subject to the trackbed rehabilitation approach. Additional drainage inlets will be placed based within the trackbed as needed. Overall, the drainage patterns along the Main Street corridor will not change, as the roadway/trackbed profile will be retained.

4.8 Train Control

Within the street running portion of the LRRT service, the train control consists of the following apparatuses:

1. Inductive Loop (AVI also located at Scott St.)
2. Station Start Light
3. Traffic Intersection Controller (TPS System)
4. Alstom's Datatran (Train Location Indications)
5. Onboard Transponder activated through operator push
6. Train Control Signal/Track Circuit/Power Switch (Erie Canal Only)
7. Supporting Hardware (Control Cases, Power, Cabling)

On the street portion of the system, the on-board or Car borne portion of the Train Control System is switched to the off position by the operator selecting the street running mode on the control console of the LRV. The operator is then restricted by operating rules to 15 MPH Maximum Authorized Speed (MAS) until 8 PM at which time the operator can run at 20 MPH MAS. The system safety is within the hands of the highly skilled control of the LRRT operators. The carborne "Over-speed" protection while in the surface mode is set to trip at 28 MPH.

In this type of operation, the train operator becomes the critical portion of the Train Control system in two ways. When operators receive an indication via the "Ready to Depart" light, to leave the station, they push a button on the control console of the LRV, which in return transmits a frequency signal into an inductive loop that is located within the concrete portion of the track bed near the mini-high portion of the station. The loop receives this transmission and determines the validity of the request, at which point a closed contact is made within the Train Control cabinet located at the stations which completes a circuit that is transmitted from the intersection controller located at the cross street. When the signal is received, two things occur: First the system returns an acknowledgement that the signal has been received by the traffic controller and illuminates a starter light located just in advance of the mini-high portion of the station. This acknowledgement tells the operator that the traffic controller has received the request and that they can proceed toward the intersection. In addition, the traffic controller acts upon the request in several ways. The controller determines at what point the controller is in, in the normal timing sequence and depending upon those conditions initiates a request to change the traffic light signals to allow the LRV to proceed through the intersection unobstructed.

The second critical area is at the Erie Canal Harbor Station where the operator is the completion part of the routing selection process. Depending upon which platform is currently occupied at the Erie Canal Harbor Station, the operator may

need to change tracks and enter into the Erie Canal Harbor Station platform on the outbound side. For this to occur several things need to occur, one the vital train detection circuits must make the determination that it is safe to throw the power switch machine from the normal (straight track operation) to the reverse side (crossover rail operation). With these circuits satisfied the LRV dispatcher back at the Operations Control Center makes a request for the switch to operate to the reverse position. No action occurs until the operator selects the switch to also go to the reverse position on the LRV control console, at which time an agreement or a hand-shake occurs between the wayside portion of the Train Control System and the OCC the system then moves the switch points to the reverse position and a wayside authorizing movement into the station displays a proceed aspect.

The OCC monitors the street running operation remotely based upon a station check-in, check out system that is a subset of the train starter signals. The dispatcher cannot determine the exact location of the LRV but rather can only determine the last station that the LRV was at and waits until an arrival at the next station is sent. Should no signal be sent from the next station the OCC will continue to display the location of the LRV at the last known station. Should the dispatcher wish to hold an LRV at a particular station location either in response to an emergency or to re-establish a correct headway, the dispatcher must contact the LRV operator over the LRRT dedicated radio frequency.

The intersection traffic controller that receives the LRT station request and determines the signal sequence is the original equipment that was installed in the early 1980's. The system is well beyond its useful life to the point that when parts are needed they are obtained from a spare parts supply that the LRRT staff has accumulated from NYSDOT when they retire or renew traffic controllers statewide.

The traffic controller logic was designed by an independent contractor who assembled the parts and performed the programming required for the LRT traffic preemption logic. This contractor is no longer available and the supporting logic documentation is obsolete. Replacement of the controller is necessary to maintain the existing system as well as to interface with the proposed traffic signal system discussed under Section 3.

Train Control (CTC Communication)

This subsystem of the Train Control system provides the communication device between the wayside TC system and the OCC. The system is responsible for transmitting non-vital controls and indications required by the Train Control System. This subsystem is based upon General Railway Signal (GRS) (Now Alstom) Datatran (8) communication system. This subsystem is obsolete and only minimal support for replacement and/or repair can be obtained from Alstom.

External Communications

From conversations with NFTA staff, it was noted that HSBC has installed underneath the LRRT track infrastructure an essential Fiber Optic cable separate from the NFTA duct system. Interruption and/or damage to this cable could

result in severe legal penalties to NFTA. Work in and around the HSBC area will need to be closely monitored and staged with NFTA and HSBC staff to assure protection of this cable during the construction phase of this project.

There are fiber optic cables for 6 outside utilities running through the LRRT Cable infrastructure conduit duct banks within the street running section. Below are the current names of these six organizations. Prior to beginning design, each organization should be contacted. Currently, these six organizations are:

University of Buffalo
AT & T
Time Warner Cable (formerly Adelphia Communications)
Metropolitan Fiber Systems
QWEST Communications
MCI

These leased lines (conduits) will need to be treated in the same manner as the LRRT communication systems. Fiber Optic Cables as well as communications and train control cables loop in and out of each "Green Cabinet" (discussed in Section 5), and associated with each surface station will have to be relocated prior to their removal or relocation to maintain service.

4.9 Summary

A primary consideration in determining the extent of improvements related to the trackbed and rail is cost. The trackbed can be utilized by car traffic for the next 5 to 10 years with limited work being performed on the pavement. Ultimately reconstruction of the trackbed, including installation of subsurface drainage, will be required. Due to the cost limitations as discussed in Section 10, the following improvements are proposed:

- Minimal trackbed pavement repairs.
- Rehabilitation of existing trench drains.
- Removal of catenary poles within the trackbed and installation of new catenary poles in the sidewalks to support the OCS with cross-span wires.
- Relocation of OCS switch housing.
- Cable relocations associated with station shifts.
- Replacement of traffic signal controllers and software to interface with the Train Control System.

SECTION 5 – STATION REHABILITATION AND LOCATION

There are 6 sets of stations, in-bound (west side) and out-bound (east side), on the surface section of the LRRT system. The stations are identified as Erie Canal Harbor Station, Seneca Street Station, Church Street Station, Lafayette Square Station, Fountain Plaza Station and Theatre District Station. The stations are generally located on every other block with the exception of the Fountain Plaza and Theatre Stations, which are located on adjacent blocks. The goals of the preliminary station design effort are to develop station design concepts that do not dominate the landscape or architecture, while providing for weather protection as well as maintaining accessibility to the LRRT system. Evaluation of the existing station locations and strategic placement of the redesigned stations is a significant component of the preliminary design effort. Exhibits, which relate to the text for this Section, are included in Appendix B of this report.

5.1 Architecture

A number of concerns have been identified over the condition of the existing stations. The size of the stations has been identified as a concern as they tend to block exposure of the existing buildings. The existing stations range in length from 60 feet for the Church Street Station, to over 170 feet for the Fountain Plaza Station. The existing Erie Canal Harbor Stations are over 240 feet in length, which include dual platforms required for the current LRRT switchover operations. The existing station area includes platforms, ramps and covered areas within the train boarding area. The existing station structures are dark, non-transparent and create hidden spaces. Peeling paint and corrosion are some of the maintenance problems that exist on the structures.

The proposed station design concepts will incorporate strategies, which will create a greater sense of transparency including clear glass wall panels and translucent roof panels. The architectural theme is one of compact transparency. The streetscape behind and beyond each station will be more visible than currently accommodated by the existing stations. Storefront visibility along Main Street is of primary importance encouraging public interface and reducing blind corners, which currently exist along the transit corridor. The construction of stations, which do not compete with the existing architectural vocabulary on Main Street, is an additional programmatic requirement. Use of stainless steel materials where possible will help in reducing the overall maintenance of the structures. Improved lighting within the station areas will enhance security.

A uniform station length is proposed in order to standardize components, facilitate maintenance and future rehabilitation of the structures while minimizing their size. A station area length of approximately 42 feet is proposed for each station, which is approximately 2/3 of the length of the Church Street station and is similar in size to the Events Station located south of the Erie Canal Harbor Station. The depth of the station area is approximately 14 feet, which will allow for a sidewalk width of over 20 feet between the stations and building fronts.

5.2 Boarding Area

The boarding areas within each station are separated into two waiting areas. The elevated platform at approximately 30" above the sidewalk grade level and 36" above the rail is intended for passengers with accessibility requirements or those with limitations which will not permit at grade boarding via the foldout train steps. Accessible by a ramp with a 1:12 slope and a stairway, the elevated platform is designed to accommodate 2 wheel chairs and 3 ambulatory passengers. The grade level boarding area is sized to accommodate approximately 20 ambulatory passengers at 7 sf per person within the sheltered enclosure. Benches are provided for both boarding areas with the ticket machines accessible in the at-grade boarding area. Proper lighting of the boarding areas will enhance security as well as improve the overall look of the stations.

In addition to the sheltered boarding area, non-sheltered boarding areas will be provided as part of the streetscape design. These areas are discussed in Section 7 of this report.

5.3 Weather Protection

Each station is protected to the fullest extent possible to create a shelter, which will provide protection during inclement weather. Shelter overhangs on all sides provide additional protection for station occupants. The selection of a roofing panel which is translucent and which does not telegraph surface debris accumulated between periods of regular maintenance would be an optimal material choice. Either tinted glazing or prefabricated translucent panels would meet this objective. The selection of stainless steel for structural components is a logical choice for a highly durable and attractive finish. Transparent wall panels with minimized openings of 5 feet will provide wind protection, which is a concern within the project corridor. The wall panels in the ground level area would be setback from the curb a minimum of 4 feet to allow for maneuverability of transit users.

5.4 Accessibility

Currently, train accessibility is provided for those in need of assistance via ramps to the raised platform areas, which extend to the door opening. The existing platforms overhang the curb line by approximately 6-inches. The timber boards which are mounted to the face of the platforms to fill the gap between the platforms and train doors have been dislodged numerous times by emergency and delivery type vehicles that drive along the trackbed. As described under Section 2, there is a need to create a 2-foot clear zone adjacent to the curb line to prevent future incurrences. Several considerations were evaluated to accomplish this, which include elimination of raised platforms through train mounted or wayside lifts, as well as setting back the raised platform and installing train mounted or platform mounted bridge plates. Shifting of the curb line was also evaluated which would require modifications to the foldout train steps. The high cost of the train step modifications, over \$12 million, along with implementation, maintenance and operational concerns eliminated this option from further consideration. Train mounted lifts at a cost of almost \$6 million for the LRRT fleet, implementation time constraints relative to the current mid-life

project for the LRV's and operational impacts that would likely increase station dwell times anywhere from 2 to 6 minutes depending on the user's abilities, when lifts are required were key considerations for eliminating the train mounted lift option by the Technical and Advisory Committees. Wayside lifts pose significant operational and maintenance concerns as other systems which have wayside lifts have experienced dwell times up to 8 minutes, breakdowns due to weather exposure and require the train operator's assistance. Therefore, wayside lifts were eliminated from further consideration.

The preferred option selected by the Technical and Advisory Committees is to continue to use raised platforms accessed by a sloped ramp with the platform setback 2 feet from the curb. The two remaining considerations relative to using the raised platforms are whether to use train mounted or platform mounted bridge plates. While train mounted bridge plates have benefits of weather protection allowing for flexibility in aligning with the platform, the primary concerns are the \$2 million to \$3 million price tag to retrofit the fleet, implementation constraints with the train mid-life rebuild project and operational concerns should there be a mechanical failure with the plate extended as the train would be shutdown until the problem is corrected. As such, the Technical and Advisory Committees prefer the implementation of a fold-down type, platform mounted bridge plate. The fold-down plate option would be incorporated into each phase of construction unlike the train-mounted option, which would have to be completed prior to the completion of the initial construction phase.

The fold down plate would create a physical barrier at the edge of the platform to protect the edge. The fold down option will facilitate a manual override operation in the event of mechanical failure to mitigate impacts on rail service, as exposure to the weather creates an operational concern for platform-mounted plates. The plate design will include an edge barrier at least 2-inches high to prevent mobility aids from slipping off the edge, interface with the train control system for automated use to minimize operational impacts, a slip resistance surface, and visual and/or sound delineation to alert the public of its operation. A minimum length of 8 feet for the bridge plate was specified by NFTA in order for the train operators to properly align the door with the plate. The cost for implementation for all of the bridge plates is estimated at approximately \$1.0 million in 2006 dollars.

The raised platforms are generally designed for persons in need of assistance to board the train at a level plane (such as handicapped persons, elderly people or people with strollers). The ground level station boarding areas will be provided for those able to use the train steps. The train stations will be designed to provide improved weather protection to all train users.

5.5 Equipment and Furnishings

Benches incorporated into the boarding areas must be low maintenance and durable similar in material to those chosen for the shelter. Ticket machines provided either at the stations or another location must be accessible and sheltered for user facility. Additional components for each station include station location maps, message boards and signage. As themes for the design of landscaping and other urban design elements including lighting continue to

develop, the equipment and furnishings should reflect these themes incorporating them into a comprehensive environment. Further incorporation of large-scale elements like the panel boxes is of primary importance and can be addressed when the ability to downsize or relocate them has been further determined in the design process. Provisions will be made for keeping the ramp areas free of snow and ice during the winter weather through heating elements in the ramps.

5.6 Station Locations

Existing station platforms and shelters are located approximately 1000 feet apart on average with the exception of the Fountain Plaza and Theatre District Stations, which are approximately 800 feet apart. The Erie Canal Harbor Station has dual platforms in each direction to accommodate the current staging operations employed by the LRRT system as it functions as the start and end station for the system. The Events Station is located just south of Scott Street and is used only for Arena events and not during normal system operations.

Generally, the intent of the design is to maintain stations within the general vicinity of their current locations in order to minimize disruption to current LRRT system operations and maintain convenience for the transit users. Other factors that influence the decision for station placement include vehicular traffic interfaces, lane transitions and required operational changes.

- The Erie Canal Harbor Station is currently able to function as the start and end station for both the in-bound (west) and out-bound (east) tracks by utilizing the double crossover north of the station and the train control system. However, post construction operations will not be able to continue in this manner once vehicular traffic is sharing the trackbed. Therefore, there is no longer the need to maintain dual platforms on each, allowing single platform and shelters to be placed on each side. The proposed location for the Erie Canal Harbor Station platforms would align with the existing platforms at the far end of each approach. Coordination with the Bass Pro project may ultimately effect the final location of the station platforms in this block. Shifting of the Events Station will have to be coordinated with the proposed development projects at the lower end of Main Street, and will require further evaluation during the final design phase.
- Slight shifts of the Seneca Street Station platforms are proposed to allow for the addition of parking on each end of the block as well as to provide the recommended vehicle storage lengths identified by the traffic model. The resulting shifts away from the Seneca and Swan Street intersections are approximately 35 feet for both the in-bound and out-bound platforms respectively.
- Parking and vehicle storage lengths are key reasons for the approximate 100-foot shift to the north for the in-bound Church Street station platform. The out-bound station platform requires a shift to the south of just over 10 feet in order to accommodate the proposed Eagle Street connection.

- The in-bound Lafayette Square Station platform will remain in approximately the same location as currently exists, while the out-bound station platform is proposed to shift approximately 40 feet to the south to accommodate parking.

The Theatre District and Fountain Plaza stations were evaluated collectively due to the closer proximity of the two stations than any other stations on the surface section of the LRRT system. Generally, the surface stations are located on every other block except for the Fountain Plaza and Theatre Stations, which are on consecutive blocks. The out-bound Theatre Station is within 700 feet of the Chippewa Street intersection. In order to accommodate the necessary travel lane transitions around the portal along with associated delineation and warning measures, the distance between the station and Chippewa Street would be reduced by approximately one half. The existing out-bound Fountain Plaza Station is located just south of the Chippewa Street intersection. Input was sought from property owners in both the Theatre District block as well as the 700 block on placement of the Theatre District Stations. The general consensus from stakeholders and the Advisory Committee was:

- The resulting close proximity of the Theatre and Fountain Plaza Stations minimizes any benefit for having both stations.
- Drop-off zones are important in vicinity of the theatres for patron access.
- Stations in the Theatre block severely limit parking.
- Shifting the Theatre Stations to south end of Theatre block would negatively impact residential and hotel properties due to noise concerns.

Based on the above issues and concerns, the consensus is to combine the Theatre and Fountain Plaza Stations and locate them in the Fountain Plaza block similar to the current Fountain Plaza Station locations. The recommendation to place them in the Fountain Plaza block is supported by the larger daily LRRT system ridership in the Fountain Plaza block than the Theatre District block. Additionally, the proposed locations of the Fountain/Theatre Station platforms are strategically placed to attempt to balance the open views of Fountain Plaza as an important public space while accommodating parking at the north end of the block. A shift of approximately 50 feet to the south is proposed for the in-bound station, which will address vehicle storage requirements identified in the traffic modeling analysis. A 25-foot shift to the south is proposed for the out-bound station platform in order to provide adequate vehicle storage length while keeping the platform close to the Theatre District.

5.7 Communications, Power and Monitoring

The communication system of the LRRT is the backbone of the operation. The system supports Closed Circuit Television Vision (CCTV), PACE Emergency Communication at station platforms, Public Announcement (PA) system, and

Automatic Fare Collection (AFC), NFTA Police, Maintenance and LRRT Radio frequencies. In addition to these systems, the Power/Catenary remote Supervisory Control and Data Acquisition (SCADA) system and the Train Control System both in the tunnel and for the street running operation are supported by the LRRT communication system. At the core of this system is a 48-Fiber Optic cable, which provides the vehicles for all of these systems to successfully communicate between the field operations and the Operation Control Center (OCC).

The system has two distinct parts that are based upon varying technology. The fiber optic cable provides the “express” portion of the system, while a 50 pair communications cable picks up and supports the wayside functions at particular locations. This type of system architecture is common and reduces the amount of splices and possible level losses along the wayside system. At specific locations, the fiber optic cable is terminated and the 50 pair communication cable breaks out or provides input into the Fiber optic cable. The combination of the fiber and the traditional copper communication cable provide the cable infrastructure for the entire communication system.

CCTV

Unlike the train control, some portions of the communication system have been upgraded. In particular, the CCTV portion of the system is state of the art and provides excellent quality video resolution along with a new control and monitoring system back at the OCC. The system was installed in 2002 and with the exception of several problems with the overall Digital Light Projection (DLP), display the system has been extremely reliable. The cameras are PELCO an excellent manufacturer of security cameras and should provide the LRRT years of successful operation.

The CCTV does however use up quite a few of the fibers within the fiber optic cable as each station along the line has a dedicated fiber that provides the digital based signal from the cameras mounted on the mini-high portion of the station back to the control and monitoring station. The system is manned and operated by the NFTA Police force dedicated to the LRRT operations, who work closely with other law enforcement agencies, fire departments, and the LRRT Power and Train Dispatchers. The officer that monitors the camera system reported that the current system meets their needs exceptionally well. The system has built in intelligence to the point where if a passenger at a station pushed the emergency control phone at the station the camera for that particular station is immediately displayed and the emergency phone is connected to a phone located right on the officers console. He can then from the same console determine a method in which to react and at the officers finger tips has connection ability to any of the emergency response teams or organizations that could/would be required.

Public Announcement

The PA portion of the system is a traditional system found on many properties in the late 1970’s and early 1980’s. The system has performed and been maintained extremely well but has also reached the end of its useful life. The Aztec-Lansing system is a fairly simple system, which allows the dispatcher

within the OCC to broadcast system wide announcements or target an individual station. The systems at the station consists of a local power supply, the field end of the Aztec Lansing communication package and two PA type speakers mounted under the roof of the mini-high platforms in the surface stations.

Passenger Assistance Communication Equipment (PACE)

At each mini-high platform along the street running portion of the system a device allows passengers to either select information or call NFTA police in an emergency. Back at the OCC the system is interfaced into the CCTV system, which when activated a dedicated Video Display Unit (VDU) on the NFTA Police surveillance system pops up showing the location from where the call is being initiated. The system consists of a basic speaker/phone device with the built in functionality described above. This system will need to be replaced or relocated depending upon the project phasing selected in accordance with the new station location and mini-high platform.

Passenger Information Displays (PIDS)

The PIDS are relatively new, installed during the late 1990's and possess the capabilities of most modern day digital displays. The signs were manufacturer by Daktronics one of the premiere manufacturer of addressable LED text message signs. The signs can be addressed from NFTA's OCC when necessary, however under normal conditions the signs re-play a pre-determined message usually relating to the station and passenger security. Given the age and capabilities of this system it should be maintained under this project and re-located along with the station.

Automatic Fare Collection (AFC)

The AFC has been renewed since the original operations of the line. The system is based upon current technology with video display units (VDU) that perform the interface between the patrons and the system. A money collection system intakes the funds and places them within a secure box within the AFC housing. The system is sophisticated enough to perform remote reporting to the LRRT staff at the NFTA yard and shop facilities. The money or funds are collected by LRRT staff (Police and Communications) on a daily or as needed basis. Newer AFC equipment is also starting to make its way to the LRRT stations, which offer patrons additional ways to pay (debit/credit cards) as well a more user-friendly VDU display. Each station has multiple AFC interface units more than supporting the need of the patrons at times along the street running service.

Wayside Radio

The wayside radio portion of the system consists of three talk-groups and has been recently upgraded to add the Buffalo Fire Department. This system is an 800 Mhz "trunked" system and is based upon Ericsson equipment. The LRRT surface radio system is supported by three Microwave Sites at:

- HSBC Tower
- Boston
- Lancaster

This core system provides excellent service with a coverage rate of approximately 95% system wide. Wayside Radio equipment does not exist along the wayside in the street running portion of the system, so from a station standpoint will not require re-location or modification.

The tunnel portion of the radio system is support by bi-directional amplifiers at each station along with Omni - Antenna's mounted on each roof. Through the tunnel portion, a slotted Radiax (leaky) cable runs the entire way.

Supervisory Control And Data Acquisition (SCADA)

Along the street running area of the system, only certain areas contain SCADA equipment. The SCADA system provides the OCC Dispatchers the ability to control and monitor the conditions of the Catenary Traction Power System. Monitoring and control of the system is accomplished by the SCADA system. Dispatchers wishing to isolate or turn off portions of the traction power system can perform this task back at the OCC. The office system was provided by QEI Electronics, which has been involved in the electric traction power field for many years. The current wayside systems that support the LRRT operation today are nearing the end of its useful life and will require replacement in the near future.

The system AC & DC circuit breakers and isolations switches that can remove or return power to the traction power system. Through the use of Remote Terminal Units (RTU) located in several locations along the LRRT, system messages are transmitted and received from the OCC.

The communication system has been updated in some areas and these subsystems should be retained and relocated where possible, this includes:

1. CCTV
2. PIDS
3. AFC
4. PACE

Other portions of the communications system will need to be renewed or installed new to bring the technology up-to-date. These subsystems are:

1. PA
2. Emergency Call Box Phones
3. Wayside Phone
4. Conduit Duct Bank and Communications Cabling

Factors affecting potential modifications or replacement of system components include:

- Proximity of equipment with relationship to station location.
- Age and condition of the existing system.
- The need for improved technology

Power and communications are routed through control panels at each of the stations. The existing "Green Cabinets" are large and create a visual barrier. It is anticipated that the panels can be reduced in size by at least one third and incorporated into the station structures. The "Green Cabinet" in the vicinity existing out-bound Theatre Station houses the interphase to the tunnel ATC and will have to be relocated to outside of pavement areas with the proposed consolidation of the Fountain Plaza and Theatre Stations.

5.8 Summary

The proposed concept design for the stations call for a significant reduction in size from the existing stations, at 2/3 the size of the smallest station, and about 1/4 of the size of the existing Fountain Plaza Station. A station area approximately 14 feet by 42 feet, including a raised platform is proposed throughout. Transparent, translucent, stainless steel are the types of materials that will be incorporated. The platforms will be setback 2 feet from the curb line to meet the clear zone requirements. Automated, platform mounted bridge plates; 8 feet in length are proposed to bridge the gap. Consolidation of the Theatre District and Fountain Plaza Stations are proposed in order to accommodate a safe and viable design for the 600-block segment, which has to contend with the train portal interface. Incorporation of the power and communication control panels into the station structures will further reduce the visual impact of the stations on the environment. Relocation of the CCTV, PACE, PIDS and AFC system components is planned for the new stations. Replacement of the PA system, emergency phones and a wayside phone is required due to their age and condition. Relocation of communication lines through the new control panels would require close coordination with the cable owners.

SECTION 6 – ACCESSIBILITY/ADA COMPLIANCE

Maintaining accessibility for transit riders as well as insure accessibility for all throughout the project corridor is an important objective for the project. Compliance with all applicable code requirements set forth by ADA, ANSI, NYS and FTA must be achieved. Specific elements of the preliminary design effort are discussed below.

6.1 Sidewalks

The generally wide nature of the sidewalks throughout the project corridor will insure adequate maneuverability space. The streetscape components will be placed in a manner to maintain and enhance accessibility. Discussion of the design of these elements is included under Section 7. The sidewalk cross-slopes will be designed to comply with the ADA requirements. Specific grading will be developed as part of the final design effort.

6.2 Crosswalks

Accessible ramps (1 on 12 or flatter) will be provided at each intersection crosswalk. All ramps will include detectable warning fields. The width of the ramps will be sufficient to meet current ADA requirements. Wide, enhanced crosswalks, 16 feet with a 2-foot border on each side, are being proposed as part of the overall streetscape design.

Options being considered for reducing the excessive crosswalk lengths at the Church Street/Division Street and Goodell Street intersections are being discussed under Section 7. All proposed changes to these intersections are subject to the approval by NYSDOT.

6.3 Station Areas

The train accessibility requirement is currently met at the stations. Raised platforms with accessible ramps are provided at all stations for access to the first car of each train. The proposed stations will retain the raised platform and ramp features, as discussed under Section 5, in order to accommodate persons requiring assistance. Automated, station mounted bridge plates are proposed to fill the gap between the station platform and accessible train door. Warning surfaces will be provided at the station boarding areas behind the curb and at the edge of the raised platform for ADA compliance.

6.4 Parking

Designation accessible parking spaces will be evaluated for incorporation at various locations throughout the project area. The spaces will be located with consideration of the public spaces and various land uses.

6.5 Summary

All elements of the project design will be developed to comply with all current regulations for accessibility for persons with disabilities.

SECTION 7 – SIDEWALKS, STREETScape AND URBAN DESIGN

Main Street is a major civic corridor through the heart of downtown Buffalo. The present form of downtown echoes the importance of the street as the early development of the city was largely born at the foot of Main Street in the present Erie Canal Harbor District. Major commercial, retail, and entertainment facilities developed along Main Street as downtown grew in a relatively linear fashion. As a result Main Street today functions as a connective thread that integrates downtown districts and venues and conveys much of the identity of the downtown area.

The redesign of Main Street offers the opportunity for the street to contribute positively to the image of Buffalo by improving the quality of the streetscape. The re-introduction of vehicular traffic will add vibrancy to the street with greater visibility and increased access to businesses and at the same time the physical design of the streetscape will express the significance of the street as a civic space. There is a great opportunity to create a leafy corridor with high quality furnishings that becomes a major public amenity to the growing downtown residential population, the existing downtown office workers, and visitors alike who will be encouraged to linger longer and explore further.

This section outlines the parameters by which the streetscape component of the project will be designed.

7.1 Existing Conditions

The existing character of Main Street is defined by wide sidewalks, limited landscape elements, variable pavement conditions, and extensive architectural treatment of the streetscape. Visually the street is interrupted by structures that were intended to be lively additions to downtown that unfortunately are now dated and maintenance intensive. Paving is problematic as unit pavers were set on an inadequate base material causing differential settlement. Overall concrete slabs are sound however cracking and heaving has occurred in areas characterized by different sub-grade conditions. In many places planting is restricted to raised planters that are too small to support mature trees and do not offer pedestrians a place to sit. Seating options include small benches placed in variable locations adjacent to planters and beneath transit shelters. Streetscape elements such as lighting and trash receptacles are painted green, which if combined with the red painted asphalt draw attention to these features. The broad sidewalks offer the opportunity for street programs to occur such as the Country Market. Areas that are used for outdoor seating for restaurants help liven the street in summer months.

7.2 Districts and Street Typologies

At the onset of the project, the Design Team and Client Group identified four districts within the Main Street Corridor that describe the streetscape character and existing land uses today. These were:

<u>District</u>	<u>Boundaries</u>
Entertainment District	<i>Goodell to Chippewa</i>
Retail / Office District	<i>Chippewa to Church</i>
Traditional Office District	<i>Church to Exchange</i>
Erie Canal Harbor District	<i>Exchange to Scott</i>

Recognizing that changes in land use patterns will occur within the Main Street Corridor in the future, the Design Team identified four Street Typologies as a framework for design decisions. The four typologies are:

<i>Typology</i>	<i>Typical location</i>
Station Areas	253 feet length of a station zone
Parking Areas	On street parking, loading and drop off areas
Intersections	Intersections including pedestrian crossing features and required sight lines
Unique Spatial Conditions	View corridors and open space (contributing); portal and overhead structures (challenges)

(See Appendix C, Exhibit 1)

Each typology is further defined and expressed through criteria that:

- Address pedestrian and vehicular safety
- Maximize on-street parking
- Create memorable streetscapes
- Address existing district character while planning for the future

7.2.1 Station Areas

Within the 11 block long Main Street project area there are a total of six stations representing the at grade portion of the LRRT System, the special events station is located south of Scott Street which is used during events at the HSBC Arena. One station, the Theater District Station, has been consolidated with the Fountain Plaza station. The remaining stations are located in the approximate location of the existing stations and therefore occur at an interval of nearly one every other block. Station locations are discussed in Sections 3 and 5 of this report.

The existing station boarding areas are delineated by a wider (21”) curb that is 6-inches high to properly interface with the train steps. A narrower, lower (4” high) curb exists in all other areas. The higher curb will be retained in all proposed station areas. The length of the station boarding area is determined by the maximum number of LRV’s that may be used at any one time. A total of four cars has been established and a minimum length of 253’ for the station platform, inclusive of the station shelter.

The width of each station area from the face of building to the curb is 37’-9” and is comprised of three zones. From the curb, the first six feet is required clearance that both accommodate station patrons and snow clearing machinery. The next area, at a minimum of 16’-9”, is the station planting zone that accommodates large planters with seating. These planters create a distinctive Main Street environment that is comfortable and green. These areas serve not only light rail patrons but also provides a respite for visitors, residents, and workers in the downtown area. The final width established at each station area is the remaining distance from the edge of the planting zone to the building face, typically fifteen feet. Fifteen feet provides ample pedestrian circulation and the opportunity for outdoor seating associated with a restaurant or café. Without seating, the width of these areas may be reduced to twelve feet. (See Appendix C, Exhibit 2 and 3)

Design goals for the station areas are two-fold and include:

- Pedestrian safety boarding, disembarking, and waiting for the trains
- An aesthetically pleasing environment that provides comfortable shaded seating within a distinctive setting on Main Street

The following criteria is recommended for pedestrian safety:

- A minimum offset from the vehicular travel lane of eight feet to any permanent obstruction is suggested. This provides the ability of the station patron to step back an adequate distance from moving traffic while waiting for the train. This area should be kept free of all obstructions to allow the station patron to view an approaching train without stepping forward onto the curb. This is especially important with the use of the light rail system by children and students.
- An unobstructed view for the pedestrian of any potential hazard including moving vehicles or a suspicious person is suggested. The unobstructed view should be maintained between the heights of 3 and 8 feet from the surface of the sidewalk. Minor obstructions such as tree trunks and signposts are acceptable as well as any required element of the light rail station such as ticket vending machines. This view shed also provides visibility of pedestrians from the vantage of automobiles on Main Street which increases their awareness of the proximity of pedestrians to the roadway curb.

The client group has requested the design team to explore the option of constructing a traversable (mountable) curb in the station boarding area in order to allow for additional parking. The idea was initially proposed as a compromise to the decision by NFTA to retain the ability to operate with four car trains during special events such as hockey games. Subsequently, the advisory committee requested that the concept be implemented throughout the station-boarding zone for the 2nd, 3rd and 4th train cars. NFTA currently operates with 2 car trains at all times and with 3 car trains during peak operating hours on a daily basis.

At the direction of the City of Buffalo, traversable curb type parking is proposed only along the 3rd and 4th rail car zone and will not be considered for the 2nd car zone. The parking in the 3rd car zone will be effective only during the non-peak hours when only 2 rail cars are being used by NFTA. Similarly, the 4th car zone would be used for parking daily, except for when NFTA operates with 4 rail cars, which is during special events at the HSBC area. Proper signs would be posted with the imposed restrictions for parking along in the 3rd and the 4th rail car zones.

Implementation of the traversable curb concept for parking within the station boarding zones presents a number of challenges related to safety for LRRT passengers, pedestrians and motorists. Additional study is required to determine how these challenges can be adequately addressed. Safety and operational concerns include:

- Interaction between motorists and passengers in waiting areas as passengers tend to wait close to the curb.
- Establishing adequate clear zones between parking areas and LRV's to provide passenger access and prevent view obstructions.

- Balancing of the clear zone with vehicle maneuvering for parallel parking. Too great an offset from the trackbed to parking spots will encourage motorists to perform parking maneuvers entirely within the passenger waiting areas.
- Establishment of adequate safety barriers at edge of parking for pedestrian protection as vehicles must travel over a curb to park. This is of particular concern during winter months when snow and ice are present.
- Sloped curb within train stop area.
- Establishment of vehicle restrictions to allow for safe LRRT operations.

These issues will be properly addressed for all station-boarding zones and therefore will be studied further as part of the final design.

7.2.2 Parking Areas

The primary objective of the 'Cars Sharing Main Street' project is to provide vehicular access to Main Street. This is accomplished by providing travel lane (light rail track bed shared with cars) and new parking located parallel to the curb. The amount of parking is maximized between intersections on non-station blocks, with additional parking on station blocks either beyond the leading or trailing end of the station area.

The width of the new parking bays, along the trackbed segments where wider sidewalks exist, has been established at nine feet with an additional three foot buffer between the parking bay and shared track bed. This additional three-foot area provides safe access to a vehicle during the operation of light rail trains. In the 600 block of Main Street, this dimension is increased to five feet, thereby serving a dual purpose as a bike lane and buffer between parked cars and the train. The length of each parking bay has been established as twenty-two feet. In areas where the sidewalks are narrower such as around the portal, the 700 block, Eagle Street and Mohawk Street, eight-foot wide parking slots are provided. The approximate number of short-term parking spaces proposed along the project are 166 spaces between Scott Street and Tupper Street, 43 spaces between Tupper Street and Goodell Street, 16 spaces along Eagle Street and 32 spaces along Mohawk Street. Approximately 250 parking spaces are proposed within the project corridor. These however, do not include the parking in the station zone areas.

Loading zones have been identified along the length of Main Street at each block where a number of businesses do not have alternative off-Main Street access to their building. There are a total of nine loading zones. They are typically comprised of one or two parking spaces (22 or 44 feet) each in length with a width of nine feet plus a three feet buffer. In the theater district, a zone has been established that may be used for either vehicular passenger drop-off for Theater District venues or loading and unloading during non-event hours. The length of this zone is approximately 110 feet with a width of nine feet plus a three foot buffer.

The sidewalk adjacent to parking will have the following dimensional criteria. To allow for the clearance of snow at the curb, a six-foot zone without vertical obstructions will be provided. For general pedestrian circulation a minimum 10-

foot clear zone from the face of the building is accommodated which will increase to a minimum of 12 feet where café seating might occur. The remaining area at a dimension of either 9'-9" or 7'-9" will become the planting and amenity zone. (See Appendix C, Exhibit 4).

7.2.3 Intersections

The highest priority at each intersection along Main Street is safety. Clearly marked pedestrian crosswalks and un-obstructed views for pedestrians and automobile drivers define the design objectives. Each intersection zone along the length of Main Street is established as 50 feet beyond the curb of the intersecting street. The exceptions are the smaller streets of Mohawk and Eagle where 30 feet is established. Within these zones, no parking is permitted and planting is kept at a minimum. Crosswalks are 20 feet wide and composed of a simple stamped or scored concrete with a color variation that is distinct from the remainder of the street pavement. Crosswalks on intersecting streets are located such that the pedestrian path on Main Street is as straight as possible without jogging toward the center of the street at each intersection. The stop bar is therefore kept flush to the building face, which prevents vehicles from stopping within the sight line of a pedestrian approaching the intersection on Main Street. Curb ramps are located at the end of each crosswalk and comply with ADA regulations dictating slope and the use of a tactile warning surface.

7.2.4 Unique Spatial Conditions

The Ellicott Plan for Buffalo as designed by Joseph Ellicott, is modeled on the layout of Washington, D.C. Downtown has several public squares defined by the intersection of radial streets with an orthogonal street grid. Three of these public spaces occur along the length of Main Street and include Lafayette Square, Roosevelt Square, and the open space at Division and Church Streets. The design of the Main Street streetscape will respect these important public spaces by the placement of planting, seating, and pavement scoring that reinforces the original Ellicott layout. These areas are design opportunities that will serve to enhance the public spaces. Design challenges characterize the remaining unique spatial conditions, the 600-block portal and the HSBC and highway underpasses, where the surrounding streetscape is not conducive to pedestrian movement. The portal area will be addressed by replacing the existing fence on the portal wall with a new, more transparent screening. Providing continuity to the streetscape and aesthetic improvements that will enliven these environments will improve the character and help unify Main Street.

7.3 Sidewalks & Materials

The design goal of the Main Street sidewalks is to improve pedestrian circulation while accommodating various amenities that enhance the experience and viability of Main Street. The width of the new sidewalks will generally range from approximately 22 to 38 feet. Sidewalks will be wider in station zones and at intersections, and narrower where on-street parking is provided. The minimum proposed clear width for pedestrian circulation along any sidewalk on Main Street is ten feet.

Sidewalk materials will typically be poured-in-place concrete. Finishes may include exposed aggregate, other textured finishes and distinctive scoring patterns as well as stamped concrete, in limited areas. Colored concrete will be considered and stone unit pavers will be reviewed for special use at historic facades.

The layout of sidewalk amenities whether planters, street trees, signage, or other vertical elements, will provide a minimum width of six feet clear at the curb to allow the passage of snow removal machinery. This dimension of six feet, as recommended by Buffalo Place, will be respected elsewhere to maximize the ability to remove snow from the sidewalk. Additionally, snow storage areas will be provided to allow for short-term storage before the removal of snow from the Main Street district. (See Appendix C, Exhibit 5)

7.4 Pedestrian Amenities

The sidewalk amenities in the Main Street corridor should contribute to the overall character of the districts and provide places for people to safely interact. Pedestrian amenities should be distinctive in style and well-built. The following list of amenities is a preliminary outline of those under consideration:

Item	Material	Size
Benches	Wood seating with metal arms and legs	6 feet to 8 feet in length
Trash Receptacles	Metal with powder coated finish	30-40 gallon capacity
Planters	Concrete with Granite	400-500 CF of soil should be provide for each tree

7.5 Landscaping

New landscape elements will include deciduous shade trees, flowering trees, a limited number of evergreen trees, deciduous and evergreen shrubs, perennial and seasonal plantings. Due to the required street and curb reconstruction, all of the existing street trees will need to be removed. New plantings will be used to create distinctive zones within the corridor and provide seasonal interest. Plants will be selected based on streetscape typology, amount of available sunlight, sight line requirements, adjacent uses, maintenance requirements and planting conditions.

An important goal of the project is to improve horticultural standards, including use of continuous tree planting trenches for improved tree health. Current research shows that an 8” caliper tree requires 500 cubic feet of soil for healthy growth while a 16” caliper tree requires 1000 cubic feet of soil. A key consideration in evaluating planting conditions on Main Street is whether in-ground locations are available or if the required soil volume will need to be planned for above-ground planters. Above ground planters will be considered at some locations because of the high number of sidewalk vaults in the project area, particularly between Huron and Seneca Streets.

Trees to be used on Main Street will be selected from the City of Buffalo Forest list.

7.6 Light Fixtures

A distinctive, but standard City of Buffalo approved luminaries will be used along Main Street to ensure that replacements are timely and cost effective. The lighting levels will be safe but not excessive. Location of light fixtures will, in part, be determined by the required spacing of the catenary poles which are being relocated from the center of the roadway to the sidewalks. These 30 foot high poles will include street light luminaries with a lower level, pedestrian height fixture on the same pole. The intermediate street and pedestrian light fixtures will be in the same family of fixtures, located on lower height poles (typically 12 feet high). The poles may include custom arms for banners and hanging baskets.

Other specialty light fixtures may be incorporated within the unique spatial zones, particularly near the portal in the Theater District and beneath the elevated I-90 expressway. In addition, outlets may be provided at select trees to allow for electrical power that may be used for seasonal lighting

7.7 Events Spaces

The majority of downtown events occur at locations along Main Street. The streetscape design should accommodate the event by providing adequate space for the physical elements associated with each event. Designs should also provide enough room and unobstructed views for the crowds in attendance. The following chart identifies current events and location:

Name of event	Location
Curtain-up	Theater District
Tree Lighting	Fountain Plaza
Thursday at the Square	Lafayette Square
Country Market	Main Street between Lafayette Square and Eagle Street
M&T Events Series	M&T Plaza

7.8 Art Work

The incorporation of artwork into the project should be accomplished through the development of an Art Master Plan for Main Street. This document could be developed by the design team and would identify opportunities for the inclusion of permanent and/or temporary art, coupled with the consideration of budget, design requirements, and project schedule. The goal of the Master Plan would be to identify the best opportunities and a thematic concept that would make art a meaningful and exciting addition to the streetscape. Art objects may either be incorporated as stand alone features such as a freestanding sculptural element, or may be integrated into required elements such as benches, lighting, pavement, or planters.

7.9 Encroachments

Six buildings have sidewalk encroachments along Main Street.

Name of establishment <i>Use of encroachment area</i>	Address	Encroachment area (Length x width)
Hyatt <i>Atrium</i>	532 Main Street	88' x 19'
'B' District Police Station	695 Main Street	(2)4' x 4' columns encroaching 8' into walk
Bijou Grill <i>Addition</i>	643 Main Street	63' x 10.5'
Market Arcade <i>Cinema Signage</i>	639 Main Street	14' x 14' four post sign
Main Place <i>Columns for Pedestrian bridge to former AM&A's</i>	377 Main Street	4 columns, 2 paired each side of street 13' from face of building
City Grill <i>Wood Patio Deck</i>	256 Main Street	32' x 20'

Verification of the permits for the use in the City of Buffalo right-of-way will be performed during the final design. The encroachment issue will be resolved by the City of Buffalo prior to the start of construction, since the reconstruction of the sidewalks will impact these encroachments.

7.10 Utilities

As noted under Section 4, utility lines, with the exception of those required for the LRRT system, were generally relocated outside of the trackbed prior to or as part of the LRRT system construction. Therefore, there are numerous utilities located under the sidewalk areas between the curb lines and building faces. A description of the various utilities are listed as follows:

Sanitary Sewers

The sanitary sewer system along the project corridor, owned and maintained by the Buffalo Sewer Authority, consists of a combined sewer system located on the east and west sides of the trackbed running parallel to the project corridor. The combined sewers throughout the project corridor are generally comprised of brick and range in size from 12 to 36 inches in diameter. The sanitary sewer system generally consists of five distinct segments, with sanitary sewer system outfalls characterizing the segments. The combined sewers running south from the project limits at Goodell Street and the combined sewers running north from Court Street to the previously removed Genesee Street intersection just south of Huron comprise the first two segments, with all flows from Main Street being picked up by a seven foot outfall crossing the project corridor. The combined sewers running south from Court Street to Swan Street comprise the third segment, with all flows from Main Street being picked up by an eight-foot outfall crossing the project corridor. The fourth segment runs from Swan to Seneca Streets with all flows from Main Street being picked up by the outfall that crossed the project corridor at Seneca Street. The final segment consists of all sewer

systems south of Exchange Street, with all flows being picked up by the Hamburg Drain outfall.

The current EPA and NYSDEC rules and regulations require that the combined storm and sewer systems should be separated as part of the new construction. No utility work is proposed under the preferred alternative and therefore the separation of the combined system will not be a part of this project.

Waterlines

The water distribution system along the project corridor consists of 10 to 12 inch diameter mains, located on the east and west side of the trackbed with several crossings and hydrant branches located throughout the project. Waterlines along Main Street were installed between 1980 and 1985; a majority of the waterline section was installed during the LRRT construction period.

The waterlines are generally located in the sidewalk area between the trackbed and R.O.W. and run parallel with the trackbed. The west side waterline terminates at the intersection of Main and Tupper, while the east side waterline converges back into the roadway pavement beyond Tupper and continues along Main Street. No improvements or relocation of the waterline is proposed under this project.

Communications

Telephone and fiber optic lines owned by Verizon, World Com Telecommunications, Adesta Communications, Fibertech Networks and MCI Telecommunications are located at various locations throughout the project corridor. The majority of the communication systems in the project corridor consist of shared facilities, with single conduit and duct bank branches to provide specific building feeds. Verizon owns several duct banks and manholes, which are generally concentrated at the intersecting side streets, with minor branches onto Main Street. Communications is further discussed in Section 5.6 in detail.

Electric

Electrical distribution systems along the project corridor are owned by National Grid and generally consist of underground concrete encased duct banks and manholes running throughout the project corridor. The majority of the electrical distribution system was relocated outside the trackbed during the construction of the LRRT system. The primary electrical duct bank runs parallel with the trackbed and is comprised of 4-inch conduits, ranging from twenty to twenty four in number. Feeder ducts branch off the primary duct bank at numerous locations within the project limits to provide power feeds to rails stations, street lighting and building services. Electrical transformers are located within the sidewalk vaults throughout the length project corridor. The primary electrical duct bank is shared by other utilities including MCI telecommunications and Adesta Communications at various locations within the project limits. National Grid also owns and maintains street lighting located within the project corridor. The street light poles, luminaries and the cable are owned by the City of Buffalo. National Grid supplies power on a demand meter system basis.

Gas

Natural gas lines, owned by National Fuel Corporation are interspersed throughout the project corridor. Medium and low-pressure lines, 3 inches to 16 inches diameter in size, cross the project at various locations from the project limits at Scott Street to Chippewa Street with minor branches onto Main Street. Low-pressure gas mains run parallel on both the east and west side of the trackbed from Chippewa Street to the project limits at Goodell Street.

General Approach/Coordination

No major utility related work is anticipated at this time; however, due to the nature of the project minor utility location work in certain areas may be required. As part of the construction process all utility companies will be notified of the construction and a pre-construction meeting with the various utility companies will be scheduled.

7.11 Drainage

The existing drainage along Main Street is a closed system. A network of pipes and catch basins collect the stormwater and drain into various combined sewer trunk line outfalls along the Main Street corridor and side streets. The drainage along the corridor is working as designed except for isolated locations where low points have been created due to poor surface and sub-surface conditions. Inlets, manholes and separated storm piping, generally 12" to 18" in diameter, were installed throughout the project corridor as part of the station site work contracts in the 1980's.

The section between Goodell Street and Court Street consists of 16-inch to 30-inch storm pipes, with catch basins, drainage manholes and inlets located at regular intervals. The trench drains within the trackbed are also connected to this system. This section of Main Street between Goodell and Huron Street drains into a 7-foot combined sewer under Genesee Street. The section of Main Street between Court Street and Swan Street drains into an 8-foot combined sewer running along Swan Street. However, a section of Main Street between Church and Mohawk Street drains into a combined system along Mohawk Street. The section between Swan Street and Seneca Street drains into a combined system under Seneca Street. Similarly, the area south of Swan drains into an 11-foot combined system located under Exchange Street. The Hamburg drain is the outfall for the area between Exchange Street and Scott Street.

Replacements of drainage system components will be performed as needed to accommodate proposed grading conditions, station components and streetscape elements established as part of the final design effort.

7.12 Special Wind Conditions

HSBC Underpass / Seneca Street Station block / Main Place Block

Severe wind conditions occur in the vicinity of the HSBC center. Various wind calming features have been installed near the underpass of the HSBC center and

along the Seneca Street station block. These range from a metal passage structure with curved roof between Seneca Street and the LRRT station to simple metal structures. Wind calming techniques are being studied for this project, a technique that best suits the purpose will be installed to provide wind calming effects in the HSBC center and Seneca Street station areas. The pedestrian bridge at the Main Place block includes a wind screen that slows the wind effects in this block.

7.13 Feature Removals

Existing decorative art features are located at various locations within the project corridor, specifically steel “gateway” arches located north of Scott Street and north of Chippewa Street and decorative steel art features located at Mohawk Street. Additional features at Eagle Street and between Huron and Chippewa will also be removed. Feature removal is necessary to meet the objectives of this project and to accommodate the new streetscape and urban design themes being developed for this project. These features will be removed in their entirety, including structural steel, electrical components and foundations.

7.14 Heated Sidewalks

Snow and ice accumulation along the sidewalks during the winter season can cause problems if not maintained properly. Heated sidewalks are an option along the Main Street corridor to reduce the maintenance costs related to snow removal and deicing of the sidewalks. However, there are costs associated with maintaining the heated sidewalks as well. Heated sidewalks will also require replacement or repairs every few years on average. At present there are heated sidewalks located in the downtown Buffalo area. The installation of heated sidewalks was raised in the survey distributed in 2005. Responses were limited but favorable by those who were willing to pay for the installation, up-charges and the regular utility costs. Implementation of the heated sidewalks would have to be performed under betterment agreements with property owners.

7.15 Summary

A successful redesign of Main Street is dependent upon providing convenient vehicular access, a safe and comfortable experience for light rail patrons, and a dynamic and attractive setting for pedestrians. The extensive length of Main Street in downtown Buffalo requires both variety and consistency. Design variation will occur by responding to distinct downtown districts while consistency is derived from the dimensional standards inherent in the streetscape typologies. Major design objectives include creating high horticultural standards that insures the growth of healthy street trees and a distinctive yet simple strategy for the inclusion of streetscape elements that reduces visual clutter while at the same time provides a unique character to the street. The redesign of the streetscape is intended to help facilitate the economic rebirth of Main Street.

SECTION 8 – SAFETY AND SECURITY MEASURES

In addition to traffic safety measures being evaluated for the reintroduction of vehicular traffic to the shared trackbed roadway, various other safety and security measures will be addressed along the project corridor. Currently, the stations are monitored through closed circuit television and NFTA police patrols the mall area. Expansion of the monitoring system will be evaluated to enhance security along the entire corridor. Areas that present unique safety challenges are the portal opening and the roadway segment under One HSBC Center. Lighting improvements will be evaluated to help create a safe feeling for pedestrians. The interface with cars, trains, bicyclists and pedestrians will be addressed in the project design.

8.1 Lighting

The proposed lighting for the project must provide for safe levels along the roadway/trackbed as well as address the needs of the wide sidewalk areas and monitoring system. The existing light fixtures are spaced at approximately 100 feet on center. Combining the OCS and light poles will require that intermediate poles be added to maintain the desired intensities. The required intensities for Main Street are discussed under Section 2 and will be further evaluated in the final design phase to provide sufficient lighting and to minimize the shadow effects within the project corridor. A reasonable spacing of light poles similar to the existing poles and fixtures (metal halide) is 75 feet.

8.2 Monitoring

As discussed in Section 5, NFTA police monitoring of station areas is performed through the CCTV system that is routed through the OCC. Consolidation of the Fountain Plaza and Theatre District Stations will require the existing Theatre District cameras to be mounted on poles to monitor the portal area. This is of particular importance given that the portal area will become the interface between the shared and separated lanes. Additional cameras are recommended at each of the intersections throughout the shared trackbed areas in order to monitor and react to traffic conditions. Two adjustable cameras are proposed at each of the intersection that would connect to the existing fiber optic system that is routed to the OCC. Ultimately, the monitoring system could be interfaced with NITTEC to assist in the management of traffic operations.

8.3 Special Conditions

8.3.1 Portal Entrance

Of significant importance is proper identification and control of the interface at the portal. In the southbound direction, cars will be merging from a separated lane into a shared lane with the LRV's. A traffic signal and automated gate arm is proposed that would interface with the train control system to insure that vehicles cannot merge into the shared lane when the train is approaching from the tunnel portion. Also, the divergence of vehicular traffic from the shared to separated lanes in the northbound direction is a concern for the potential driver confusion that could result in vehicles entering the portal and tunnel area. Delineation in

the form of flashing warning lights, signage and markings is necessary to identify this area. Consideration of a positive barrier system is necessary to insure that vehicles are prohibited from entering the portal from both a safety and security standpoint. Various types of barriers have been evaluated as discussed in Appendix I. The fabricated type of barrier recommended is an automated horizontal beam barrier interfaced with the train control system. Another consideration would be the removal of trackbed slabs at the portal entrance. Maintenance of the open section of the portal is a concern that would have to be addressed further should slab removal be implemented.

8.3.2 HSBC Underpass

Security at the HSBC Tower has been identified as a concern with the returning of vehicular traffic to Main Street. Representatives of HSBC have expressed concern over vehicles stopped beneath the building structure within the roadway. Measures considered to address these concerns include installation of positive barriers similar to the portal area, side barriers to restrict lane widths and discourage motorists from stopping and exiting vehicles, coordination of signals each side of the building to minimize occurrences of standing vehicles, additional security cameras to assist in monitoring and height restricting barriers to limit the vehicle size utilizing this segment. Positive barriers would only be utilized during High Threat Levels (based on the Terror Alert Color) as this would close the road under HSBC. Assessment of barrier types and implementation will be studied further during the final design phase. Further coordination with One HSBC Center and familiarization with the building structure will be required to finalize measures considered for this location.

8.3.3 LRV Modifications

LRV improvements directly related to the project discussed during the preliminary design process include the installation of brake lights and possible variable signage at the rear of the vehicles. NFTA determined that the brake lighting system on the vehicles is in need of upgrades to adequately notify trailing vehicles of the LRV's intent to stop. Variable signage was considered as a supplemental measure to aid in the delineation at the portal interface, LRV signage is not considered further at this stage due to cost considerations.

8.4 Summary

Safety and security measures proposed for the project include:

- Improved lighting
- The addition of cameras at intersections to expand monitoring capabilities
- Positive barriers at the portal and potentially at HSBC Tower
- Signal and arm/gate for merging lanes at the portal
- Brake light improvements on the LRV's

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

Further study is needed to determine the extent of additional measures to be considered at One HSBC Center. LRV signage is not considered further at this time due to cost considerations.

SECTION 9 – CONSTRUCTION PHASING

A primary objective of the project is economic revitalization. As such, the construction must occur in a manner that maintains access to existing properties along the corridor to minimize disturbances. A balance must be established between disturbances and construction duration, limiting the duration on any block to one construction season. Work hours, rail operations and funding are all factors in the phasing of construction. Nighttime construction is a primary concern for residences along Main Street, which are predominately located north of Court Street. Rail operations create limitations for trackbed improvements during daytime hours. Considerations of single tracking and alternate modes of transporting passengers such as shuttle service will be evaluated. The installation of a crossover at Church Street is a consideration for mitigating service impacts during single-track operations.

9.1 General Approach

In order to minimize disruption to properties along the Main Street corridor as well as on transit operations, minimizing the number of phases is preferable. Additionally, overall project costs are historically higher the more a project is segmented. The additional costs relate to transitions between segments, mobilization or other measures to address train/car interfaces at the project limits as well as additional traffic control measures to name a few. However, funding limitations, interfaces with other projects and construction durations on each block weigh heavily into the construction phasing decisions.

At this point, it is understood that the project will be constructed in multiple phases starting at the north project limit and working south. The first phase (1A) would include the section between Goodell Street and Chippewa Street. In order to coincide with the anticipated completion of the projects along the lower Mains Street, it is anticipated that the construction work will then shift to the southern limits, with Phase 1B construction of the project happening between Scott Street and Exchange Street. Phase 2 of the construction will incorporate the remainder of the Main Street section between Chippewa Street and Exchange Street. The final construction under Phase 3 will include work South of Scott Street. The initial phasing concept is shown in Exhibit 9-1.

The construction work performed in each phase will be staged. Each stage would involve the reconstruction of sidewalk area on one side. The second stage will involve the reconstruction of the opposite sidewalk area. Given the proposed option of performing minimal trackbed repairs in lieu of major rehabilitation or reconstruction, the trackbed work would be performed either at night during operational shutdowns or during times of reduced operations when single tracking could be accommodated. Work will have to be staged to maintain access to properties at all times during the construction period. The exact phasing and staging will be developed during the detailed design. Closure of station platforms within the block being constructed would be necessary to facilitate construction of the new station areas.

It is proposed that the reconstructed sections of Main Street will be fully functional with the reintroduction of cars on Main Street. The sections that remain to be reconstructed or under construction will have proper traffic signs to guide the traveling public.

9.2 LRRT Operations

Maintaining rail service throughout the course of construction is integral to the success of the project as well as the long-term success of the downtown area. Interruption of rail service would limit accessibility to the downtown area for many riders as well as potentially impacting the long-term ridership. A concern raised by NFTA Metro Rail is that the current crossover locations result in headways increasing from the current 7-minute time to over 20 minutes during single-track operations. The installation of the Church Street crossover is said to reduce the time by an estimated 50 percent to 10 minutes for single-track operations. These durations are significant to rail operations. However, based upon the proposed alternative of minimal trackbed repairs, the crossover has been eliminated from consideration (further discussion can be found in Section 4).

Other considerations include closure of stations located within the blocks under construction and rail operations during later project phases. Closures will likely be required to accommodate the construction of the new stations as well as modifications to train control components within each work area. Safety considerations related to de-boarding passengers within a work zone are another concern. Other operational considerations and short-term measures will have to be evaluated further once the phasing is finalized.

9.3 Work Hours and Duration

The proposed construction work will progress mainly during normal daytime construction hours, particularly within blocks with residences and hotels. Nighttime work would be limited to low noise generating type work such as concrete placement and electrical work related to the catenary system. Coordination with stakeholders throughout the construction process will be key in minimizing problems and disturbances. Short-term construction impacts are anticipated to be consistent with the scale and scope of the proposed improvements. It is anticipated that standard construction mitigation procedures will be utilized by this project.

Work requiring LRRT system shutdowns such as catenary system modifications and train control modifications would have to be performed during nighttime system shutdowns, between 1:00 a.m. and 5:30 a.m. Other shutdown periods would have to be coordinated with NFTA to coincide with light usage, non-event periods such as Sunday afternoons.

9.4 Schedule

The following is a preliminary schedule for the project. The schedule for the project will may vary due to the funding of the project.

Design Approval	Summer 2006
Begin Phase 1A Final Design	Fall 2006
Project Bid Phase 1A	Spring 2007
Contract Award	Spring 2007
Phase 1A Construction Begins	Summer 2007
Phase 1A Construction Completed	Winter 2007

The schedule for the other phases of work would depend on the progress of Phase 1A operations and funding for the rest of the phases.

9.5 Summary

The proposed project to bring back Cars on Main Street is anticipated to be completed in three phases with two stages in each phase. A majority of the work will be located outside of the trackbed and can be completed during the daytime hours. Repair work within the trackbed and switchover of LRRT system components would be performed when single-tracking LRRT operations are acceptable or during the nighttime when the LRRT is not in operation. Access to residences, businesses and offices will be provided at all times. Pedestrian facilities will be maintained during the construction period. Construction mitigation measures will be in place to minimize any impacts (such as noise, dust etc.) due to the project. Each construction work phase will be completed in one construction season.

SECTION 10 – COST ESTIMATING

An initial construction cost estimate of \$ 53 million in 2003 dollars was developed in the EA for the overall project for the Shared the Trackbed alternative. This included roughly \$30 million to rebuild the deteriorating trainway and Metro Rail Stations. This figure was recently updated in the EA to reflect projected costs in 2008 dollars as well as to incorporate elements such as new crossovers at Church and Scott Streets and the relocation of catenary poles outside of the trackbed. As such, the project estimate escalated to approximately \$75 million. Subsequently preliminary design estimates have been developed which evaluated the various scope elements identified in the Scope Summary Memorandum. Upon development of scope element costs, work elements have been prioritized in order to achieve a fundable project that achieves the goal of returning cars to Main Street.

10.1 Cost Analysis

Throughout the course of the preliminary design development, costs have been developed for various scope elements evaluated for consideration under the project. Elements similar in nature or integral to each other have been grouped together when formulating costs. Categories established include:

- Roadway Pavement (including trackbed and rail related work)
- Parking Area Pavement
- Sidewalk Pavements
- Signalization, Signage and Markings (traffic control measures)
- Catenary Work (relocation or protection)
- LRRT Systems (includes all train control and station related systems)
- Stations (includes demolition, new structures and amenities)
- Bridge Plates (at station platforms)
- Streetscape/Landscaping (including all planters, plantings, furnishings and amenities)
- Safety and Security Measures (specific to portal interface and HSBC Tower)
- Drainage, Utilities and Vaults (in non-trackbed areas)

Costs for the above groupings were developed for the entire project on a block to block basis. Understanding the segmental costs was critical in the evaluation of funding related to the proposed phasing which was key to shaping the scope. Additional elements that apply to the overall project were evaluated for their impact on the project construction costs. These elements include:

- Crossovers at Church Street and Scott Street
- Drip Irrigation System
- LRV Brake Light Improvements
- LRV Signage
- Intersection Monitoring System (cameras added at intersections)
- Wind Screening (allowance carried for lower Main Street with scope to be developed as part of the detailed streetscape design for this area)

Additional elements discussed as part of the preliminary design but not incorporated into the estimate at this time include heated sidewalks and parking meters as they are not eligible for funding under this project. Allocation for funding of artwork will be evaluated further as the design progresses.

As a result of the cost escalation presented in the updated EA, alternatives were evaluated as discussed in earlier chapters. The primary alternatives considered were focused on the trackbed work discussed in Section 4. The alternative work approaches considered full trackbed pavement reconstruction, trackbed rehabilitation (resurfacing) and minimal trackbed repair work. Relocation of all catenary poles was compared with protecting the poles and relocating poles within intersections. The minimal trackbed at a construction cost of approximately \$51 million (the total project cost being \$ 61 million) with all work being completed by the end of 2009, is the most cost effective approach. The trackbed rehabilitation and reconstruction approaches add approximately \$ 6 million and \$ 16 million to construction costs respectively. The significant difference in cost resulted in the recommendation for advancing the minimal trackbed alternative. A summary of costs associated with the minimal trackbed alternative is included in Appendix E.

10.2 Phasing Considerations

Estimated project construction costs without regard to phasing are developed initially as a baseline for the project as the phasing is ultimately a function of the availability of funds and can be variable. At this point in time, a three-phase project is being considered for implementation. Additional costs associated with transitions, time constraints, LRRT operations, inflation projections, among other phasing related issues will ultimately impact the overall project costs.

10.3 Funding

The project will be primarily funded through FHWA with an 80 percent, 10 percent and 10 percent proportion shared between FHWA, the City of Buffalo and NFTA respectively. To date, approximately \$6.0 million has been allocated under the FHWA funding to begin the first phase of construction, Phase 1A. Additional funds in the amount of approximately \$2.0 million through a Transportation Enhancement Program grant is being applied for with a matching grant from the City in the amount of \$500 K for landscaping improvements. The approximately \$8.5 million figure is key in shaping the scope for Phase 1A. Similarly \$ 8 million funding has been secured for the lower Main Street. Additional funding will be established for the remaining project segments as the project design progresses.

10.4 Summary

In order to make the project viable for funding, decisions had to be made for the selection of scope elements that are vital to the successful completion of the project. As such, important but not vital elements such as trackbed reconstruction and rail fixation work have been eliminated from the project scope along with the Church Street crossover and LRV signage. Removal of the catenary poles within the trackbed with new combined catenary and light poles outside the trackbed has been determined to be a key element to the project and has been included in the scope. Other items will continue to be evaluated, as the project progresses are drip irrigation and wind screening elements.

SECTION 11 – ADDITIONAL CONSIDERATIONS

11.1 Maintenance Jurisdiction

The City of Buffalo, Niagara Frontier Transportation Authority and Buffalo Place are the main agencies having maintenance and jurisdiction over the different elements along the Main Street corridor. Negotiations in developing maintenance agreements for the roadway/trackbed, sidewalks, landscaping, traffic signals and controls amongst other concerns are on-going between the agencies. NYSDOT has jurisdiction on North and South Division Streets as well as Goodell Street.

11.2 Snow Removal

Snow removal will be a priority in order to maintain the trackbed for LRRT and motor vehicles during winter months. Removal of the catenary poles from the trackbed will facilitate snowplow operations. Placement of landscaping and streetscape elements will be coordinated to allow for snow storage adjacent to the trackbed in non-station areas. Other locations in the project area that do not impact traffic or pedestrian movements will continue to be evaluated as the project progresses.

11.3 Vault Abandonment

There are numerous basements and building vaults throughout the project corridor. Modifications and abandonment's were performed at various locations as part of the reconstruction work completed in the 1980's. Maintaining access and coordination with streetscape components and sidewalk construction will be integral with the design effort. Further investigation will be performed during the detailed design phases to determine if additional abandonment's can be performed to facilitate construction.

11.4 Environmental Assessment

An Draft Final Environmental Assessment sponsored by the City of Buffalo, the Niagara Frontier Transportation Authority (NFTA), Erie County, the New York State Department of Transportation, and Buffalo Place has been developed to address all environmental related issues for the project. NFTA is the lead agency and is currently facilitating the review process with the Federal Transit Administration (FTA). A final determination is required before the final design phase can be advanced beyond fifteen percent completion.

11.5 Public Input

A survey questionnaire was developed at the start of the preliminary design process in order to gain an understanding of local conditions and needs individuals and businesses located along Main Street. A summary of the information was made available to the public at a first public information meeting. The first public information meeting was held on February 1, 2006 for the project. Concepts for station designs and potential streetscape elements and approaches were presented to the public. A second public meeting was held on August 8,

2006, that presented a 3D traffic model depicting the interaction of vehicles, pedestrians and the rail cars along Main Street. Preliminary station and urban design concepts were also presented to the public. The public was asked to provide their input on the design of this project. The comments received are included in Appendix G of this report with responses to the comments.

11.6 Coordination with Other Projects

There are other projects sponsored by various other agencies that are under design or planning phase for the improvements in downtown Buffalo at this time. Coordination will be required with these agencies at various stages of this project. Some of the projects include:

- Bass Pro/Buffalo Erie Canal Harbor Area Design
- Church Street Median Improvements
- Implementation of projects contained within The Queen City Hub Plan; i.e. Pearl Street conversion to two-way traffic
- Erie Street Improvements

Planning and interfacing with these and any other projects identified will be an on-going process. Much of the coordination effort will be performed during the final design of each phase of this project.

APPENDICES

Appendix A

Exhibits – Roads and Trackbed Plans

Profiles, Sections & Details



ENTERTAINMENT DISTRICT





RETAIL/OFFICE DISTRICT




TRADITIONAL OFFICE DISTRICT




ERIE CANAL HARBOR DISTRICT




STATION



PARKING



INTERSECTION



UNIQUE SPATIAL CONDITIONS



JOSEPH ELLICOTT RADIAL STREET PLAN




HSBC AND HIGHWAY UNDERPASS





LIGHT RAIL PORTAL


Parking




Station









PARKING






Not To Scale




CARS SHARING MAIN STREET, Buffalo, New York
Design Report, August 24, 2006


Fountain Plaza Station View



Not To Scale




SECTION A



SECTION B


VIEW NORTH




SECTION C
VIEW SOUTH




SECTION D
VIEW WEST



SECTION E
VIEW SOUTH



SECTION F
VIEW SOUTH



PARKING SECTION IN THEATER DISTRICT



CARS SHARING MAIN STREET, Buffalo, New York
Design Report, August 24, 2006

Theater District View



CARS SHARING MAIN STREET, Buffalo, New York
Design Report, August 24, 2006

MATHEWS
NIELSEN

700 Block View

Exhibit 14

Trees



Ginkgo biloba 'Autumn Gold'
Autumn Gold Maidenhair Tree



Ginkgo biloba 'Princeton Centry'
Princeton Centry Maidenhair Tree



Platanus x acerifolia 'Bloodgood'
Bloodgood Sycamore



Quercus robur 'Skyrocket'
Skyrocket English Oak



Ulmus parvifolia 'Dynasty'
Dynasty Lacebark Elm



Ulmus 'Pioneer'
Pioneer Elm



Ulmus 'Frontier'
Frontier Elm



Cercidiphyllum japonicum
Katsura Tree



Cladrastis kentukea
American Yellowwood

Tree Planting Precedents



Shrubs



Berberis thunbergii 'Atropurpurea' - Red Barberry
Cotinus coggygira - Smoke Tree
Fothergilla gardenii - Dwarf Witch Alder



Hydrangea quercifolia - Oakleaf Hydrangea
Ilex glabra - Inkberry
Ilex meserveae - Blue Holly



Pinus mugo - Mugo Pine
Prunus 'Otto Luykens' - Otto Luyken's Cherry Laurel
Rosa alba 'Meidiland' - White Meidiland Rose



Rosa 'Bonica' - Bonica Meidiland Rose
Rosa 'Sea Foam' - Sea Foam Rose
Viburnum opulus 'Compactus' - Dwarf European Cranberrybush



Perennials



Echinacea purpurea - Purple Coneflower
Nepeta sp. - Catmint



Liriope muscari - Lily Turf
Liriope muscari 'Variegata' - Variegated Lily Turf



Bulbs



Allium giganteum - Giant Onion
Narcissus sp. - Daffodil
Tulipa sp. - Tulip



Scale of Newly Planted Tree (Typical)




Appendix B

Exhibits – Station Concept Plans,


Elevations & Details

NEW STATION PLAN AND ELEVATIONS




TRAIN SIDE ELEVATION

SCALE 1/4" = 1'-0"



SIDE ELEVATION

SCALE 1/4" = 1'-0"



BRIDGE PLATE OPTION

SCALE 1/4" = 1'-0"



ADVANTAGES OF THE NEW STATION DESIGN


- MORE TRANSPARENT
- DURABLE AND EASILY MAINTAINABLE SURFACES
- PANEL BOXES INCORPORATED INTO DESIGN OF STATION
- HEATED RAMPS FOR SNOW AND ICE MELTING
- ALLOWS FOR GREATER MAIN STREET RETAIL VISIBILITY
- TRANSLUCENT ROOF ALLOWS FOR DAYLIGHTING OF PLATFORM AND WAITING AREAS
- SHELTERED TICKET MACHINE STATION
- LARGER PROTECTIVE STATION OVERHANGS


NEW STATION EXTERIOR VIEW



CARS SHARING MAIN STREET
LRRT STATION - ALTERNATIVES


NEW STATION INTERIOR VIEW





PEAKED ROOF OPTION

SCALE 1/4" = 1'-0"



VAULTED ROOF OPTION

SCALE 1/4" = 1'-0"



CARS ON MAIN STREET
LRR STATION - ALTERNATIVES



FOIT-ALBERT ASSOCIATES
Architecture, Engineering and Surveying, P.C.
763 Main Street
Buffalo New York 14203

© FOIT-ALBERT ASSOCIATES P.C., 2005



HIDDEN SPACES AT STREET LEVEL



CORRODED STRUCTURAL MEMBERS



DARK, UNINVITING ENCLOSURES



OUTDATED FINISH MATERIALS



DIFFICULT TO MAINTAIN SURFACES




VISUALLY OBSTRUCTED RETAIL VENUES

CARS ON MAIN STREET
LRRT STATION – EXISTING CONDITIONS




FOIT-ALBERT ASSOCIATES
Architecture, Engineering and Surveying, P.C.
763 Main Street
Buffalo New York 14203


© FOIT-ALBERT ASSOCIATES P.C., 2005




NEW STATION PROTOTYPE



EVENTS STATION



CHURCH STREET STATION




FOUNTAIN PLAZA STATION

CARS ON MAIN STREET
 LRRT STATION – EXISTING STATIONS

Appendix C

Exhibits – Streetscape Concept

Plans & Details



MATCHLINE STA. 44+50. SEE C-RP-02

LEGEND


- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⋆ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES

1. FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
2. RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006	
PRELIMINARY PLANS		DRAWN BY MBS		FILE NAME: C-RP-01.DWG	
MAIN STREET		CHECKED BY PAR		DRAWING # SHEET #1 OF 13	
BUFFALO, NEW YORK		C-RP-01			



MATCHLINE STA. 44+50. SEE C-RP-01

MATCHLINE STA. 49+50. SEE C-RP-03

LEGEND	
	EX. CATENARY POLE- TO BE REMOVED
	NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
	EX. VAULTS/BASEMENTS
	SIGNAL HEAD LAYOUT
	TRAFFIC FLOW DIRECTION

NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.


GENERAL WILLIAM J. BONDYAN
STATE OFFICE ADDRESS
7 1/4
S ST
BUT REMOVE OR SEE MAP
OF NEW YORK



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063			
PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK		SCALE AS NOTED DRAWN BY MBS CHECKED BY PAR FILE NAME: C-RP-01.DWG DRAWING # SHEET #2 OF 13		JULY 2006	
NO.	REVISIONS	BY	DATE	C-RP-02	

MATCHLINE STA. 49+50. SEE C-RP-02

MATCHLINE STA. 55+00. SEE C-RP-04




LEGEND	
	EX. CATENARY POLE-- TO BE REMOVED
	NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
	EX. VAULTS/BASEMENTS
	SIGNAL HEAD LAYOUT
	TRAFFIC FLOW DIRECTION


NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.





CITY OF BUFFALO
DEPARTMENT OF PUBLIC WORKS




NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063	SCALE AS NOTED	JULY 2006
				PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK		
					DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-RP-01.DWG
					DRAWING #	SHEET # 3 OF 13

C-RP-03

MATCHLINE STA. 55+00. SEE C-RP-03

MATCHLINE STA. 60+50. SEE C-RP-05



LEGEND

- ✕ EX. CATENARY POLE-- TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES


- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO				
		DEPARTMENT OF PUBLIC WORKS				
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063	SCALE AS NOTED	JULY 2006
1				PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK	DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-RP-01.DWG
					DRAWING #	SHEET #4 OF 13
C-RP-04						

MATCHLINE STA. 60+50. SEE C-RP-04

MATCHLINE STA. 66+00. SEE C-RP-06



LEGEND

- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⋈ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES


- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO			
		DEPARTMENT OF PUBLIC WORKS			
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006	
<p align="center">PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK</p>		NO.	REVISIONS	BY	DATE
DRAWN BY MBS		CHECKED BY PAR		FILE NAME: C-RP-01.DWG	
DRAWING #		SHEET #5 OF 13		C-RP-05	

MATCHLINE STA. 66+00. SEE C-RP-05

MATCHLINE STA. 71+50. SEE C-RP-07




LEGEND	
✕	EX. CATENARY POLE- TO BE REMOVED
⋈	NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
▨	EX. VAULTS/BASEMENTS
⬇	SIGNAL HEAD LAYOUT
⇒	TRAFFIC FLOW DIRECTION

NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS		
		CONSTRUCTION PROJECT NUMBER -- 05-1063		
NO.	REVISIONS	BY	DATE	DRAWN BY: MBS CHECKED BY: PAR
△				
PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK				FILE NAME: C-RP-01.DWG
				DRAWING # SHEET #6 OF 13
C-RP-06				



LEGEND

- ✕ EX. CATENARY POLE—TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.

NFTA CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS

CONSTRUCTION PROJECT NUMBER - 05-1063


**PRELIMINARY PLANS
MAIN STREET
BUFFALO, NEW YORK**

NO.	REVISIONS	BY	DATE

SCALE AS NOTED	JULY 2006
DRAWN BY	MBS
CHECKED BY	PAR
FILE NAME:	C-RP-01.DWG
DRAWING #	SHEET #7 OF 13

C-RP-07

MATCHLINE STA. WM SEE BELOW



MATCHLINE STA. 77+00. SEE C-RP-07

MATCHLINE STA. 82+50. SEE C-RP-09

LEGEND

✕	EX. CATENARY POLE- TO BE REMOVED
⋈	NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
▨	EX. VAULTS/BASEMENTS
⬇	SIGNAL HEAD LAYOUT
⇒	TRAFFIC FLOW DIRECTION

NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.


NEW PAVEMENT LIMITS

MATCHLINE STA. WM SEE ABOVE

		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS										
		CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006							
<table border="1"> <thead> <tr> <th>NO.</th> <th>REVISIONS</th> <th>BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>1</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		NO.	REVISIONS	BY	DATE	1				PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK		DRAWN BY: MBS CHECKED BY: PAR FILE NAME: C-RP-01.DWG DRAWING #: SHEET #8 OF 13
NO.	REVISIONS	BY	DATE									
1												
				C-RP-08								

MATCHLINE STA. 82+50. SEE C-RP-08

MATCHLINE STA. 88+00. SEE C-RP-10



LEGEND

- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES


- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063			
NO.	REVISIONS	BY	DATE	SCALE AS NOTED	JULY 2006
1				DRAWN BY	MBS
				CHECKED BY	PAR
<p align="center">PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK</p>				FILE NAME:	C-RP-01.DWG
				DRAWING #	SHEET #9 OF 13
				C-RP-09	

MATCHLINE STA. 88+00. SEE C-RP-09

MATCHLINE STA. 93+50. SEE C-RP-11



LEGEND

- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES


- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006
PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK		DRAWN BY: MBS CHECKED BY: PAR	FILE NAME: C-RP-01.DWG DRAWING #: SHEET #10 OF 13	C-RP-10	
NO.	REVISIONS	BY	DATE		
1					

MATCHLINE STA. 93+50. SEE C-RP-10

MATCHLINE STA. 99+00. SEE C-RP-12



LEGEND


- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES

- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006
PRELIMINARY PLANS		DRAWN BY MBS		
BUFFALO, NEW YORK		CHECKED BY PAR		
FILE NAME: C-RP-01.DWG		DRAWING #		SHEET #11 OF 13
				C-RP-11



MATCHLINE STA. 99+00. SEE C-RP-11


MATCHLINE STA. 104+50. SEE C-RP-13

LEGEND	
	EX. CATENARY POLE- TO BE REMOVED
	NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
	EX. VAULTS/BASEMENTS
	SIGNAL HEAD LAYOUT
	TRAFFIC FLOW DIRECTION

NOTES	
1.	FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
2.	RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS									
		CONSTRUCTION PROJECT NUMBER -- 05-1063									
<p style="text-align: center;">PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK</p>		SCALE AS NOTED	JULY 2006								
		DRAWN BY MBS	CHECKED BY PAR								
<table border="1"> <thead> <tr> <th>NO.</th> <th>REVISIONS</th> <th>BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	REVISIONS	BY	DATE					FILE NAME: C-RP-01.DWG	SHEET # 12 OF 13
NO.	REVISIONS	BY	DATE								
		C-RP-12									



MATCHLINE STA. 104+50. SEE C-RP-12

LEGEND


- ✕ EX. CATENARY POLE- TO BE REMOVED
- ⚡ NEW CATENARY/LIGHT POLE/ CROSS-SPAN WIRE
- ▨ EX. VAULTS/BASEMENTS
- ⬇ SIGNAL HEAD LAYOUT
- ⇒ TRAFFIC FLOW DIRECTION

NOTES


- FOR CLARITY, ONLY MAJOR STRUCTURAL ELEMENTS AND TRAIN CONTROL CABINETS ARE NOTED FOR REMOVAL. HOWEVER, ALL EXISTING AMENITIES AND LANDSCAPE FEATURES WILL BE REMOVED UNLESS NOTED OTHERWISE.
- RIGHT-OF-WAY SHOWN IS APPROXIMATE BASED ON RECORD PLANS AND TAX MAPS.




		CITY OF BUFFALO				
		DEPARTMENT OF PUBLIC WORKS				
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063	SCALE AS NOTED	JULY 2006
△				PRELIMINARY PLANS MAIN STREET BUFFALO, NEW YORK	DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-RP-01.DWG
					DRAWING #	SHEET # 13 OF 13
					C-RP-13	




MAIN STREET CENTERLINE PROFILE




NFTA		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006	
NO.	REVISIONS	BY	DATE	
△				
PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK		DRAWN BY	MBS	
		CHECKED BY	PAR	
		FILE NAME:	C-PR-01.DWG	
		DRAWING #	SHEET #1 OF 15	
C-PR-01				




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS																																			
		CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED JULY 2006																																	
<table border="1"> <thead> <tr> <th>NO.</th> <th>REVISIONS</th> <th>BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>△</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		NO.	REVISIONS	BY	DATE	△																				PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK		<table border="1"> <tr> <td>DRAWN BY</td> <td>MBS</td> </tr> <tr> <td>CHECKED BY</td> <td>PAR</td> </tr> <tr> <td>FILE NAME:</td> <td>C-PR-01.DWG</td> </tr> <tr> <td>DRAWING #</td> <td>SHEET #2 OF 15</td> </tr> </table>		DRAWN BY	MBS	CHECKED BY	PAR	FILE NAME:	C-PR-01.DWG	DRAWING #	SHEET #2 OF 15
NO.	REVISIONS	BY	DATE																																		
△																																					
DRAWN BY	MBS																																				
CHECKED BY	PAR																																				
FILE NAME:	C-PR-01.DWG																																				
DRAWING #	SHEET #2 OF 15																																				
				C-PR-02																																	




MAIN STREET CENTERLINE PROFILE



		CITY OF BUFFALO			
		DEPARTMENT OF PUBLIC WORKS			
NO. REVISIONS BY DATE		CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED JULY 2006	
DRAWN BY MBS		PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK		CHECKED BY PAR	
FILE NAME: C-PR-01.DWG				DRAWING # SHEET #3 OF 15	
				C-PR-03	




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063			
NO.	REVISIONS	BY	DATE	SCALE AS NOTED	JULY 2006
△				DRAWN BY	MBS
				CHECKED BY	PAR
				FILE NAME:	C-PR-01.DWG
				DRAWING #	SHEET #4 OF 15
				C-PR-04	

PRELIMINARY PROFILES
MAIN STREET
BUFFALO, NEW YORK




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006	
PRELIMINARY PROFILES		DRAWN BY MBS		CHECKED BY PAR	
MAIN STREET		FILE NAME: C-PR-01.DWG		DRAWING # SHEET #5 OF 15	
BUFFALO, NEW YORK		C-PR-05			




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO				
		DEPARTMENT OF PUBLIC WORKS				
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063	SCALE AS NOTED	JULY 2006
△				PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK	DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-PR-01.DWG
					DRAWING #	SHEET #6 OF 15
				C-PR-06		




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006	
PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK		DRAWN BY	MBS	
		CHECKED BY	PAR	
		FILE NAME:	C-PR-01.DWG	
		DRAWING #	SHEET #7 OF 15	
		C-PR-07		




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063
△				
PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK				SCALE AS NOTED
				JULY 2006
DRAWN BY MBS				CHECKED BY PAR
FILE NAME: C-PR-01.DWG				DRAWING # SHEET #8 OF 15
				C-PR-08




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO			
		DEPARTMENT OF PUBLIC WORKS			
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006		
NO.	REVISIONS	BY	DATE	DRAWN BY	MBS
△				CHECKED BY	PAR
PRELIMINARY PROFILES			FILE NAME: C-PR-01.DWG		
MAIN STREET			DRAWING # SHEET #9 OF 15		
BUFFALO, NEW YORK			C-PR-09		




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006	
NO.	REVISIONS	BY	DATE	PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK
△				
DRAWN BY		MBS		FILE NAME:
CHECKED BY		PAR		C-PR-01.DWG
DRAWING #		SHEET # 10 OF 15		C-PR-10




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED	JULY 2006
NO.	REVISIONS	BY	DATE	PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK	
△				DRAWN BY	MBS
				CHECKED BY	PAR
				FILE NAME:	C-PR-01.DWG
				DRAWING #	SHEET #11 OF 15
				C-PR-11	




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006
NO.	REVISIONS	BY	DATE	DRAWN BY
△				MBS
				CHECKED BY
				PAR
PRELIMINARY PROFILES			FILE NAME: C-PR-01.DWG	
MAIN STREET			DRAWING # SHEET #12 OF 15	
BUFFALO, NEW YORK			C-PR-12	




MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006
PRELIMINARY PROFILES		DRAWN BY MBS		
MAIN STREET		CHECKED BY PAR		
BUFFALO, NEW YORK		FILE NAME: C-PR-01.DWG		
		DRAWING #		SHEET # 13 OF 15
				C-PR-13




MAIN STREET CENTERLINE PROFILE




			CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS		
			CONSTRUCTION PROJECT NUMBER - 05-1063		
NO.	REVISIONS	BY	DATE	PRELIMINARY PROFILES MAIN STREET BUFFALO, NEW YORK	
△					
				SCALE AS NOTED	JULY 2006
				DRAWN BY	MBS
				CHECKED BY	PAR
				FILE NAME:	C-PR-01.DWG
				DRAWING #	SHEET # 14 OF 15
C-PR-14					



MAIN STREET CENTERLINE PROFILE




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
CONSTRUCTION PROJECT NUMBER - 05-1063		SCALE AS NOTED		JULY 2006
PRELIMINARY PROFILES		DRAWN BY	MBS	
MAIN STREET		CHECKED BY	PAR	
BUFFALO, NEW YORK		FILE NAME:	C-PR-01.DWG	
		DRAWING #	SHEET #15 OF 15	
		C-PR-15		




TYPICAL TRACKBED SECTION

41+26 TO 45+33
 46+73 TO 47+45
 47+85 TO 49+35
 53+92 TO 68+35
 70+20 TO 93+75





TYPICAL CROSS-OVER SLAB TRACKBED SECTION


45+33 TO 46+70
 68+35 TO 70+20




		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063
				SCALE AS NOTED JULY 2006
				DRAWN BY MBS
				CHECKED BY PAR
				FILE NAME: C-SC-01.DWG
				DRAWING # SHEET # 1 OF 6
EXISTING TRACK BED SECTIONS MAIN STREET BUFFALO, NEW YORK				C-SC-01




				CITY OF BUFFALO																									
				DEPARTMENT OF PUBLIC WORKS																									
<table border="1"> <thead> <tr> <th>NO.</th> <th>REVISIONS</th> <th>BY</th> <th>DATE</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>				NO.	REVISIONS	BY	DATE																					CONSTRUCTION PROJECT NUMBER - 05-1063	
NO.	REVISIONS	BY	DATE																										
EXISTING TRACK BED SECTIONS MAIN STREET BUFFALO, NEW YORK				SCALE AS NOTED																									
				JULY 2006																									
				DRAWN BY MBS																									
<table border="1"> <tr> <td>CHECKED BY</td> <td>PAR</td> </tr> </table>				CHECKED BY	PAR	FILE NAME: C-SC-01.DWG																							
CHECKED BY	PAR																												
DRAWING #				SHEET # 2 OF 6																									
				C-SC-02																									




EXISTING SECTION - TUPPER STREET TO GOODELL STREET
101+58 TO 108+55




		CITY OF BUFFALO				
		DEPARTMENT OF PUBLIC WORKS				
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063	SCALE AS NOTED	JULY 2006
				EXISTING TYPICAL SECTION MAIN STREET BUFFALO, NEW YORK	DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-SC-01.DWG
					DRAWING #	SHEET # 3 OF 6
				C-SC-03		





CATENARY POLE RELOCATION
(OUTSIDE OF TRACKBED)





		CITY OF BUFFALO				
		DEPARTMENT OF PUBLIC WORKS				
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1036	SCALE AS NOTED	JULY 2006
				TRACK BED SECTION MAIN STREET BUFFALO, NEW YORK	DRAWN BY	MBS
					CHECKED BY	PAR
					FILE NAME:	C-SC-01.DWG
				DRAWING #	SHEET # 4 OF 6	C-SC-04




PARTIAL ROAD/TRACKBED SECTION AT PROPOSED PARKING AREA




TYPICAL HALF SECTION AT HSBC TOWER
49+35 TO 53+92





TYPICAL FLOATING SLAB SECTION AT PORTAL INTERFACE
93+75 TO 97+65





		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063			
NO.	REVISIONS	BY	DATE	SCALE AS NOTED	JULY 2006
				DRAWN BY	MBS
				CHECKED BY	PAR
PROPOSED TYPICAL SECTION MAIN STREET BUFFALO, NEW YORK				FILE NAME:	C-SC-01.DWG
				DRAWING #	SHEET # 5 OF 6
				C-SC-05	




PROPOSED TYPICAL SECTION - 700 BLOCK





PROPOSED TYPICAL SECTION - PORTAL





PROPOSED TYPICAL SECTION - EAGLE STREET & MOHAWK STREET



		CITY OF BUFFALO DEPARTMENT OF PUBLIC WORKS			
		CONSTRUCTION PROJECT NUMBER - 05-1063			SCALE AS NOTED JULY 2006
NO.	REVISIONS	BY	DATE	<p>PROPOSED TYPICAL SECTION MAIN STREET BUFFALO, NEW YORK</p>	
FILE NAME: C-SC-01.DWG				DRAWING # SHEET # 6 OF 6	
DRAWING #				C-SC-06	




COURTESY OF: SARNICOLA TECHNICAL SERVICES


		CITY OF BUFFALO		
		DEPARTMENT OF PUBLIC WORKS		
NO.	REVISIONS	BY	DATE	CONSTRUCTION PROJECT NUMBER - 05-1063
				SCALE NOT TO SCALE
				JULY 2006
				DRAWN BY: MBS
				CHECKED BY: PAR
				FILE NAME: C-PBP-1.DWG
				DRAWING # SHEET #
				C-PBP-1

Appendix D
Traffic Engineering
And
Analysis Data


**Buffalo Main Street Traffic
Existing AM Smoothed
FIGURE 1**



**Buffalo Main Street Traffic
Existing MD Smoothed
FIGURE 2**




**Buffalo Main Street Traffic
Existing PM Smoothed
FIGURE 3**



**Buffalo Main Street Traffic
2025 AM Build**

LEGEND
Target Volume (Estimated Based on EA AM Peak)


FIGURE 4



**Buffalo Main Street Traffic
2025 MD Build**

LEGEND
 Target Volume (Estimated Based on EA Midday Peak)
 Revised Balanced Target Volume


FIGURE 5



**Buffalo Main Street Traffic
2025 PM Build**


LEGEND
Target Volume From EA

FIGURE 6




**Buffalo Main Street Traffic
Single Special Event (Hockey)
Outbound Traffic (1-12-06)**


FIGURE 7



**Buffalo Main Street Traffic
Dual Special Events (Hockey/Shea)
Outbound Traffic (2-9-06)**

FIGURE 8






LEGEND	
145/152	A.M. PEAK LRRT TRAVEL TIME EXIST. A.M. PEAK HOUR/ (IN SECS.) YEAR 2025 A.M. PEAK HOUR
144/167	A.M. PEAK LRRT TRAVEL TIME EXIST. P.M. PEAK HOUR/ (IN SECS.) YEAR 2025 P.M. PEAK HOUR

X/X TOTAL TRAVEL TIME X/X
 LRRT – TRAVEL TIMES
 AM & PM PEAK HOURS

*NO LRRT STOP AT THEATER DISTRICT STATION

Figure 9



LEGEND	
115	SINGLE EVENT TRAVEL TIME (IN SECS.)
145	DUAL EVENT TRAVEL TIME (IN SECS.)

LRRT – TRAVEL TIMES
SINGLE AND DUAL SPECIAL EVENTS

Figure 10

Appendix E

Construction Cost Estimates

CARS SHARING MAIN STREET PRELIMINARY CONSTRUCTION COST ESTIMATE - JULY 18, 2006

REHABILITATION APPROACH - MODIFIED SCOPE (MINIMAL TRACKBED WORK)

PHASE	BLOCK SEGMENT		2007 DOLLARS	2008 DOLLARS	2009 DOLLARS	ADDITIONAL PHASING COSTS (10%)	PHASE TOTAL
			REVISED SCOPE INVOLVES ELIMINATION OF CHURCH STREET CROSSOVER, ELIMINATION OF LRV SIGNAGE AND THE INCLUSION OF MINIMAL TRACKBED REPAIRS.				
1A	A	GOODELL TO TUPPER	\$1,332,355				\$1,332,355
	B	TUPPER TO CHIPPEWA	\$4,380,769				\$4,380,769
	P-1	LRV BRAKE LIGHTS	\$300,000				\$300,000
	Q-PH1	INTERSECTION MONITORING SYSTEM (CAMERAS)	\$28,080				\$28,080
	PHASE 1A TOTAL		\$6,041,204				\$6,041,204
1B	J	EXCHANGE TO SCOTT	\$6,482,899				\$6,482,899
	PHASE 1B TOTAL		\$6,482,899				\$6,482,899
	TOTAL PHASE 1A, 1B		\$12,524,103				\$12,524,103
	C	CHIPPEWA TO HURON		\$5,335,050			\$5,335,050
	D	HURON TO MOHAWK		\$2,119,783			\$2,119,783
	E	MOHAWK TO COURT		\$5,735,682			\$5,735,682
	F	COURT TO CHURCH		\$7,171,672			\$7,171,672
	G	CHURCH TO SWAN		\$1,636,102			\$1,636,102
	H	SWAN TO SENECA		\$5,234,100			\$5,234,100
	I	SENECA TO EXCHANGE		\$1,875,935			\$1,875,935
	K	EAGLE		\$484,112			\$484,112
	L	MOHAWK		\$1,033,012			\$1,033,012
	R	WIND SCREENING ALLOWANCE (LOWER MAIN STREET)		\$54,000			\$54,000
	Q-PH2	INTERSECTION MONITORING SYSTEM (CAMERAS)		\$87,480			\$87,480
	PHASE 2 TOTAL			\$30,766,929		\$3,076,693	\$33,843,622
3	N	SCOTT STREET CROSSOVER			\$4,256,000		\$4,256,000
	PHASE 3 TOTAL				\$4,256,000		\$4,256,000
TOTAL PHASES 1, 2, 3						\$50,623,725	
CONSTRUCTION COST GRAND TOTAL							\$50,623,725

**ITEMS M AND P-2 WERE ELIMINATED FROM THE PROJECT SCOPE AT THIS TIME.

**ITEM O WILL BE EVALUATED FURTHER DURING THE FINAL DESIGN PHASES BEFORE ACCEPTING OR ELIMINATING.

CARS SHARING MAIN STREET PRELIMINARY CONSTRUCTION COST ESTIMATE - JULY 18, 2006

**REHABILITATION APPROACH - MODIFIED SCOPE (MINIMAL TRACKBED WORK)
CONSTRUCTION ESTIMATE 2006 DOLLARS**

BLOCK SEGMENT	ROADWAY PAVEMENT	PARKING PAVEMENT	SIDEWALKS	SIGNALIZATION/SIGNAGE/MARKINGS	CATENARY WORK	LRR SYSTEMS	STATIONS	BRIDGE PLATES	STREETSCAPE/LANDSCAPING	LIGHTING STREET / PEDESTRIAN	SAFETY AND SECURITY MEASURES	DRAINAGE, UTILITIES, VAULTS	M&PT, STAGING, MOBILIZATION	SUBTOTAL	CONTINGENCY (15%)	BLOCK SEGMENT TOTAL				
																2006 DOLLARS	2007 DOLLARS	2008 DOLLARS	2009 DOLLARS	
A	GOODELL TO TUPPER (634 ft)	\$168,336	\$88,247	\$197,822	\$109,500				\$250,060	\$114,525		\$103,000	\$82,519	\$1,114,009	\$167,101	\$1,281,111	\$1,332,355	\$1,383,599	\$1,434,844	
B	TUPPER TO CHIPPEWA (1297 ft)	\$688,838	\$112,118	\$340,960	\$274,500	\$661,720	\$250,000	\$70,253	\$355,168	\$227,950	\$241,000	\$152,910	\$287,433	\$3,662,850	\$549,428	\$4,212,278	\$4,380,769	\$4,549,260	\$4,717,751	
C	CHIPPEWA TO HURON (541 ft)	\$250,964	\$28,510	\$205,416	\$166,000	\$504,212	\$460,000	\$1,362,722	\$200,000	\$468,820	\$101,100	\$209,600	\$338,188	\$4,295,532	\$644,330	\$4,939,861	\$5,137,456	\$5,335,050	\$5,532,645	
D	HURON TO MOHAWK (528 ft)	\$266,701	\$67,466	\$178,558	\$166,000	\$493,152			\$225,960	\$93,950		\$69,000	\$145,963	\$1,706,750	\$256,012	\$1,962,762	\$2,041,273	\$2,119,783	\$2,198,294	
E	MOHAWK TO COURT (589 ft)	\$301,387	\$34,978	\$232,542	\$205,000	\$548,948	\$460,000	\$1,336,923	\$200,000	\$582,640	\$116,950	\$234,800	\$363,933	\$4,618,101	\$692,715	\$5,310,817	\$5,523,249	\$5,735,682	\$5,948,115	
F	COURT TO CHURCH (1014 ft)	\$439,643	\$102,372	\$373,823	\$329,500	\$945,048	\$460,000	\$1,302,789	\$200,000	\$719,750	\$189,250	\$246,800	\$465,318	\$5,774,293	\$866,144	\$6,640,437	\$6,906,054	\$7,171,672	\$7,437,289	
G	CHURCH TO SWAN (404 ft)	\$201,121	\$51,047	\$148,808	\$128,000	\$376,528			\$95,080	\$73,550		\$130,600	\$112,579	\$1,317,313	\$197,597	\$1,514,910	\$1,575,506	\$1,636,102	\$1,696,699	
H	SWAN TO SENECA (463 ft)	\$196,959	\$25,833	\$175,352	\$128,000	\$431,516	\$460,000	\$1,433,775	\$200,000	\$468,820	\$80,350	\$284,350	\$329,296	\$4,214,251	\$632,138	\$4,846,389	\$5,040,245	\$5,234,100	\$5,427,956	
I	SENECA TO EXCHANGE (471 ft)	\$194,173		\$126,656		\$438,972			\$76,224	\$79,600	\$400,000	\$65,500	\$129,290	\$1,510,415	\$226,562	\$1,736,977	\$1,806,456	\$1,875,935	\$1,945,415	
J	EXCHANGE TO SCOTT (804 ft)	\$309,690	\$89,445	\$274,193	\$307,000	\$749,328	\$460,000	\$1,463,538	\$200,000	\$560,370	\$158,350	\$231,350	\$416,461	\$5,219,725	\$782,959	\$6,002,684	\$6,242,791	\$6,482,899	\$6,723,006	
K	EAGLE (225 ft)	\$54,736	\$29,956	\$44,613	\$50,000				\$67,306	\$42,000		\$72,300	\$28,873	\$389,784	\$58,468	\$448,251	\$466,182	\$484,112	\$502,042	
L	MOHAWK (500 ft)	\$117,087	\$63,157	\$84,703	\$174,500				\$125,126	\$73,000		\$132,550	\$61,610	\$831,733	\$124,760	\$956,493	\$994,752	\$1,033,012	\$1,071,272	
SUBTOTALS		\$3,189,635	\$693,129	\$2,383,446	\$2,038,000	\$5,149,424	\$2,550,000	\$6,970,000	\$1,000,000	\$3,995,324	\$1,350,575	\$641,000	\$1,932,760	\$2,761,463	\$34,654,756	\$5,198,213	\$39,852,970			
INDEPENDENT ELEMENTS AND ALLOWANCES																				
M	CHURCH STREET CROSSOVER															\$3,500,000	\$3,640,000	\$3,780,000	\$3,920,000	
N	SCOTT STREET CROSSOVER															\$3,800,000	\$3,952,000	\$4,104,000	\$4,256,000	
O	DRIP IRRIGATION SYSTEM															\$400,000	\$416,000	\$432,000	\$448,000	
P-1	LRV BRAKE LIGHTS																	\$300,000	\$324,000	\$336,000
P-2	LRV SIGNAGE																	\$2,200,000	\$2,376,000	\$2,464,000
Q-PH1	INTERSECTION MONITORING SYSTEM (CAMERAS)															\$27,000	\$28,080	\$29,160	\$30,240	
Q-PH2	INTERSECTION MONITORING SYSTEM (CAMERAS)															\$81,000	\$84,240	\$87,480	\$90,720	
R	WIND SCREENING ALLOWANCE (LOWER MAIN STREET)															\$50,000	\$52,000	\$54,000	\$56,000	

CARS ON MAIN STREET

SUMMARY OF WORK ASSOCIATED WITH ITEMS LISTED IN ESTIMATE

ROADWAY PAVEMENT

- ◆ Minimal Trackbed Repairs consisting of the following:
 - Estimate developed without the benefit of a pavement condition study
 - Assumes repairs performed on every other transverse joint (existing joints spaced 5-foot o.c.). Assumes repair width of 4". Repair material to consist of rapid set polymer concrete.
- ◆ Sawcut of existing curb in parking areas
- ◆ Underdrain will be installed behind existing curb
- ◆ Full depth asphalt pavement, underdrain & curbing for parking areas, lanes around portal, Eagle Street & Mohawk Street
- ◆ Trench drain rehabilitation within trackbed
- ◆ Mill/2" asphalt overlay in 700 block with full depth asphalt pavement widening for parking lane along west side
- ◆ Full depth concrete pavement for side street crosswalks at intersections
- ◆ Includes bike lanes for 600 block

PARKING PAVEMENT

- ◆ Full depth asphalt pavement, underdrain and granite curb in new parking areas
- ◆ Includes parking and buffer areas along trackbed

SIDEWALK PAVEMENTS

- ◆ 4 inches of scored concrete and 4 inches of subbase
- ◆ Includes allowance for modification to vaults where there is a potential for impact
- ◆ 700 block includes concrete median
- ◆ Seneca to Exchange (HSBC Basement) assumes new sidewalk infill at existing bituminous pavement lanes. No adjustment made for possible lightweight concrete or HSBC Basement modifications options that may be required to support additional dead loads resulting from new sidewalk
- ◆ Sidewalk ramps and tactile strips

CATENARY WORK

- ◆ Includes removal of existing poles and installation of new poles in sidewalk areas along with all relocated catenary work described in Appendix H.
- ◆ Assumes splices for needed feeder poles.

LRRT SYSTEMS

Work generally includes all systems associated with the stations and train control. Work and assumptions are as follows:

- Passenger Information Displays (PIDS) – reuse existing sign panels
- Passenger Assistance Communication Equipment (PACE) – reuse existing device
- Public Announcement System (PA) – new equipment
- Closed Circuit Television (CCTV) – reuse existing equipment
- Traffic Intersection Request Priority "Loop" System (TRIPS) with Starter light for the LRT – new
- Fare Collection /Ticket Vending – reuse
- New Combined Housing for - PIDS, PA, PACE, CCTV, and TRIPS
- Station Power System Housing
- Wiring, conduit, housing for station systems
- Splicing of existing cabling which is assumed to be in good condition

STATIONS

- ◆ Station demolition costs with foundations removed below subgrade.
- ◆ New station shelter and platform.
 - Stainless steel frame
 - Translucent roof system
- ◆ Station lighting, electrical and roof drains.
- ◆ Furnishings
- ◆ Heated ramps for snow and ice

BRIDGE PLATES

- ◆ Stainless steel plate mounted to station platforms
- ◆ Hydraulic, automated mechanism interfaced with train control

STREETSCAPE/LANDSCAPING

Conceptual layouts of trees, planters and streetscape components were developed for estimating purposes. Layout of elements differ in station and non-station blocks. A general listing of elements for the two different approaches that have been applied to the overall project are as follows:

- ◆ **Station Blocks**
 - Planters with seating along the station boarding zones (approximately 14 per block)
 - Street trees spaced approx. 25 feet apart
 - Bowl planters at intersections
- ◆ **Non-Station Blocks**
 - Street trees spaced approx. 25 feet apart
 - Bowl planters at intersections
 - Mohawk and Eagle side streets treated under this approach

Other areas with unique conditions are noted as follows:

- 700 Block with planted median
- Area below I-190
- Area beneath HSBC Tower
- Lafayette Square and Roosevelt Square
- Planters and additional street trees adjacent to new stations
- Portal area planters, gateway features (clock etc.)

Furnishings provided at various locations throughout the project area include:

- ◆ Benches, trash receptacles, and bike racks
- ◆ 600 Block cost include portal wall screening
- ◆ Feature removals including steel arches (Auditorium and 600 block), “features” at Mohawk, Eagle and Kiosk removals
- ◆ Landscape irrigation system treated independently.

LIGHTING

- ◆ Includes installation of fixtures on catenary poles
- ◆ Includes new fluted poles for additional lighting in between catenary poles where required
- ◆ Includes new conduit, cabling and junction boxes

SAFETY AND SECURITY MEASURES

- ◆ Includes safety measures at the portal entrance and HSBC Tower
- ◆ Components include:
 - barrier systems
 - gates
 - delineation measures

DRAINAGE, UTILITIES, VAULTS

- ◆ Utility adjustments required specific to adjustments required for new pavements
- ◆ Utility Impacts due to proposed station construction (drainage, water, electric & phone Vaults and ducts and Gas lines that fall directly in the new footprint)
- ◆ New drainage inlets and piping connected to existing drainage system as required for new pavement areas and grading

MAINTENANCE AND PROTECTION OF TRAFFIC

- ◆ MPT costs based on 4% of total cost of work per block to account for measures at intersections as well as delineation and standard barriers along the work areas
- ◆ Additional cost for a temporary 6 foot chain link fence added into total cost as it is anticipated that additional means beyond orange plastic construction fencing will be required to delineate the work zone and keep pedestrians from crossing work zones
- ◆ No additional costs are attributed for temporary stations or LRRT impacts
- ◆ Night and weekend work assumed work within the trackbed

ENGINEERING AND CM COSTS

- ◆ Administration, engineering and construction monitoring costs are not included in the estimate, which are intended to convey anticipated construction costs only.

Appendix F

Reference Standards

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

REFERENCE STANDARDS

Geometric Design of Highways and Streets 2004 American Association of State Highway and Transportation Officials (AASHTO), Washington, DC.

Roadside Design Guide, 2006 American Association of State Highway and Transportation Officials (AASHTO), Washington, DC.

Manual of Traffic Control Devices 2003 American Association of State Highway and Transportation Officials (AASHTO), Washington, DC.

New York State Department of Transportation's *Highway Design Manual (w/various Design Chapter revisions)*

Official compilation Codes Rules and Regulations of the State of New York, *17 Transportation (B), 2005 (w/ revisions)* - (Also known as NYS MUTCD)

New York State Department of Transportation's *Engineering Instructions, Engineering Bulletins and Engineering Directives (EI' EB's and ED's)*

City of Buffalo Department of Public Works *Standard Specifications for Construction and Materials February 1, 1994*

Traffic Calming: State of the Practice, Institute of Transportation Engineers and the Federal Highway Administration, 1999

Americans with Disabilities Act *Accessibility Guidelines for Buildings and Facilities (ADAAG) Amended September 2002*

Architectural and Transportation Barriers Compliance Board's Part 1192 - Americans with Disabilities Act *Accessibility Guidelines for Transportation Vehicles (ADAAG) Amended September 2002*

Department of Justice Code of Federal Regulations *49CFR Part 37 Transportation Services for Persons with Disabilities Revised October 1, 2003*

Department of Justice Code of Federal Regulations *28CFR Part 36 ADA Accessibility Guidelines for Buildings and facilities Revised July 1, 1994*

USDOT Federal Transit Administration *Accessibility Handbook for Transit Facilities July 1992*

Highway Capacity Manual 2000, Transportation Research Board

Guide for the Development of Bicycle Facilities, American Association of State Highway and Transportation Officials (AASHTO), Washington, DC, 1991.

Track Design Handbook for Light Rail Transit, Transit Cooperative Research Program, Report 57 Transportation Research Board, National Research Council

**Final Design Report
Preliminary Design**

MAIN STREET MULTI-MODAL ACCESS AND REVITALIZATION PROJECT

Accessible and Useable Buildings and Facilities ICC/ANSI 1998.

Accessibility Handbook for Transit Facilities, Federal Transit Administration July 1992

Building Code : New York State Department of State; Albany , New York ;2002.

Design Rationale Report, LRRT Lafayette Station Modifications;
EI Associates: Buffalo, New York; 1995.

Greater Buffalo –Niagara Regional Transportation Council On Board Passenger Survey;
NU Stats;Austin,Texas2002.

Green Transportation-Tacoma’s Light Rail Link: Eco Structure April 2006.

Main Street Pedestrian Mall Summary of Economic Impacts; Harmon and Associates
Washington D.C.; February 1982.

The Queen City Hub - A Regional Action Plan for Downtown Buffalo; City of Buffalo;
Buffalo, New York 2003

Rail Transit Capacity Report 13, National Academy Press; Washington D.C. 1996

Niagara Frontier Transportation Authority Metro Construction Division’s *Design Criteria
Manual for Light Rail Rapid Transit*, August 1981.

Denver Regional Transportation District’s *LRT Design Criteria Manual*, Revised October
2000.

Code of Massachusetts Regulations – Architectural Access Board *521 CMR Section 18
– Transportation Terminals*

Appendix G

Public Information Meeting

Comment Summary & Responses

**MAIN STREET MULTI-MODAL ACCESS AND
REVITALIZATION PROJECT**

SUMMARIZED
COMMENTS AND RESPONSES
PUBLIC INFORMATION MEETING #1
FEBRUARY 1, 2006

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Response
Joseph Marcella 625 Main #9 Buffalo, NY 14203 jmarcella@chek.com	<ul style="list-style-type: none"> • Eliminate Theater District Station • Two lanes each way • Minimum sidewalk • Only Main St. resident/owners should have a say • No parking • Overall Great Idea 	Outside the scope of the project
J. Staton 28 Brookfield Lane Cheektowaga, NY 14227 No email	<ul style="list-style-type: none"> • Prefers lanes outside of trackbed • Trackbed sharing will increase train dwell time 	Only “Share The Trackbed Alternative” per EA considered. Traffic model did not predict increase in train dwell times
Joel Lippes 341 Franklin Street Buffalo, NY 14202 Jlippes@verizon.net	<ul style="list-style-type: none"> • Extend LRRT to Amherst • Open side streets between Washington and Pearl • Not a strong proponent 	Outside the scope of the project
Bea Militello – Bijou Grille 643 Main Street Buffalo, NY 14203 bea@bijougrille.com	<ul style="list-style-type: none"> • Access during construction • Construction time for each block 	Access will be maintained. Final construction phasing yet to be decided.
Alan Bedenko 9294 Via Cimato Dr. Clarence Center, NY 14032 abedenko@gmail.com	<ul style="list-style-type: none"> • Well designed streetscape • Strongly favors the project • Expand the LRRT system 	Expanding LRRT system not in scope

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Response
<p>Thomas Reagle c/o Picture This Market Arcade 617 Main Street Buffalo, NY 14203</p> <p>Picturethis21@hotmail.com</p>	<ul style="list-style-type: none"> • ADA access from all train cars • No parking meters • Existing trees should remain 	<p>ADA requirements will be met. No individual parking meters, but parking fee will be in place. All new landscape due to reconstruction.</p>
<p>E. Edward Deutschman 4485 Arondale Road Williamsville, NY 14221-6222</p> <p>eddeu@localnet.com</p>	<ul style="list-style-type: none"> • Controlled access to portal and at intersections • Sidewalk cafes • Traffic control for cars behind trains • No left turns • No overtaking of trains • In favor of project 	<p>Access will be controlled. Traffic control will be in place. Left turns will be considered, overtaking of trains will not be permitted due to shared lane concept.</p>
<p>Mark Casell 108 N. Shore Drive Alden, NY 14004</p> <p>Mark.Casell@am.jll.com</p>	<ul style="list-style-type: none"> • No parking meters, 1 hr parking • Bike lane • Minimum signs • Sidewalk cafe • Streetscape & more lighting 	<p>Parking for 2 hrs max. No designated bike lanes. Signs per MUTCD</p>

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
Kevin F. Yost Tower 3 Room 840-B PO Box S119 Buffalo State College Buffalo, NY 14213 YostK321@yahoo.com	<ul style="list-style-type: none"> • In favor of project • More trees/landscaping 	None required
Gregory P. Stein 228 Euclid Ave. Kenmore, NY 14217 gncstein@aol.com	<ul style="list-style-type: none"> • Car/train safety issues • Left turns • No overtaking of trains • Bike lane ? 	No designated bike lane. Safety will be a project priority.
Deborah Kane 69 Cary Street Buffalo, NY 14201 musessong@hotmail.com	<ul style="list-style-type: none"> • Favors the project • Means to generate traffic during PM and on weekends 	None required
Genco 600 Main Street City Centre	<ul style="list-style-type: none"> • No Casino 	Not in scope of the project
Betty Howell	<ul style="list-style-type: none"> • Favors project 	None required
Peggy Beardsley-Buffalo Place 671 Main Street Buffalo, NY 14203 pbeardsley@buffaloplace.com	<ul style="list-style-type: none"> • Favors special events, impact on special events due to project 	None required

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
<p>Seth C. Triggs PO Box 616 Buffalo, NY 14205</p> <p>sethtriggs@yahoo.com</p>	<ul style="list-style-type: none"> • Safety and environmental issues • LRRT dwell time • Separate car lanes • No left turns 	<p>Safety will be a project priority Draft Final EA has been prepared for the project and submitted to FTA for approval No increase in dwell time. Only Share the Trackbed option considered per EA. Left turns will be considered</p>
<p>Mark Galvin 6901 Erie Street #5 Derby, NY 14047</p> <p>(716) 947-5140</p>	<ul style="list-style-type: none"> • Favors steel/glass material for stations • More trees • Heated sidewalks • Favors project 	<p>None required</p>
<p>Brian Mahoney 96 ½ Crescent Ave. Buffalo, NY 14214</p> <p>Brian.Mahoney@invitrogen.com</p>	<ul style="list-style-type: none"> • Owns property at 9 Genesee Street • Loading zone 	<p>Designated loading zones will be provided.</p>
<p>Ronald W. Bates 282 Delaware Ave. Buffalo, NY 14202</p> <p>reprocraft@aol.com</p>	<ul style="list-style-type: none"> • Closed section near old Bon-Ton • Extend LRRT to Amherst • No catenary, eliminate tunnel 	<p>Not in the scope of the project</p>

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
Stephen P. Fitzmaurice One HSBC Center Buffalo, NY 14203-2897 spf@onehsbc.com	<ul style="list-style-type: none"> • Favors the project 	None required
James Bryant 378 Franklin Street Buffalo, NY 14202 No email	<ul style="list-style-type: none"> • Favors project • Parking • Public involvement 	None required
Joan Miller 144 Goering Buffalo, NY 14225 joanmiller60@aol.com	<ul style="list-style-type: none"> • Favors project • Parking • More Landscape 	None required
Chris D'Angelo – Comfort Suites/ TGIF 4225 Genesee Street Buffalo, NY 14225 Chris@dynamic-brands.com	<ul style="list-style-type: none"> • Sidewalk café preservation • Do not eliminate Theatre and Fountain Plaza stations • Favors the project 	Theater District Station is being consolidated with Fountain Plaza Station based on Advisory Committee recommendations.
Aldo and Sharon Ferrelli 600 Main Street, Unit 104 Buffalo, NY 14202 aslfer@adelphia.com	<ul style="list-style-type: none"> • More trees/landscape • Existing trees should remain • Seating benches • No cars along 500-600 block 	Parking spaces provided in the 500-600-block. Vehicular traffic will remain in the 500-600 blocks.

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
Rick Serra 465 Main Street, Suite 200A Buffalo, NY 14203 rserra@propark.net	<ul style="list-style-type: none"> • Favors project • Likes station design 	None required
Sheri and Greg Rehwoldt 600 Main Street, #704 Buffalo, NY 14202 sheri@rehwoldt.com	<ul style="list-style-type: none"> • Smart streetscape • More parking 	None required
Harold L. Cohen 600 Main Street, Apt. 1101 Buffalo, NY 14202 mdcohen@acsu.buffalo.edu	<ul style="list-style-type: none"> • Covered and heated sidewalks • Bring more businesses. • Eliminate stations 	Out of the project scope
Lynda Stephens* 266 Hartwell Road Buffalo, NY 14216 * Comments from Ms. Stephens were originally sent to Mr. Alan Taylor, Regional Director NYSDOT Region 5.	<ul style="list-style-type: none"> • Concerns regarding 2003 EA • Wants EIS for the project • Wants more public input • Safety issues for bicycle riders, pedestrians and vehicles • Payback of Federal Dollars for demolition of Mall features • Destruction of award winning streetscape for minimizing wind effects • Impacts on sidewalk vaults • Disruption during construction • Impact on Ellicott Street Project • Omission of designated Bike Path 	The 2003 EA was updated in 2005 The project was developed from the proposed Alternate from EA. EIS is not in the scope of this project. Safety issues will be addressed as part of this project. Mall features will not be a part of the proposed Urban Design. Sidewalk vaults are being evaluated Normal disruption due to construction. Safety reasons prohibit a designated bike path.
Gladys Gifford CRTC P. O. Box 1186 Buffalo, NY 14231 crtc@buffalo.com	<ul style="list-style-type: none"> • Separate lanes for cars • Cars trains safety hazards for pedestrians • Delay in LRRT operations • Prohibit left turns from Main St. • Traffic calming features 	Only “Share The Trackbed Alternative” per EA considered Safety of all is a project priority Left turns will be considered 15 mph design speed, other measures for traffic calming.

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
Rick Serra 465 Main Street, Suite 200A Buffalo, NY 14203 rserra@propark.net	<ul style="list-style-type: none"> • Favors project • Likes station design 	None required
Sheri and Greg Rehwoldt 600 Main Street, #704 Buffalo, NY 14202 sheri@rehwoldt.com	<ul style="list-style-type: none"> • Smart streetscape • More parking 	None required
Harold L. Cohen 600 Main Street, Apt. 1101 Buffalo, NY 14202 mdcohen@acsu.buffalo.edu	<ul style="list-style-type: none"> • Covered and heated sidewalks • Bring more businesses. • Eliminate stations 	Out of the project scope
Lynda Stephens* 266 Hartwell Road Buffalo, NY 14216 * Comments from Ms. Stephens were originally sent to Mr. Alan Taylor, Regional Director NYSDOT Region 5.	<ul style="list-style-type: none"> • Concerns regarding 2003 EA • Wants EIS for the project • Wants more public input • Safety issues for bicycle riders, pedestrians and vehicles • Payback of Federal Dollars for demolition of Mall features • Destruction of award winning streetscape for minimizing wind effects • Impacts on sidewalk vaults • Disruption during construction • Impact on Ellicott Street Project • Omission of designated Bike Path 	The 2003 EA was updated in 2005 The project was developed from the proposed Alternate from EA. EIS is not in the scope of this project. Safety issues will be addressed as part of this project. Mall features will not be a part of the proposed Urban Design. Sidewalk vaults are being evaluated Normal disruption due to construction. Safety reasons prohibit a designated bike path.
Gladys Gifford CRTC P. O. Box 1186 Buffalo, NY 14231 crtc@buffalo.com	<ul style="list-style-type: none"> • Separate lanes for cars • Cars trains safety hazards for pedestrians • Delay in LRRT operations • Prohibit left turns from Main St. • Traffic calming features 	Only “Share The Trackbed Alternative” per EA considered Safety of all is a project priority Left turns will be considered 15 mph design speed, other measures for traffic calming.

**PUBLIC INFORMATION MEETING NO. 1
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Comment	Responses
Comments provided by the Public on the Existing Condition Roll Map		
NA	<ul style="list-style-type: none"> • Provide lot of trees 	None required
NA	<ul style="list-style-type: none"> • Provisions for Erie St. connection from Main St. to Buffalo River 	Out of the project scope
NA	<ul style="list-style-type: none"> • Reduce excessive Church Street lane widths , difficult for pedestrians to cross 	Out of the project scope
NA	<ul style="list-style-type: none"> • Reconnect Mohawk and Eagle Streets 	Reconnecting Mohawk and Eagle Street is under consideration
NA	<ul style="list-style-type: none"> • No encroachment of public right-of-way (like City Grill) 	Under consideration
NA	<ul style="list-style-type: none"> • Provide more lighting 	Adequate street lighting will be provided as part of the design
NA	<ul style="list-style-type: none"> • Reconnect Genesee Street/ Huron Street to Main Street 	Out of the project scope
NA	<ul style="list-style-type: none"> • Provide drop off area for theatre patrons 	Drop area will be provided for the theatre patrons in the Theater District
NA	<ul style="list-style-type: none"> • Aesthetic and greenery around the portal 	Screening and landscaping of the portal area is part of the project.
NA	<ul style="list-style-type: none"> • Provide art around the Y at portal 	Art around the portal is under consideration
NA	<ul style="list-style-type: none"> • Reconstruct Goodell and Edward Street intersection with a roundabout for traffic safety 	Out of the project scope

**MAIN STREET MULTI-MODAL ACCESS AND
REVITALIZATION PROJECT**

SUMMARIZED
COMMENTS AND RESPONSES
PUBLIC INFORMATION MEETING # 2
AUGUST 8, 2006

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
Steven Joseph 671 Main Street Buffalo, NY 14203 sjoseph@buffaloplace.com	<ul style="list-style-type: none"> Consider single car trains running more frequently. 	<ul style="list-style-type: none"> NFTA operational issue which is beyond the scope of the design project.
Ken Swanekamp ECDEP 95 Franklin St. Buffalo, NY 14202 Swanekak@erie.gov	<ul style="list-style-type: none"> Construction cannot start soon enough! Walked to meeting in perfect weather, Main Street virtually deserted. 	<ul style="list-style-type: none"> No response required.
Donnie Morgan 667 Main Street Buffalo, NY 14203 stay@hostelbuffalo.com	<ul style="list-style-type: none"> Please incorporate "Theater" into the station name at Fountain Plaza. They have printed materials around the world listing Theater Station as destination for Youth Hostel. This is opportunity to deal with problems presented by alley between 665 & 667 Main Street. Perhaps alley could be used for Metro equipment and closed to foot traffic. Theater traffic could be directed through Market Arcade Theater, late-night club traffic could be directed around the police station. 	<ul style="list-style-type: none"> Comment will be conveyed to respective agencies for consideration. City of Buffalo would have to make a determination about the alley before any work can be considered for inclusion under this project.
Dianne Giliforte Studio Arena Theatre 710 Main Street Buffalo, NY 14202 dgiliforte@studioarena.com	<ul style="list-style-type: none"> Concerned about Motorcoach drop-off and pickup in front of Studio Arena Theatre (SA). Should be no parking zone in front of SA. Current design does not allow for any turnaround zone in front of SA. Coaches/cars would have to drive to Chippewa before being able to turnaround. Would be cumbersome and cause dire situations on performance nights at SA and Shea's as well as busy nights on Chippewa. 	<ul style="list-style-type: none"> Drop-off, loading and parking zones will continue to be coordinated with stakeholders throughout the design process. The limited distance between the portal and Tupper Street (approx. 100 ft.), the need to accommodate a pedestrian cross-walk and the transition around the portal where cars will merge into the shared lane restrict the ability to accommodate a bus turnaround. Further evaluation and coordination with stakeholders will continue throughout the design process.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
Veronica Ann Astrello 600 Main Street, #705 Buffalo, NY 14202 vaastrello@att.net	<ul style="list-style-type: none"> Finally! After many years of meeting, looks like there's a vision and a plan. Let's make this work, the faster, the better! 	<ul style="list-style-type: none"> No response required.
Kevin F. Yost 1474 Middle Road Rush, NY 14543-B YostK321@yahoo.com	<ul style="list-style-type: none"> Theater station should be moved to current parking area between portal and tower at intersection with Main and Pearl Streets. Portal should be moved closer to tower and Main/Pearl intersection. Raised median with retaining wall blocks and soil and mulch should divide both directions of Main Street instead of yellow line. Cars and light rail should be equal instead of current plans for cars first and light rail second. Bicycle lanes should run entire length. All downtown streets should be 2-way. Skyway should be replaced by tunnel combining Fuhrmann with Route 5 splitting into Pearl, Franklin, Delaware & Elmwood and doing away with Upper and Lower Terraces. Main Street bridge should go forward and Michigan Street Bridge should return. 	<ul style="list-style-type: none"> Would add significant cost to the project. Extensive study would be required before it could be considered. Would have significant impact on LRRT operations during construction. Beyond scope of project. A raised median throughout limits access for emergency vehicles and the ability clear lanes in the event of accidents or breakdowns. Space between the rails is limited which would not allow for a planted median. The design calls for the cars and trains to share the trackbed in a manner that will provide for safe operations for both cars and trains. Bicycle access was evaluated for the entire corridor length but could not be accommodated on station boarding blocks as the curb height and location must be retained for train access. Beyond the scope of the project. Beyond the scope of the project. Beyond the scope of the project.
Mary Elizabeth Ritz riszhotel@ovebtv.net	<ul style="list-style-type: none"> Terrific, modern, awesome idea! Expand subway to UB Amherst campus. Wait until ethanol is developed for cars, work hard to get that done as soon as possible. We need to keep up with other cities in US, Canada & Europe. Suggests checking out "An Inconvenient Truth" 	<ul style="list-style-type: none"> No response required. Beyond the scope of the project. Schedule must be responsive to availability of funding as well as the need for revitalization. No response required. No response required.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
<p>K. Bonl 230 Summit Avenue Buffalo, NY 14214</p>	<ul style="list-style-type: none"> • This plan seems designed to frustrate mass transit, rapid transit and anything other than vehicles. As a frequent train rider, sees nothing positive about the plan. Train trips will no longer be rapid as train will have to wait for red lights, left turning vehicles, cars stopped to load/unload (there aren't pull over places the length of the above-ground portion of LRRT). Why are super wide sidewalks being kept? Include separate lanes for cars rather than share track bed. • Wants to retain Theater Station (late night, winter weather, safety) – thinks people will drive instead of taking LRRT. • Disappointed in lack of bike lane after Chippewa. • Enormously disappointed with this plan. 	<ul style="list-style-type: none"> • The scope of the preliminary design is based on the preferred “Share the Trackbed” alternative selected during the development of the Environmental Assessment. Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. Design of the signalization system and traffic control measures will further address operational issues. • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block. • Bicycle access was evaluated for the entire corridor length but could not be accommodated on station boarding blocks as the curb height and location must be retained for train access. • No response required.
<p>Seth C. Triggs PO Box 616 Buffalo, NY 14205</p> <p>seth.triggs@verizon.net</p>	<ul style="list-style-type: none"> • Theater Station must be retained at least close to its current location. 	<ul style="list-style-type: none"> • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<ul style="list-style-type: none"> • The Share the Trackbed alternative will have detrimental effects towards public safety and transit efficiency (notes rise in oil prices necessitating high quality transit). Allowing left turns create delays for LRRT. • There is room for two traffic, two parking and two bike lanes around train lanes. • There is not effective separation between opposing lanes. Lack of traffic calming all but guarantees high-speed driving. Doubts drivers will stay at 15 mph • Inadequate protection of tunnel portal. 	<p>stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.</p> <ul style="list-style-type: none"> • Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. Design of the signalization system and traffic control measures will further address operational and safety issues. • The scope of the preliminary design is based on the preferred “Share the Trackbed” alternative selected during the development of the Environmental Assessment. • A raised median throughout limits access for emergency vehicles and the ability clear lanes in the event of accidents or breakdowns. Traffic control measures and enforcement will be key to safe operations as with any city street. The street will likely function as a destination rather than a collector or thoroughfare given the multi-modal use, narrow lanes and vehicle restrictions. Therefore, motorists that don’t want to travel at higher speeds will tend to use alternate routes. • Protection at the portal for motorists as well as for protection of the light rail system is a key concern that will be studied further before final measures are selected.
<p>Mike Quinlan 242 Irving Terrace Buffalo, NY 14223 quinnyarch@hotmail.com</p>	<ul style="list-style-type: none"> • Black (not green) catenary poles. • LCD displays indicating arrival of station meters- not individual meters. • Good job. 	<ul style="list-style-type: none"> • Poles will be carefully coordinated with the overall streetscape design elements. • Will evaluate further as part of the station design and information systems. • No response required.
<p>Alvin J. Schuster 175 Capen Blvd. Buffalo, NY 14226</p>	<ul style="list-style-type: none"> • This won’t work. A double yellow line will not stop vehicles from trying to pass trains. 	<ul style="list-style-type: none"> • A raised median throughout limits access for emergency vehicles and the ability clear lanes in the event of accidents or breakdowns. Traffic control measures and enforcement will be key to safe operations as with any city street.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<ul style="list-style-type: none"> • Concerned about LRRT schedules when vehicles are backed up from a traffic light and when accidents occur. • Eliminating Theater Station is horrible idea. • Left turns should not be allowed. • Cars should not share the trackbed. 	<ul style="list-style-type: none"> • Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. The proposed station locations are based on anticipated queue lengths at intersections to minimize the potential for cars impeding trains at the stations. Relocating the catenary poles outside of the trackbed and keeping the center of the road open will facilitate emergency vehicle access for clearing out potential accidents. Traffic monitoring will be enhanced with additional cameras throughout to help response times. • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block. • Left turns were accounted for in the traffic modeling which demonstrated ability to allow for these movements without significant adverse impact. Further analysis will be performed as part of the final design effort. • The scope of the preliminary design is based on the preferred "Share the Trackbed" alternative selected during the development of the Environmental Assessment.
<p>Daniel Leonard 1310 Delaware Avenue #108 Buffalo, NY 14209 djlzz@buffalo.edu</p>	<ul style="list-style-type: none"> • Extremely concerned about "mountable curb" – does not seem safe. -people waiting for train will be standing/walking where cars are trying to park. -a car climbing steep incline will accelerate at a much higher rate and then hit the brakes before sidewalk area. -cars attempting to mount curb will take longer-slows traffic & trains. 	<ul style="list-style-type: none"> • The curb would be sloped to be traversable by a car. Further study is needed to address what type of restrictions and enforcement would be necessary to make it safe for all. Intent is to use areas for parking when not used for boarding. Curbed planters would be used to create barriers at perimeter. Parking has been identified by stakeholders and community as a key part of the revitalization effort along with access and exposure.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<p>-oil and tire marks will remain in sidewalk/parking area-ugly. -will increase clutter in what should be a clean/uniform sidewalk area. -will cause confusion for people unfamiliar w/area. -how will it be regulated when parking is not allowed?</p> <p>All of these issues for extra 2-3 parking spots per car? Parking is not the most important thing in this project. If street is done correctly, people will find parking. Putting parking in forefront is extremely shortsighted. Viable cities sacrifice parking for good development, not the other way around.</p> <ul style="list-style-type: none"> Concerned about loss of Theater Station. 700 block is a hub for residential development. Current station is perfect for these people, Theater District and Entertainment District. Do not sacrifice for parking. 	<ul style="list-style-type: none"> The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.
<p>Ken Neufeld Studio Arena 710 Main Street Buffalo, NY 14202</p> <p>kneufeld@studioarena.com</p>	<ul style="list-style-type: none"> Need drop off zone in front of SA for patrons & deliveries. Need a closer turnaround for vehicles/buses dropping of patrons. 	<ul style="list-style-type: none"> Drop-off, loading and parking zones will continue to be coordinated with stakeholders throughout the design process. The limited distance between the portal and Tupper Street (approx. 100 ft.), the need to accommodate a pedestrian crosswalk and the transition around the portal where cars will merge into the shared lane restrict the ability to accommodate a bus turnaround. Further evaluation and coordination with stakeholders will continue throughout the design process.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<ul style="list-style-type: none"> • Too far to walk to Fountain Plaza station, especially in cold weather. 	<ul style="list-style-type: none"> • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.
Rhonda Avino 36 Highgate Ave. Buffalo, NY 14214 rhondaavino@hotmail.com	<ul style="list-style-type: none"> • In favor of project. • Plans look outstanding-loves the trees. • Hopes this happens-hope for a downtown again. • Great presentation! 	<ul style="list-style-type: none"> • No responses required.
Clifton Lund 33 Linwood Ave. Apt. 604 Buffalo, NY 14209	<ul style="list-style-type: none"> • Complete rail extensions to UB Amherst and to Dick Road. • Update or re-built downtown stations. • Cars sharing trackbed will cause problems. • Cost of re-designing the system to provide parking spaces does not seem to be cost effective. 	<ul style="list-style-type: none"> • Beyond the scope of the project. • Rebuilding the surface stations is included in the project scope. • Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. Design of the signalization system and traffic control measures will further address operational and safety issues. • The primary objective of the project is to return cars to Main Street to improve access. Providing parking is a key element in meeting this objective as identified in previous studies.
Bruce Brody bbrody@adelphia.net	<ul style="list-style-type: none"> • Thinks it's great putting cars back on Main Street. • Was in San Jose (Santana Row) which has outside restaurant/bar places in the middle of the median of the street. Barnes and Noble with a balcony and upscale stores remind him of what Main Street wants to be. • Check out www.santanarow.com 	<ul style="list-style-type: none"> • No responses required.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
Valerie Moliterno 262 Ruskin Road Amherst, NY 14226	<ul style="list-style-type: none"> • 204 parking spaces does not equate to the amount of money to be spent on this project. • As Main Street is re-awakening thinks construction will only set it back. • Landscaping is quite nice as are some of the rail stations. • Paving is already creative, why change it? 	<ul style="list-style-type: none"> • The primary objective of the project is to return cars to Main Street to improve access. Providing parking is a key element in meeting this objective as identified in previous studies. • Work will be staged in a manner to maintain access to properties throughout construction. All work started in a block will be completed during the same construction season to further limit the construction impact. • No response required. • The various types of materials used pose maintenance problems. It is important to develop a cohesive design that addresses the street as a whole when establishing the “right look” for Main Street.
Donna Kostrzewski 29 Silent Meadow Lane Orchard Park, NY 14127 donna@workingdowntown.com	<ul style="list-style-type: none"> • Simplify the train stations-they should be practically invisible and simple. • Too much \$ budgeted for station construction and landscaping. Reduce the amount of trees-architecture stands alone! • Can't wait for this to happen. 	<ul style="list-style-type: none"> • Intent is to reduce the size to full extent possible while maintaining accessibility to trains and providing improved weather protection. • Costs associated with the new stations are based on the reduced sizes. Utilizing materials that will minimize future maintenance is a key element of the station design. The stations will continue to be value engineered throughout the design process. The landscaping proposed is a key part of developing a beautiful street that will help bring people back to Main Street. Placement of trees to accentuate the architecture and not hide it will continue to be evaluated throughout the design process. • No response required.
Francis Moliterno 262 Ruskin Road Amherst, NY 14226 Fran33@inflowline.net	<ul style="list-style-type: none"> • Buffalo should focus on increasing residency and retail will follow. • New construction will disrupt a slowly improving Main Street-same old story. • The benefit of a few additional parking spaces and cars in the pedestrian area is not worth the cost. • Improve the existing rail line and concentrate on adding features to that system. 	<ul style="list-style-type: none"> • Beyond the scope of the project. • Work will be staged in a manner to maintain access to properties throughout construction. All work started in a block will be completed during the same construction season to further limit the construction impact. • The scope of the preliminary design is based on the preferred “Share the Trackbed” alternative selected during

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
<p>Gladys Gifford On behalf of Citizens Regional Transit Corporation (CRTC)</p>	<ul style="list-style-type: none"> • Not a good idea. • 3-D simulation was excellent. Planners and public are well-served by this effort to allow better understanding of project. • Simpler station design looks good. • Station Design fails to adequately provide for ADA access to rail cars. City requirement for a 2-foot setback from traffic lanes for fixed objects. Simulation shows retractable platform to bridge that gap and depends on NFTA maintenance to keep operational. • Track-bed should not be opened to vehicular traffic. A model for the whole street exists in front of Ellicott Square bldg. • Parking should not be allowed in vicinity of train stations, both in front and alongside boarding area. As a transit-oriented development consideration must be given to foot traffic and pedestrian congestion. Cars accessing and leaving parking spaces will impede flow of vehicular and rail traffic. • Design should prohibit all left turns, all times. Left hand turns impede flow of vehicles and trains, and delay while idling creates excessive air pollution. • Theater Station should be retained. Patrons of the Theater District depend on the rail and have their first positive experience using public transit because of the convenient access to the Theater District. 	<p>the development of the Environmental Assessment.</p> <ul style="list-style-type: none"> • No response required. • No response required. • No response required. • Setback of station is necessary for vehicular and pedestrian safety. ADA access to first train car will be maintained via the platform and bridge plate. NFTA is fully aware of the maintenance issues associated with the bridge plate. Costs were significantly more favorable for installing and maintaining wayside plates in lieu of train mounted bridge plates or lifts. • The scope of the preliminary design is based on the preferred "Share the Trackbed" alternative selected during the development of the Environmental Assessment. • Further study is needed to address what type of restrictions and enforcement would be necessary to make it safe for all. Intent is to use areas for parking when not used for boarding. Curbed planters would be used to create barriers at perimeter. Parking has been identified by stakeholders and community as a key part of the revitalization effort along with access and exposure. • Left turns were accounted for in the traffic modeling which demonstrated ability to allow for these movements without significant adverse impact. Further analysis will be performed as part of the final design effort. • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<ul style="list-style-type: none"> • For efficient use of public funds, order of work should be reversed (do the south section first, Theater District last) • Questions the process used to involve the public. The 2 info meetings held have not allowed public to express viewpoints verbally, as in a forum, to exchange views. • Project should be transit-oriented. 	<p>in this block.</p> <ul style="list-style-type: none"> • The timing of the south end is being coordinated with development currently being planned for that area which will not likely coincide with the intended start of construction in 2007. Also, the north end has been identified as high priority given the lack of activity on a daily basis. • Open format is common to the design phase. The EA process allowed for additional public input to help shape the scope. • No response required.
<p>Richard Olday 171 Parwood Trail Depew, NY 14043-1071 Member of CRTC</p> <p>raolday@yahoo.com 716-684-1604</p>	<ul style="list-style-type: none"> • Main Street is a transit corridor, automobiles are secondary to transit system and must not impede the operation and utilization of light rail. • Left turns should not be allowed, or at the very least, should not be allowed from 7 am to 7 pm. • Some type of barrier or median should be installed on blocks where there is a train station. Impatient motorists will want to pass sopped trains and cause accidents. Spotty law enforcement will not deter the impatient motorist. • The Theater Station should remain the Theater District Block. The new station could be located on the north side of Chippewa Street and would replace Fountain Plaza station. The parking shown along both sides of Main Street at the location could be relocated to Fountain 	<ul style="list-style-type: none"> • The scope of the preliminary design is based on the preferred "Share the Trackbed" alternative selected during the development of the Environmental Assessment. Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. Design of the signalization system and traffic control measures will further address operational issues. • Left turns were accounted for in the traffic modeling which demonstrated ability to allow for these movements without significant adverse impact. Further analysis will be performed as part of the final design effort that will evaluate restrictions as well. • A raised median throughout limits access for emergency vehicles and the ability clear lanes in the event of accidents or breakdowns. Traffic control measures and enforcement will be key to safe operations as with any city street. • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<p>Plaza block. Forcing theater patrons to use Fountain Plaza would be unacceptable, especially during winter (ie. Elderly and handicapped patrons), and would not longer be able to go the theaters, contrary to the idea of creating more accessibility.</p> <ul style="list-style-type: none"> • Concerned about maintenance of landscaping. 	<p>Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.</p> <ul style="list-style-type: none"> • Maintenance agreements will be established between the various agencies involved with the project.
<p>Paul Bond 304 Getzville Road Amherst, NY 14226-3542</p>	<ul style="list-style-type: none"> • Project team members and consultants capably responded to all questions. Impressed with displays and effort for meeting. 3-d simulation was especially interesting. • As a person with 42+ years of active railroad freight service, is somewhat biased with love affair with steel wheel on steel rail. • In favor of opening the street to traffic, but is concerned about the continued efficient operation and safety of the trains/train riders while sharing the trackbed and steel platforms that would be lowered when trains pull into stations. 	<ul style="list-style-type: none"> • No response required. • No response required. • Traffic modeling demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations. Design of the signalization system and traffic control measures will further address operational and safety issues. NFTA is fully aware of the maintenance issues associated with the bridge plate. Costs were significantly more favorable for installing and maintaining wayside plates in lieu of train mounted bridge plates or lifts.
<p>Steve Siegel 489 Ellicott St. Apt. 4 Buffalo, NY 716-622-9246</p>	<ul style="list-style-type: none"> • Theater Station should be kept. Many completed and under construction residences are in that area. These residents rely on the Metro Rail and use of the Theater Station. 	<ul style="list-style-type: none"> • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block. The expansion of bus service within the 700 block will be evaluated by NFTA Metro.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
<p>Caroline and William Duax ctduaxetal@aim.com</p>	<ul style="list-style-type: none"> For the sake of the theatres which are essential for Buffalo's growth, those attending the theatre, and those who do not drive cars, DO NOT close the Theatre Station. 	<ul style="list-style-type: none"> The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential properties and the hotel on the north side of Chippewa Street was not favorable due to owners, tenants and patrons. Placing the combined stations in the Fountain Plaza block is important given the large daily ridership represented in this block.
<p>Lynda Stephens 266 Hartwell Road Buffalo, NY 14216</p>	<ul style="list-style-type: none"> Questions the public involvement and EA process. Concerns expressed include: <ul style="list-style-type: none"> Safety issues for bicycle riders, pedestrians and vehicles. Payback of Federal dollars related to demolition of federally funded pedestrian/transit mall features. Destruction of award winning streetscape, including stations designed to minimize wind effects without creating wind tunnels. Impact of project on sidewalk vaults. Disruption during construction. Impact on nearby Ellicott Street project. Omission of a designated bike path. Does not want Main Street turned into parking 	<ul style="list-style-type: none"> Questions should be redirected to officials involved in the EA. Traffic control measures will be designed to address these issues to the full extent possible. Beyond the scope of the design process. Reduction of station sizes and improving weather protection in station areas are concerns raised by the public that are being addressed under the project. Sidewalk vaults will be accounted for in the final design. Work will be staged in a manner to maintain access to properties throughout construction. All work started in a block will be completed during the same construction season to further limit the construction impact. Maintenance and protection of traffic measures during construction will be considerate of other concurrent projects in the area. Bicycle access was evaluated for the entire corridor length but could not be accommodated on station boarding blocks as the curb height and location must be retained for train access. Proposed bike lanes will ultimately connect to the lower end via Pearl Street which is currently in the planning stages. Parking is one of the key elements in improving access.

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
	<p>lot.</p> <ul style="list-style-type: none"> • 3-D simulations showed very few pedestrians. Wasn't the point to bring more people to Main Street? • Consultants do not identify supporters of Shared Trackbed who are "lenders supporting local retailers" mentioned in paragraph "provide Vehicle Access to Adjacent Land Uses" of page 1-4 of May 2006 EA. • During the past 4 years, substantial development has occurred in downtown and nearby neighborhoods. Doubts that this project had anything to do with it. Disruption during construction will discourage new businesses from establishing themselves over the next several years. • Recommends a "Time Out" and rethinking of project. 	<ul style="list-style-type: none"> • Simulation demonstrated traffic during times when vehicular and light rail operations are at the peak which is 5:00 p.m. Pedestrian volumes are higher during the midday hours. • Questions should be redirected to officials involved in the EA. • See staging response above. • No response required.
<p>Giovanni D. Centurione 160 Utica Street Buffalo, NY g_centurione@yahoo.com</p>	<ul style="list-style-type: none"> • Love the look of the stations and landscape design. Wants work to start ASAP. 	<ul style="list-style-type: none"> • No Response required.
<p>Donna Berry B District BPD 695 Main Street Buffalo, NY 14203 dberry@bpdny.org</p>	<ul style="list-style-type: none"> • Bring Vehicles back to Main Street to begin a rebirth that should have happened long ago. 2007 is too long to wait. 	<ul style="list-style-type: none"> • No response required

**PUBLIC INFORMATION MEETING NO. 2
COMMENT SUMMARY AND RESPONSE SHEETS**

Name/Address	Summarized Comment	Response
<p>Ruth S. Brock 33 Gates Circle Buffalo, NY 14209</p>	<ul style="list-style-type: none"> • Distressed to hear that consideration is given to closing the Theatre Station. Feels access to Theatre District should be made easier not more difficult. Wants the station to be kept open. 	<ul style="list-style-type: none"> • The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.

**PUBLIC INFORMATION MEETING NO. 2
COMMENTS FROM LAYOUT SHEET**

COMMENT	RESPONSE
Near intersection of Main and Goodell - The sacrifice of valuable pedestrian space for 10' bike lane may be unwise	Bicycle access is a goal, which cannot be accommodated on station blocks. The plan as design will provide for a connection from areas north of the project to lower Main Street via a future Pearl Street bike lane. A sidewalk width of approximately 12 feet will be maintained in the most constrained areas.
700 Block – Fragmented bike lane may be ill conceived. Visually, drivers will see 16-foot wide vehicle lane, increasing speeds.	Flush curb, markings and materials will be used to help distinguish this area.
700 Block – Why limit landscaped median to entrance points? Consider expanding over more/most of block. Concerned about perceived vehicle lane width mid-block without median.	Similar to Main Street improvements constructed north of the project. Opening will improve access to parking and existing driveways.
700 Block – Parking reduced on this block?	Changed from angled parking to parallel parking as street will be two-way in lieu of the current one-way traffic.
700 Block – Consider keeping mid-block pedestrian crossing on such a long block with pedestrian island.	Flush median will not restrict crossing. City of Buffalo does not promote crossings where traffic control measures are not in place.
700 Block – 10' is wide enough for double row of trees in median. Consider expanding median to 12' to slow vehicle speeds.	11-foot travel lanes will help promote a calming effect. Median width proposed works with the placement of the bike lanes, parking lanes and existing sidewalk widths.
600 Block – Town Ballroom crowds will overflow into vehicle lanes without wider sidewalks than proposed here. Is parking a good idea around the portal?	Parking is not proposed directly in front of the Town Ballroom for this reason.
600 Block – Sidewalks far too narrow around portal. Bikes would be better served by 11' wide vehicle lane and wider sidewalks.	Pedestrian safety would be put at risk if bikes are directed onto the sidewalk areas.
600 Block – Pedestrian volumes could increase over time as underutilized buildings and vacant lots are redeveloped. Sidewalks should consider anticipated increase in volume.	The Shared Trackbed concept provides for the largest sidewalk width attainable.

**PUBLIC INFORMATION MEETING NO. 2
COMMENTS FROM LAYOUT SHEET**

COMMENT	RESPONSE
600 Block – Position control box so as to eliminate this narrow and dangerous walkway (between Hostel and Partnership building).	Relocation of control panel will be established in the final design.
600 Block – Retain Theater Station (2 notes)	The current northbound Theatre Station conflicts with the proposed transition around the portal. Shifting of the station within the Theatre block would conflict with potential parking and drop-off areas that are important to the Theatre operators and businesses. Positioning of stations in front of residential and hotel properties on the north side of Chippewa Street is not desirable due to noise concerns. Placing the combined stations in the Fountain Plaza block is important due to the large daily LRRT ridership represented in this block.
600 Block – Preventing cars in tunnel?	Lighting, signage, barriers and other measures will be considered during the final design.
600 Block – At portal area without parking – No trees? Street will look very stark with out them.	Planters are proposed in the sidewalk areas at each end of the portal. Visibility is important in the transition areas.
600 Block – Melanie’s is identified in Theatre Place.	No response.
500 Block (corner of Main/East Huron) – Lots of opportunity for improvements to this park, more greenspace.	Will be evaluated as part of the final design process.
At M&T Center, referring to the “Buffalo Savings Bank” label on the plan – Buffalo Savings Bank went out of business years ago.	Plan will be updated accordingly.
Overall – Median to prohibit passing.	A raised median throughout limits access for emergency vehicles and the ability to clear lanes in the event of accidents or breakdowns. Traffic control measures and enforcement will be key to safe operations as with any city street.
Overall – How will curb be low enough for cars to park, yet high enough for passengers to de-train?	Current sidewalk height will be retained in station boarding areas. Curb would be traversable (sloped) in the 3 rd & 4 th train car zones.

**PUBLIC INFORMATION MEETING NO. 2
COMMENTS FROM LAYOUT SHEET**

COMMENT	RESPONSE
Overall – Widen loading lanes.	The 3 foot buffer and 9 foot lane provides an effective width of 12 feet for vehicles that need it. Loading areas can be evaluated further during final design.
Overall – No traffic calming-straight lanes encourage speeding.	Narrow lanes proposed will have a calming effect. Street will function more as a destination than a thoroughfare.
Overall – Inadequate separation of opposing traffic lanes.	A raised median throughout limits access for emergency vehicles and the ability to clear lanes in the event of accidents or breakdowns. Traffic control measures and enforcement will be key to safe operations as with any city street.
Overall – Left-turning cars will delay trains, so will parallel parking.	Traffic modeling, which includes left turn and parallel parking maneuvers, demonstrates the ability for cars and trains to share lanes and maintain acceptable operational levels without significant impact on train operations.
Overall – Car emphasis reduces attractiveness to pedestrians.	Retaining wide sidewalks, enhanced crosswalks and the proposed streetscape improvements will improve attractiveness for all visitors.
Overall – Placing cars on trackbed instead of a separate lane will dominate clean, efficient light rail with fossil fuel use.	No response
Love the plans!	No response

Appendix H

Catenary Pole Study

CARS SHARING MAIN STREET

CATENARY POLE OPTIONS

I. OPTIONS TO CONSIDER:

The purpose of this analysis is to compare the options for integrating vehicular traffic into geometrically adequate lanes while maintaining the existing overhead simple catenary electrification system that powers the LRRT system. In reviewing the various conditions that exist along the trackbed as well as the components that makeup the overhead electrification system, it was determined that two primary options exist for retaining the system with the shared trackbed:

A. OPTION 1 – Move all Catenary Poles Outside of the Trackbed

B. OPTION 2 – Retain and Protect the Catenary Poles in the Trackbed

II. ANALYSIS OF OPTIONS

A. OPTION 1 - Move all Catenary Poles Outside of the Trackbed

1. **SCOPE** – This option involves removing all catenary poles and switches that exist within the surface trackbed section between Scott Street and the Portal at the north end of the surface section. New catenary poles would be installed on both sides of the trackbed at an offset on average of 30 feet each side of the centerline in order to clear underground utilities. The existing light poles are generally located at this offset which indicates that there is likely room to install that foundations needed for the catenary poles. Also, it is intended that the catenary poles would be designed to accommodate the installation of the sidewalk and street lighting fixtures, serving a dual purpose. Moving the poles outside of the trackbed will allow for the retention of the existing trackbed width of 23.5 feet which is important to maintain the existing train boarding interfaces at the sidewalks while providing the required vehicular travel lane widths of 11 to 12 feet identified in the Environmental Assessment. In addition to removing the existing poles and installing new poles outside of the trackbed, switches within the trackbed must be relocated outside of the trackbed, power feeds to the poles must be routed from the manholes in the trackbed to the new feeder poles outside of the trackbed and fixed, hydraulic and midpoint anchors must be incorporated into the new pole system outside of the trackbed. Specific scope elements associated with this option include:

- a. General Road/Trackbed width = 23.5'
- b. General Lane Width = 11.75'
- c. Remove approximately 43 catenary poles from Sta.41+82 to Sta.96+33 including:
 - (1) 15 Feeder Poles
 - (2) 10 Hydraulic Anchors
 - (3) 1 Fixed Anchor
 - (4) 1 mid-point anchor

CARS SHARING MAIN STREET

- (5) 4 Tie Wire Anchors
 - (6) Relocate switches at section breaks
 - (7) Pole removal and disposal
 - (8) Foundation removal to 4 ft. below finished grade
- d. Install a total of approximately 77 new catenary/light poles outside the trackbed (30 ft. from centerline) which includes:
- (1) Foundations
 - (2) Decorative Poles
 - (3) 3 support wires between each set of poles and associated connections
 - (4) 1 new tie wire pole for the ECH station crossover
 - (5) New anchors of various types
 - (6) New conduit and cabling from manholes to feeder poles
 - (7) Adjustment of hanger supports
- e. New special connections or poles will be required at the HSBC building that will require more detailed design and analysis during final design (an allowance will be included under the study based on the number of poles impacted –an additional 8 poles will be assumed to cover this area)
2. **PROS**
- a. Maximize usable lane width (center of trackbed to face of curb)
 - b. Maintain existing train boarding conditions (curb/sidewalk)
 - c. Eliminate object hazards in center on road
 - d. Consolidate facilities (catenary and lighting poles)
 - e. Facilitate maintenance (snow removal not limited by objects in road)
 - f. Maximize view down center of road
3. **CONS**
- a. Additional catenary support wires (minimal impact on visual environment as cantilever arms and pier protection will not be required)
 - b. Limitation on catenary pole foundation placement due to utilities

CARS SHARING MAIN STREET

4. COST CONSIDERATIONS

ITEM	UNITS	QUANTITY	UNIT COST	TOTAL
1. Catenary Pole & Foundation Removal	EA	43	\$10,000.00	\$430,000.00
2. New Catenary Poles, Foundations & Span Wires	EA	85	\$30,000.00	\$2,550,000.00
3. New Electrical Feeds	EA	15	\$20,000.00	\$300,000.00
4. Hanger adjustments and reconnection of catenary system	LS	1	\$860,000.00	\$860,000.00
5. Switch relocation	EA	4	\$20,000.00	\$80,000.00
6. Tensioners & Anchors	LS	1	\$70,000.00	\$70,000.00
SUBTOTAL				\$4,290,000.00
20% Contingency				\$858,000.00
TOTAL				\$5,148,000.00

Notes:

- Above Costs do not include lighting fixtures as lighting is required under each option; however, the pole costs do reflect the net cost of combining catenary and light poles under Option 1.
- Overall project associated costs for mobilization, M&PT, phasing and incidentals are not included in this estimate as it is intended to provide a comparison between the two options.

B. OPTION 2 - Retain and Protect the Catenary Poles in the Trackbed

1. **SCOPE** – This option involves retaining the catenary poles in the center of the trackbed, providing concrete median to direct traffic away from the poles, relocating poles away from intersections where conflicts occur and providing energy reducing impact cushion at the poles. The useable lane width would be reduced to 10'-3" as the median would occupy the center 3 feet of the trackbed. Specific scope elements associated with this option include:
 - a. Road/Trackbed width = 23'-6"
 - b. Lane Width = 10'-3"
 - c. Relocate approximately 12 catenary poles at intersections by installing new poles outside the track bed on each side at these locations
 - d. Installation of 3 foot wide continuous concrete median with breaks at intersections, poles and electrical manholes
 - e. Relocation of switches at the section breaks
 - f. Electrical work associated with feeder pole relocations
 - g. Reconnect catenary wires at relocations, hanger adjustments

CARS SHARING MAIN STREET

2. PROS

- a. Minimize catenary pole relocations
- b. Maintain existing train boarding conditions (curbs/sidewalks)

3. CONS

- a. Barrier in road which impacts maintenance, safety and visual environment
- b. Snow removal difficulty on median
- c. Reduced lane width, less than the desired 11 feet recommended in the EA.

4. COST CONSIDERATIONS

ITEM	UNITS	QUANTITY	UNIT COST	TOTAL
1. Precast Concrete Median	LF	4000	\$70.00	\$280,000.00
2. Catenary Pole & Foundation Removal/Relocation	EA	12	\$83,000.00	\$996,000.00
3. Impact Cushion	EA	48	\$10,000.00	\$480,000.00
4. New Electrical Feeds	EA	10	\$10,000.00	\$100,000.00
5. Switch relocation	EA	4	\$20,000.00	\$80,000.00
SUBTOTAL				\$1,996,000.00
20% Contingency				\$399,200.00
TOTAL				\$2,395,200.00

Notes:

- Above Costs do not include lighting fixtures as lighting is required under each option
- Overall project associated costs for mobilization, M&PT, phasing and incidentals are not included in this estimate as it is intended to provide a comparison between options.

Appendix I

Safety and Security Measures

SAFETY AND SECURITY MEASURES

Fabricated Vehicle Barrier Types and Effectiveness

The only barrier type considered and evaluated for the “Cars Sharing Main Street” project is what is referred to as the “fabricated vehicle barrier.” The other systems of barrier types are “natural and cosmetic barriers,” which utilize site topography, landscaping and other similar elements to provide security. This latter barrier is totally inappropriate for this project’s use.

Given the unique and specific issues related to the prevention of vehicles from entering the portal for access into the subway system, while at the same time allowing light rail vehicle (LRV) access, the system type has to be ‘positive control’.

The area under the HSBC office tower may also require similar effective control measures to ensure that motor vehicles do not use the track bed area under the tower. The system could also be expanded to include both inbound and outbound lane areas at special security alerts.

Summary information on the types of barriers, capital cost, annual maintenance, etc. can be found on the *Barrier Comparison Chart* prepared by URS, which follows this section.

Types of Fabricated Barriers

The types of fabricated vehicle barriers include:

- Concrete (“*Jersey*”)
- Portable water/sand-filled
- Chain link/gate reinforcement
- Cable
- Drum and cable
- Dragnet
- Bollard (fixed and hydraulic)
- Removable nuisance
- Guide rail
- Traffic control island
- Motorized barricade
- Drop arm beam barrier (typical highway-railroad crossing gate)

- Hydraulic barricade
- Electronic barrier gate
- Tire penetrating
- Portable roadblock Concrete Barrier (*“Jersey Barrier”*)

Barriers can be erected from either pre-cast tongue and groove sections or cast in place with special concrete-forming equipment. These barriers can be used around a fixed site as a partial or full perimeter vehicle barrier. Barriers can also be arranged to direct and slow traffic flow into a site. This provides any security personnel more time to react to a potential threat.

Portable Water/Sand-Filled Barriers

Plastic water or sand-filled barriers can be effective, as well as being easily moved without the need for heavy equipment.

Chain Link Gate Reinforcement

Wire ropes are fastened to gates and anchored on either side of the gate. For a relatively weak gate, the reinforcement transfers the force of a vehicle impact to a more substantial anchor system. It can be used on many different gate or portal applications.

Cable Barrier

Cable is fastened to each post with U-clamps at a height of 30-inches and is periodically anchored. The cable is typically 3/4-inch diameter or larger aircraft cable mounted between chain link fabric and upright posts. The barrier prevents light vehicles from crashing through a standard chain link fence. One disadvantage is that the cable can be covertly cut.

Drum and Cable Barrier

Standard 55-gallon drums are filled with dirt, rock or concrete - weighing about 900 to 1,200 pounds - attached by a 3/4-inch aircraft cable to another drum or fixed object. This type requires minimal setup time and expense. This barrier can be a cost-effective application since empty storage drums, dirt and rock are readily available.

Dragnet

This consists of a chain link "net" assembly with arresting cables attached to an energy absorber that is attached to the anchoring system. In the 'open' position, the dragnet is suspended above the access point. When a vehicle hits the dragnet in the 'closed' (dropped) position, the energy from the impact is transferred through the arresting cables to an energy absorber that brings the vehicle to a controlled stop.

Bollard

A bollard is a post made of concrete, stainless steel, steel, aluminum, cast iron, or other durable material, that creates an aboveground obstacle. Bollards can be fixed or retractable. At the high end, bollards are constructed to completely stop most vehicles.

Removable Nuisance Barrier

A 3-inch pipe driven into the ground and fastened with $\frac{3}{16}$ -inch coil chain is used to channel traffic and create marked isolation zones around sensitive areas, equipment, and buildings. It can be set up and removed quickly and easily.

Guide Rail

Standard highway guide rail or median barriers, cable, W-beam, or box beam guide rails are used as a perimeter barrier. They are not designed to prevent head-on penetrations but can immobilize a lightweight vehicle attempting an intrusion.

Traffic Control Island with Vehicle Barriers

Standard guard post, with two automatic gates, a custom base, platform curb assembly with three pass-throughs, and 16 barrier posts provide protection for security personnel stationed at a vehicle entrance.

Motorized Barricade

This refers to a steel barricade with standard height of 13-inches, and a maximum height of 30-inches. Several activation options are possible, such as by remote switch or card reader. These

barricades provide a steel barrier that can be deployed to close off vehicle access in approximately three (3) seconds.

Drop Arm Beam Barrier

This type of a barrier is typically found at at-grade highway/railroad crossings. The arm, generally fabricated from aluminum material, which can be fabricated to varying lengths, includes flashing red lights on top of the gate when the gate is in the “down” position. A track circuit of an approaching/departing train controls the operation of the barrier. The barrier arm also includes reflective tape and/or paint for visibility warning in addition to the red lights.

Hydraulic Barricade

Upon major impact, the lifting mechanism absorbs the shock. In emergency situations, a steel barricade closes off vehicle access in about one (1) second.

Electronic Barrier Gate

Chain link gates used for vehicle entrances with a remote switch, numerical code, or card reader activating electronic barrier gates.

Tire-Penetrating Traffic Barrier (1-Way Tire Treadles)

A row of $\frac{3}{8}$ -inch steel teeth that are unidirectional, spring-loaded, are embedded in the road. The barrier punctures the tires of an intruding vehicle, while allowing passage of vehicles in the opposite direction.

Portable Roadblock Tire-Puncturing Device

Hollow stainless steel spikes mounted on aluminum scissors action arms expand to stretch across a vehicle access. Anchors hold the scissors in place. The system expands to cover 21-feet and folds into a case weighing 35-pounds. When an intruding vehicle passes over the system, the spikes embed into the vehicle’s tires and detach from the aluminum frame. This opens several "tubes" which cause rapid uniform deflation and prevent the holes from sealing. Since the air loss is uniform from all times, the operator is more likely to maintain control of their vehicle. These devices are most effective against light vehicles with standard $\frac{3}{4}$ -inch thick rubber tires.

Vehicle Barrier Selection and Implementation Considerations

This section provides information on:

- Barrier selection considerations
- Implementation issues in selecting barriers
- Crash performance data for active and passive barriers (see also *Barrier Comparison Chart*)

Barrier Selection Issues

Threat /Desired Use

Select the level of security that is required for a particular facility that is based on a threat and vulnerability assessment. Barriers can be used to protect against several common aggressor tactics including: bombs in moving vehicle, bombs in stationary (parked) vehicle, or forced-entry attacks.

Degree of Protection/Crash Rating

Determine the degree of protection (range of physical restraint) required. To accomplish this, knowledge of the setback, potential vehicle speed, potential vehicle approach angle, vehicle weight, and size of explosive package is required. Table-1 (at end of this section) lists test results of different types of active and passive barriers. For a list of specific make/models of Department of State (DOS) and Department of Defense (DOD) certified anti-ram vehicle barriers, see the attached listing on the pages at the end of this section. Refer to the following documents for a list of standards and requirements that a potential product must satisfy to become qualified: Department of State (DOS) standard, SD-STD-02.01 (latest revision) –*Specification for Vehicle Crash Test of Perimeter Barriers and Gates*, and 12 FAH 5 –*Foreign Affairs Handbook – Physical Security Handbook*.

Barriers are tested and certified to perform to specific federal criteria (a specific level of anti-ram protection). In selecting barriers, it is important that NFTA security engineers consider the capabilities of these systems to protect against the threats specific to the protected facility. For crash-rated barriers, the weight and speed of the crashing vehicle are specified as well as the “allowed movement” of the barrier upon impact. There is a wide range of weights and speeds based on anticipated threat and physical approach.

Table 1. Tested Barrier Design – Test Results

		Vehicle		Protection Level (0-10)
		Weight	Speed	
Passive Barrier Test Results	Concrete Filled Steel Bollards	4,500	30	1
	Jersey Barrier	4,000	50	2.6
	Straight Retaining Wall	15,000	30	3.6
	Sloped Back Retaining Wall	15,000	40	6.4
	Concrete Planter / Retaining Wall	15,000	50	10
Active Barrier Test Results	Cable - Beam Barrier	10,000	15	0.6
	Retractable Bollards	15,000	30	3.6
	Portable Barriers	15,000	40	6.4
	Drum Type Barriers	15,000	50	10
	Sliding Gate	15,000	50	10

Source: Military FM 5-114

Passive vs. Active

Passive barriers can be used at entry points if traffic flow is restricted or rarely used. Passive barriers are normally used for perimeter protection.

Portability

What is involved if the barrier needs to be moved/repositioned? Some barriers are massive and heavy, requiring the use of heavy equipment for placement. Once placed, these barriers can only be

moved by bringing in heavy lifting equipment, and cannot be quickly changed to allow access status for authorized vehicles. If portable, how easy is the barrier to carry, transport, stack, store, and put together/interlock? What is the time needed to deploy?

Width / Load Capacity

Are the appropriate widths available to fully protect while allowing passage of almost every type of vehicle, including LRV and NFTA maintenance vehicles?

Barrier Activation Mode

For high traffic entries, vehicle barriers are normally open and closed only upon detection of a threat. For “low flow” or “high threat” conditions, barriers are normally closed in order to stop vehicle flow and are lowered only after authorization has been approved. For automated vehicle access systems the barrier should automatically return to the closed/protected position once a sensor has detected vehicle passage and should not allow tailgating. Whether the barrier can be locked in the up or down position should also be noted.

Access Control Options

Control for vehicles can include either automated or semi-automated access control, or manual access control. In automated or semi-automated access control, the driver of the vehicle (authorized motor vehicle or LRV) will use a machine-readable device or special pavement inductive loops to open the barrier. Ensure that the barrier selected can be operated by a variety of control systems to satisfy current and future needs, including needs for card and proximity readers, for keypads, for inductive loops, and for intercom. The ability to operate the system locally and/or by remote control should also be considered in the selection process.

Compatibility with Other Security Components

Active barriers should be compatible with other security equipment installed at the site (IDS, CCTV, etc.) and with the available power source.

Operation

Barriers can be operated manually, electrically, pneumatically, or hydraulically. Can the system operate individually and in groups? Is there a manual override? Can the system work in manual operation in the event of power failure? Barrier direction should be instantly reversible at any point in its cycle from the control station(s).

Consider Options / Alternate Approaches

Options exist for reconditioning, refurbishing, or converting existing barriers. It may also be possible to initiate an evolutionary plan in which the perimeter is progressively covered or where the entire perimeter is covered with something that can evolve to a higher level of protection over time. The potential for making site modifications (e.g., relocating facility elements) that would make a vehicle barrier unnecessary or a lesser-rated barrier acceptable should be assessed.

Barricade Speed / Response Time

The barrier system must contain sufficient time delay after activation to allow the vehicle to enter or exit the parking area.

Cycle Time/Pass-through Rates

Ensure that the device pass-through rate is consistent with the desired vehicle processing (3 to 15 seconds is suitable for most requirements).

Environment

Not all barriers are suited to all locations. Barrier components may require protection from excessive heat/cold, dirt, humidity, sand, salt, snow, ice, grit high water table, or require additional and continuing maintenance.

Reliability / Maintenance

Reliability is an important factor in selecting active barriers. Most manufacturers offer maintenance contracts. If a facility requires an active vehicle barrier, can the company selected provide adequate support service. Will it require painting and is it resistant to corrosion? Know what, where, when,

and how maintenance will be done. Evaluate the system's failure modes to determine that the barrier will fail in the predetermined position (open or closed) based on the security and operational requirements. Backup generators or manual override provisions are needed to ensure continuous operation during power failures or equipment malfunction. Reliability and maintainability data are available from most manufacturers.

Safety Options / Features

Active barrier systems are capable of inflicting serious injury or death, even when used for their intended purposes. Warning devices (visible colors and patterns, reflectors, lighting, warning lights, and safety signals) should be used to mark the presence of a barrier and enhance its visibility to drivers. Vehicle detector safety loops and road plates checkered for good traction would also enhance safety.

Mounting / Foundation Requirements

Consider the costs of site work for barrier mounting or required foundations:

- *Surface Mounted* – quick installation in difficult locations such as parking structure ramps or areas with sub-surface drainage problems.
- *Shallow Foundation* – sub-surface conditions that negate extensive excavations and obviate the concerns of interference with buried pipes, power lines, and fiber optic communication lines; reduces installation complexity, time, materials, and corresponding costs.
- *Sub Surface* – can require extensive excavations and the need to work around buried pipes, power lines, and fiber optic communication lines

Aesthetics

What range of visual dissonance is acceptable? An attractive appearance is usually desirable, but can contribute to the cost. The aesthetic components include color, texture, shape, and live material (plantings).

Liability

Liability issues resulting from death or injury due to normal operation or inadvertent use/ malfunction should be considered.

Budget

What range of financial resources is available? In addition to the actual cost of the barrier product, whether purchased or fabricated on site, there may be freight, placement, equipment rental, utility modification, site-work, clean up, or other related expenses. Reliability, availability, and maintainability requirements will affect the overall cost of the system.


Barrier Implementation Issues

- Locate barrier support equipment (e.g., hydraulic power, generator, etc.) on the secure side to lower the threat of sabotage.
- Tamper switches should be installed on all barrier access doors, controllers, and hydraulic systems. Tamper switches should be connected to a central alarm station.
- Mark active barriers once they are installed and channel traffic away from the system.
- Design barriers installed in clear zones so that they will not provide a protective shield or hiding place.
- Consider the use of barriers to stop vehicles from entering the wrong way via exit lanes.
- Ensure that buttresses, counterweights, and road plates do not obstruct authorized pedestrian or vehicular traffic.
- Plan for the appropriate use of safety equipment, such as traffic lights, inset warning lights, appropriate signage (“Stop”, “No Entry”, or “Warning”), and safety buffers. Use clear signage and traffic control lights with active barriers.
- Provide staff training to prevent injury, reduce liability, and prevent equipment damage caused by improper operation.

Crash Performance Data

The following diagrams showing crash performance data for a variety of passive and active barriers Data is from *Military Field Manual FM 5-114*.

Figure 1. Passive Vehicle-Barrier Capabilities



Reference: Military FM 5-114

Reference: USDOT, Transit Security Design Considerations, FTA Office of Program Management, FTATRI-MA-26-7085-05, DOT-VNTSC-FTA-05-02

Barrier Recommendation

The preliminary recommendation would be for a horizontal beam barrier similar to the one manufactured by Performance Development Corp. or a retractable bollard by Robotic Security Systems, Inc. (see number 3 and 16, respectively, listed on the *Barrier Summary*). Both have a K12 rating, able to repel high-speed (> 50 mph) assaults with 3-foot, or less of penetration. The estimated installed cost for a single unit is \$31,500 and \$64,000, respectively.

Either barrier type would be normal in the “up” position, going to the “down” position when an LRV crosses over an in-pavement loop on the approach, and returning to the “up” position when the LRV crosses over another loop on the departure. There are other system control alternates that may be appropriate, but this is dependent on the electronic interface between the LRV and the barrier.

However, please note that type of barrier ultimately selected needs to have focused discussion with the NFTA. If the barrier is such that harm could be caused to LRV passengers, then the system needs to be designed as close to vital as possible. It must be considered not from the standpoint of what happens if it does not work, but rather what would happen if it failed at the worst possible time. Would it damage or derail the LRV vehicle? If so then, the ability to detect and control this device must be designed with vital parts and methods.

Estimated Cost

Considering that 4 units would be required at the HSBC tower, and 2 units at the LRRT portal, the estimated capital cost is \$189,000 for the horizontal beam barrier and \$384,000 for the retractable bollards. For programming purposes, it is recommended that \$400,000 cost be used as the 2006 capital construction cost.

A *Barrier Comparison Chart* follows this text section, which summarizes the various individual types of barriers that could be considered, based upon operational and safety, and the desired level(s) of threat security.

Appendix J

APTA PEER REVIEW

APTA PEER REVIEW

At the request of the NFTA, the American Public Transportation Association (APTA) participated in a PEER REVIEW of the Preliminary Design for the project.

Meetings were held in early August of 2006. A debriefing provided by APTA members was presented to the Technical Committee. The following power point pages outline issues and comments discussed. A final report will be prepared by the APTA participants and presented to the NFTA. Recommendations associated with the final APTA Peer Review Report will be addressed in the Final Design Phase of the project.

APTA PEER REVIEW
for
Niagara Frontier
Transportation Authority

LRT/ Mixed Traffic Design



August 9, 2006

Peer Review Panel

- * Richard Clarke
Project Director- South East Corridor
RTD- Denver
- * Jeff LaMora
Rail Service Project Administrator
Utah Transit Authority
- * Fred Wong
Manager- LRT
Calgary Transit
- * Observer Participants:
John Jensen and Abdol Nouraeyan
City of Ottawa
- * Greg Hull
Director- Operations, Safety & Security
APTA (Staff Advisor to the Panel)



Introduction

The APTA Peer Review Panel, was convened at the request of Walter Zmuda, Director, Surface Transportation, Niagara Frontier Transportation Authority (NFTA), to assist the organization in reviewing the planned mixed traffic design for its LRT operations.

The observations and recommendations provided through this Peer Review are offered as an industry resource to be considered by the NFTA for supporting safety and operations efficiencies within its LRT service.



Peer Review Focus

At the outset of the peer review, the Panel was requested to focus on a new transportation design that would restore traffic to an LRT corridor on Main Street after an absence of mixed traffic for 20 years.

The NFTA requested the Panel to provide comment to a series of questions regarding this new design for LRT/ traffic interface as well as related operational issues.



Question # 1

Estimated impact on delay of trains is approximately 1 minute in each direction or 2 minutes round trip. If crossover is moved south of Scott St. additional time will be required for recovery. What impact will this have on service and operating costs? Are delays anticipated realistic?



Question # 1- Panel Comments

- If the crossover is moved to the south of Scott Street, recovery time will be reduced
- The anticipated delays may not be realistic as there is no actual historical data available
- The cumulative effect of all the potential schedule impacts (left hand turns, right turns affected by pedestrians, vehicular parking and drop offs, taxis, valet parking) will all add to schedule delays and variability of delay
- While in ideal conditions, a one minute delay may occur, less than ideal conditions will not be infrequent



Question # 1- Panel Comments

- From a scheduling reliability perspective, more than one minute should be added. Currently nine minutes of layover at each end is provided. The additional buffer time should be used from this current layover time.
- The annual operating cost of one additional trainset may be the worst case scenario.



Question # 2

Trains may have to double stop if cars are waiting for traffic light, thus preventing trains from pulling up to platform. May also cause delays to cars following the train stopping in the station. As there are only two lanes of traffic, no passing will be permitted for cars. What operations or safety issues could be experienced?



Question # 2- Panel Comments

- Invariably, motorists will take chances when delays are incurred.
- A double solid line will be needed. Additional considerations can include;
 - A hefty fine for passing a train
 - Establishing a Fire/Life Safety Committee to review such safety issues
 - A warning sign at the rear of the train
 - Limit left turns
 - Public outreach
- Policing blitzes will be necessary

Question # 2- Panel Comments

- Contingency plans for short and lengthier delays for various possible incidents will need to be developed (on-board emergency, vehicle accidents, mechanical problems, longer term reverse running requirements)
- Consideration should also be given for a crossover at a Main Street mid point



Question # 3

Additional train delays may be expected from vehicles stalled on the track bed or emergency situations such as ambulances and fire trucks parked on the track bed. Delivery vehicles and taxi's just dropping off packages/people could cause delays to trains and cars as there is no ability to go around stopped vehicles. What operations or safety issues could be experienced?



Question # 3- Panel Comments

- See comments to Questions # 1 and 2



Question # 4

May not have coordinated traffic signals for adjacent streets, which potentially could backup traffic across the tracks, thus delaying trains. This occurs in the current mode of operation mostly during PM peak. What operations or safety issues could be experienced?

Question # 4- Panel Comments

- There is a need for active monitoring and control (NITTEC)..
- Ops Center should be able to monitor via CCTV
- State of the art traffic control systems should be considered..
- Consider signage applications such as “ Do Not Stop On The Tracks” ..
- Review potential for priority sequencing..
- Consider public awareness & enforcement..



Question # 5

Bridge plate design for high-level boarding. Any experience with bridge-plate operation or design and what impact does the weather play in its reliability? Consideration being given to putting a sign at the entrance to the high-level area suggesting that this is for the convenience of those who require it and discourage those who are able-bodied enough to climb the stairs. Apparently another property has done this. Any experience with this?



Question # 5

- UTA, Denver and Calgary have experience with bridge plates from the vehicle
- Applications from the vehicle are very costly
- From the Panel's perspective, the planned high level boarding set-up appears to be a good solution. Regular testing, maintenance, and quick manual back up will be necessary
- Signage for limiting the use will be needed and may also require public outreach ..
- Current observable rider practices indicate frequent use by regular riders



Question # 5

- The provision of a covered area of the station will encourage regular riders to use the ramp..



Question # 6

Parallel parking in station areas. What is the safe clearance from the door/steps of the LRV to a fixed object such as a parked car? Any safety issues with passengers getting on/off trains and going between cars?. Passengers will wait for a train in this same area. Any experience with mountable curbs?

Question # 6- Panel Comments

- The Panel encourages as much clearance as possible
- The proposed spacing for parking and clearance between the LRV and the parking lane appear adequate
- Proper winter maintenance programs will be necessary
- Strong consideration should be given to not allow parking for spaces adjacent to the first 3 LRV cars or be limited as to time of day



Question # 6- Panel Comments

- It's likely that passengers will wait on the street side of the parked cars rather than on the sidewalk
- Placement of the mountable curbs will need to ensure so that passengers do not disembark on the edge of the mountable curb
- Risk exposure for disembarking passengers can be mitigated by allowing mountable curb only in area of a forth car
- Give special attention to final curb design



Question # 7

Parking parallel to track on non-station areas of the Mall may create blind spots for the Operators as pedestrians may pop out from between parked cars. Any experience with this? What setback is desirable?



Question # 7- Panel Comments

- See comments to Question # 6 ..
- When the parking spaces are marked., consider demarcation to indicate spaces for pedestrian movement between the parked cars .

Question # 8

No crossovers for emergencies in case of blockage on track. Additionally, when maintenance work (cracked rail or rail grinding) needs to be accomplished on the tracks or on the pavement, no work-around would be possible. Best headways that can be accomplished without an additional crossover is 20 minutes. What is reasonable spacing between crossovers? Is a manual emergency crossover realistic?



Question # 8- Panel Comments

- A manual crossover is a very reasonable solution. See earlier comments.



Question # 9

As the Yard and Shop are at the end of line where the project will take place, getting items like long strings of rail up the Mall and into the underground is a requirement. Any experience with this situation?



Question # 9- Panel Comments

- UTA's extension projects used this procedure. UTA will provide procedures they used.
- Overnight shutdowns will not be a rare occurrence..
- Acquire any needed MOU's in advance



Question # 10

Schedule variation may make coordination of connecting bus routes very difficult if not impossible. Some suburban routes have long headways and if the train delay results in a loss-connection with the bus, passenger would have to wait a long time for the next bus. Any work-a-rounds for this? Ways of holding buses if trains delayed? Automatic system? Radio?



Question # 10- Panel Comments

- There needs to be an integrated communication between bus and rail operations centers..
- The proposed digital signage will be helpful for passengers
- Bus drivers will need to be alerted through control and /or printed running board instructions
- A schedule buffer needs to be included to accommodate the travel time variability in the downtown core.



Question # 11

Potential for cars to follow trains into the underground may increase as traffic increases. Consideration being given to having a barrier come down behind the train to help prevent this. Any experience with barriers to prevent automobile traffic from following trains down into restricted right-of-ways? FTA would like some device that is crash worthy from a terrorist point of view

Question # 11- Panel Comments

- To the Panel's knowledge, no such applications currently exist for LRT approaches into tunnels.
- Possible solutions can include;
 - Road markings
 - Signage
 - Removal of a 4-6 foot section of concrete at the portal
 - Use of gate arm applications used in Calgary for restricted bus lanes



Question # 12

Any experience with mountable curbs.
Tripping accidents? Any ADA issues
with mountable curbs?



Question # 12- Panel Comments

➤ See prior comments

▪



Question # 13

Is there any potential safety issue with bike lane in track bed between Portal and Chippewa Street. What is experience with bikes on embedded tracks?



Question # 13- Panel Comments

- Combining bicycle and rail travel creates an increased risk exposure. Experiences of other LRT systems would encourage not mixing the two modes
- Consider a bike lane on a parallel street

Question # 14

Consideration being given to moving the terminus crossover downstream of the revenue system rather than upstream. In other words, the car would pull into the terminus station, drop off the last passengers, go through the crossover (in this case south of Erie Canal Harbor Station), change ends (no between car doors), do system check per the rules, pull forward and stop again at the outbound station to pickup outbound passengers, thus completing terminal operations. Nine minutes are built into the current schedule. We would be interested in knowing the operational experience of others as it relates to this type of operation. What kind of timing can be expected under this scenario?



Question # 14 Panel Comments

- See prior comments.



Other Panel Observations

- At the point of southbound traffic blend at the LRT portal, consider the use of standard traffic control lights
- Given the current state of the concrete track bed, consider replacing the track bed during construction. This will minimize more significant impact and costs rather than doing at a later time
- Also give consideration to replacement of the rail.
- The Panel recognizes that the Project will create an opportunity for installing a more “maintainable “ infrastructure